

Proposal:250124

Let Date:October 22, 2026

Call Order:215

J/P Num:35802(04)

Proj. Num:STP-214B(177)AG

Counties:CLEVELAND

Description:GRADE, DRAIN AND SURFACE

CITY STREET (EASTERN AVENUE): FROM SE 4TH STREET,
EXTEND NORTH IN MOORE.

PROJECT LENGTH = 0.818 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	1,737.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	324.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	100.000	LF
0060 221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	24.000	EA
0070 230(A)7200	SOLID SLAB SODDING	2,484.000	SY
0080 231(A)8200	TREES	92.000	EA
0090 231(B)8300	SHRUBS	112.000	EA
0100 231(C)8400	VINES/GRND COVERS	1,634.000	EA
0110 233(A)0200	VEGETATIVE MULCHING	0.500	AC
0120 241 3100	MOWING	2.100	AC
0130 303(A)1200	AGGREGATE BASE TYPE A	427.000	CY
0140 307(K)4200	STABILIZED SUBGRADE	2,232.000	SY
0150 317 7100	CEMENT TREATED BASE	2,232.000	SY
0160 325 0100	SEPARATOR FABRIC	2,464.000	SY
0170 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	250.000	TON
0180 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,863.000	SY
0190 414(G)5800	P.C. CONCRETE FOR PAVEMENT	468.000	CY
0200 509(D)0500	CLASS C CONCRETE	100.000	CY
0210 510(A)1230	BLOCK RETAINING WALL & CAP	166.000	SF
0220 609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	4,012.000	LF
0230 610(A)5200	4" CONCRETE SIDEWALK	4,533.000	SY
0240 610(A)5240	4" DECORATIVE CONCRETE SIDEWALK	73.000	SY
0250 610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	2,562.000	SY
0260 610(E)5610	(PL) CONCRETE PAVERS	228.000	SF
0270 610(I)6000	TACTILE WARNING DEVICE-NEW	253.000	SF
0280 610(J)6100	(PL) STAMPED CONCRETE FINISH	4,354.000	SY
0290 611(A)7210	MANHOLE (4' DIA.)	3.000	EA
0300 611(A)7230	MANHOLE (8' DIA.)	2.000	EA
0310 611(G)7786	INLET CI DES. 3 (STD)	1.000	EA
0320 611(G)7790	INLET CI DES. 3 (B)	1.000	EA
0330 613(A)5208	18" R.C.PIPES CLASS III	56.000	LF
0340 613(A)5224	36" R.C.PIPES CLASS III	4.000	LF
0350 613(B)5528	36" CORR. GALV. STEEL PIPE	100.000	LF
0360 616 2110	(PL) IRRIGATION SYSTEM	1.000	LSUM
0370 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0380 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	270.000	SY
0390 619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	2,564.000	SY
0400 619(B)6400	REMOVAL OF CURB	1,276.000	LF
0410 619(B)6404	REMOVAL OF SIDEWALK	2,509.000	SY
0420 626(A)5200	MONUMENTS	1.000	EA
0430 632 0100	(PL) SITESCAPING	1.000	LSUM
0440 850(D)1510	SPECIAL SIGNS	4.000	EA

Proposal:250124

Let Date:October 22, 2026

Call Order:215

J/P Num:35802(04)

Proj. Num:STP-214B(177)AG

Counties:CLEVELAND

Description:GRADE, DRAIN AND SURFACE

CITY STREET (EASTERN AVENUE): FROM SE 4TH STREET,
EXTEND NORTH IN MOORE.

PROJECT LENGTH = 0.818 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	SIGNING AND STRIPING		
0450	805(A)3252 (PL)REMOVAL OF EXISTING SIGNS	18.000	EA
0460	805(D)3500 (PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0470	805(D)3528 (PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
0480	850(A)1200 SHEET ALUMINUM SIGNS	114.000	SF
0490	851(C)2415 2" SQUARE TUBE POST	166.000	LF
0500	856(A)8207 (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	16,097.000	LF
0510	856(A)8219 (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,031.000	LF
0520	856(B)8307 (SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	27.000	EA
0530	857(B)9300 CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	10.000	EA
0540	857(C)9400 REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	879.000	LF
0550	857(C)9420 REMOVABLE PAVEMENT MARKING TAPE(ARROWS)	6.000	EA
0560	857(F)9700 PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,721.000	LF
0570	880(B)6300 CONSTRUCTION SIGNS 0 TO 6.25 SF	2,580.000	SD
0580	880(B)6310 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,430.000	SD
0590	880(C)6410 CONSTRUCTION BARRICADES(TYPE III)	7,050.000	SD
0600	880(D)6500 VERTICAL PANELS	26,370.000	SD
0610	880(E)6600 WARNING LIGHTS(TYPE A)	1,650.000	SD
0620	880(F)6700 DRUMS	4,200.000	SD
0630	882(A)8210 PORT.CHANGEABLE MESSAGE SIGN	840.000	SD

Proposal:250124

Let Date:October 22, 2026

Call Order:215

J/P Num:35802(04)

Proj. Num:STP-214B(177)AG

Counties:CLEVELAND

Description:GRADE, DRAIN AND SURFACE

CITY STREET (EASTERN AVENUE): FROM SE 4TH STREET,
EXTEND NORTH IN MOORE.

PROJECT LENGTH = 0.818 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003	TRAFFIC LIGHTING		
0640 802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	15.000	LF
0650 802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	29.000	LF
0660 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	110.000	LF
0670 802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	127.000	LF
0680 802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	33.000	LF
0690 802(B)0336	4" PVC SCH.40 PLASTIC CONDUIT BORED	299.000	LF
0700 802(B)0340	4" PVC SCH.40 PLASTIC CONDUIT TRENCHED	62.000	LF
0710 803(A)1220	PULL BOX(SIZE II)	4.000	EA
0720 804(A)2200	STRUCTURAL CONCRETE	15.370	CY
0730 804(B)2300	REINFORCING STEEL	2,067.800	LB
0740 805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0750 806(A)4324	POLE & 40' TS MST.ARM(G.STL.)	1.000	EA
0760 806(A)4332	POLE & 50' TS MST.ARM(G.STL.)	1.000	EA
0770 806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0780 806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	7.000	EA
0790 810(A)8200	SERVICE POLE	1.000	EA
0800 811 9120	1/C NO.6 ELECT.COND.	15.000	LF
0810 825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0820 828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0830 830 2100	PEDESTRIAN PUSH BUTTON	12.000	EA
0840 831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	12.000	EA
0850 831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
0860 831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	5.000	EA
0870 833 5100	BACKPLATE	13.000	EA
0880 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	934.000	LF
0890 834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	300.000	LF
0900 834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	595.000	LF
0910 834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,686.000	LF
0920 840(B)0300	E.P.S. OPTICAL DETECTOR	4.000	EA
0930 840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	783.000	LF
0940 840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	4.000	EA
0950 850(A)1200	SHEET ALUMINUM SIGNS	12.000	SF
0960 850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	103.500	SF
0004	STAKING		
0970 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION		
0980 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0990 641 2110	MOBILIZATION	1.000	LSUM