Proposal: 250136 **Let Date:** January 21, 2027 **Call Order:** 680
J/P Num: 35927(04) **Proj. Num:** STPG-255F(567)AG
Counties: OKLAHOMA
Description: TRAFFIC SIGNALS
CITY STREETS (SOUTH AIR DEPOT BOULEVARD/
SE 15TH STREET): AT MULTIPLE INTERSECTIONS IN MIDWEST CITY.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(H)2900	EARTHWORK	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	120.000	LF
0030	221(C)2400	TEMPORARY SEDIMENT FILTER	3.000	EA
0040	230(A)7200	SOLID SLAB SODDING	160.000	SY
0050	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	13.000	SY
0060	414(G)5800	P.C. CONCRETE FOR PAVEMENT	4.000	CY
0070	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	90.000	LF
0080	609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	100.000	LF
0090	610(A)5200	4" CONCRETE SIDEWALK	165.000	SY
0100	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	435.000	SY
0110	610(I)6000	TACTILE WARNING DEVICE-NEW	200.000	SF
0120	612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0130	612(E)3600	VALVE BOXES ADJUST TO GRADE	1.000	EA
0140	612(F)3700	METER BOXES ADJUST TO GRADE	1.000	EA
0150	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0160	619(B)6356	REMOVAL OF CURB AND GUTTER	90.000	LF
0170	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	438.000	SY
0180	619(B)6404	REMOVAL OF SIDEWALK	120.000	SY

Proposal:250136 **Let Date:**January 21, 2027 **Call Order:**680
J/P Num:35927(04) **Proj. Num:**STPG-255F(567)AG
Counties:OKLAHOMA
Description:TRAFFIC SIGNALS
CITY STREETS (SOUTH AIR DEPOT BOULEVARD/
SE 15TH STREET): AT MULTIPLE INTERSECTIONS IN MIDWEST CITY.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0002	TRAFFIC			
0190	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	40.000	LF
0200	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	335.000	LF
0210	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	50.000	LF
0220	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	75.000	LF
0230	803(A)1210	PULL BOX(SIZE I)	1.000	EA
0240	803(A)1220	PULL BOX(SIZE II)	14.000	EA
0250	804(A)2200	STRUCTURAL CONCRETE	13.000	CY
0260	804(B)2300	REINFORCING STEEL	1,525.000	LB
0270	805(A)3208	REMOVAL OF PULL BOX	16.000	EA
0280	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0290	805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0300	805(D)3504	(PL)REMOVE & RESET LIGHT POLE	1.000	EA
0310	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0320	805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	2.000	EA
0330	806(A)4320	POLE & 35' TS MST.ARM(G.STL.)	1.000	EA
0340	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	23.000	EA
0350	806(B)4412	12' MTG.HT.TS PED.POLE(G.STL.)	1.000	EA
0360	811 9130	1/C NO.10 ELECT.COND.	80.000	LF
0370	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	3.000	EA
0380	825(A)8200	SIGNAL SYSTEM CONTROLLER UPGRADE	1.000	EA
0390	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0400	830 2100	PEDESTRIAN PUSH BUTTON	42.000	EA
0410	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	40.000	EA
0420	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	2.000	EA
0430	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	6.000	EA
0440	833 5100	BACKPLATE	44.000	EA
0450	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	380.000	LF
0460	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	6,200.000	LF
0470	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,050.000	LF
0480	834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,180.000	LF
0490	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	350.000	LF
0500	840(B)0300	E.P.S. OPTICAL DETECTOR	5.000	EA
0510	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,000.000	LF
0520	840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	5.000	EA
0530	850(A)1200	SHEET ALUMINUM SIGNS	18.000	SF
0540	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	53.000	SF
0550	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	160.000	LF
0560	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	1,952.000	LF
0570	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	332.000	LF
0580	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	16.000	EA
0590	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	2,624.000	LF
0600	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	19.000	EA
0610	890 1110	(PL)TRAFFIC ITEMS	5.000	EA

Proposal:250136 **Let Date:**January 21, 2027 **Call Order:**680
J/P Num:35927(04) **Proj. Num:**STPG-255F(567)AG
Counties:OKLAHOMA
Description:TRAFFIC SIGNALS
CITY STREETS (SOUTH AIR DEPOT BOULEVARD/
SE 15TH STREET): AT MULTIPLE INTERSECTIONS IN MIDWEST CITY.
PROJECT LENGTH = 0.00 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC CONTROL			
0620	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,570.000	SD
0630	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,520.000	SD
0640	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,060.000	SD
0650	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,530.000	SD
0660	880(E)6607	WARNING LIGHTS(TYPE B)	3,060.000	SD
0670	880(F)6700	DRUMS	11,070.000	SD
0680	880(G)6805	CHANNELIZER CONES	5,040.000	SD
0004	STAKING			
0690	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION			
0700	641 2110	MOBILIZATION	1.000	LSUM