

Proposal:260187

Let Date:October 22, 2026

Call Order:243

J/P Num:30444(12)

Proj. Num:STP-255E(764)PM

Counties:OKLAHOMA

Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL PATH)

PEDESTRIAN BRIDGE (S LINCOLN BLVD):

OVER THE OKLAHOMA RIVER, IN THE CITY OF OKLAHOMA CITY.

PROJECT LENGTH = 0.266 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	508.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	5,099.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	2,305.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	28.000	LF
0070 221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0080 230(A)7200	SOLID SLAB SODDING	3,923.000	SY
0090 233(A)0200	VEGETATIVE MULCHING	0.730	AC
0100 241 3100	MOWING	1.460	AC
0110 303(A)1200	AGGREGATE BASE TYPE A	448.000	CY
0120 307(K)4200	STABILIZED SUBGRADE	260.000	SY
0130 407(B)7300	TACK COAT	25.000	GAL
0140 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	73.000	TON
0150 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	29.000	TON
0160 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	2,329.000	SY
0170 414(G)5800	P.C. CONCRETE FOR PAVEMENT	399.000	CY
0180 502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0190 504(F)5600	HANDRAILING	378.000	LF
0200 504(F)5610	DECORATIVE HANDRAILING	1,513.000	LF
0210 509(D)0500	CLASS C CONCRETE	81.000	CY
0220 510(A)1200	RETAINING WALL	127.000	SY
0230 510(A)1230	BLOCK RETAINING WALL & CAP	235.000	SF
0240 510(D)1500	GRAFFITI TREATMENT	11,980.000	SF
0250 510(D)1510	MSE RETAINING WALL	1,591.000	SY
0260 601(A)1100	TYPE I PLAIN RIPRAP	542.000	TON
0270 602(C)2410	FILTER FABRIC	222.000	SY
0280 609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	187.000	LF
0290 610(I)6000	TACTILE WARNING DEVICE-NEW	24.000	SF
0300 613(A)5216	24" R.C.PIPES CLASS III	30.000	LF
0310 613(H)6200	6" PERFORATED PIPE UNDERDRAIN ROUND	200.000	LF
0320 613(I)6305	6" NON-PERF.PIPES UNDERDRAIN RND.	50.000	LF
0330 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0340 613(S)7700	STANDARD BEDDING MATERIAL, CLASS B	12.000	CY
0350 613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	18.000	CY
0360 613(V)8000	TRENCH EXCAVATION	28.000	CY
0370 616(M)3705	WATER VALVE RISER ADJUST TO GRADE	1.000	EA
0380 616(P)4148	8" HDPE PIPE	95.000	LF
0390 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	151.000	SY
0410 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	129.000	SY
0420 619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	94.000	SY
0430 619(B)6404	REMOVAL OF SIDEWALK	672.000	SY
0440 619(B)6452	REMOVAL OF EXISTING RETAINING WALL	62.000	LF
0445 619(B)6504	REMOVE AND RELOCATE UTILITIES	1.000	LSUM
0450 619(C)6600	SAWING PAVEMENT	492.000	LF

Proposal:260187

Let Date:October 22, 2026

Call Order:243

J/P Num:30444(12)

Proj. Num:STP-255E(764)PM

Counties:OKLAHOMA

Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL PATH)

PEDESTRIAN BRIDGE (S LINCOLN BLVD):

OVER THE OKLAHOMA RIVER, IN THE CITY OF OKLAHOMA CITY.

PROJECT LENGTH = 0.266 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0460 631(A)9210	(SP)REMOVABLE BOLLARD	1.000	EA
0002	BRIDGE 'A' - BASE BID		
0470 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	225.000	CY
0480 501(F)1700	GRANULAR BACKFILL	757.000	CY
0490 504(A)5200	APPROACH SLAB	105.000	SY
0500 504(E)5500	CONCRETE PARAPET	1,326.000	LF
0510 504(F)5610	DECORATIVE HANDRAILING	1,326.000	LF
0520 506(A)7220	STRUCTURAL STEEL M270 GRADE 50 (PAINTED)	663,980.000	LB
0530 507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
0540 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	8.000	EA
0550 509(A)0210	CLASS AA CONCRETE	526.500	CY
0560 509(B)0320	CLASS A CONCRETE	216.200	CY
0570 510(D)1500	GRAFFITI TREATMENT	1,512.000	SF
0580 510(D)1510	MSE RETAINING WALL	204.200	SY
0590 511(B)2310	EPOXY COATED REINFORCING STEEL	192,790.000	LB
0600 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	1,527.000	SY
0610 516(A)8230	DRILLED SHAFTS 48" DIAMETER	274.000	LF
0620 516(A)8240	DRILLED SHAFTS 60" DIAMETER	435.000	LF
0630 516(C)8400	CROSSHOLE SONIC LOGGING	10.000	EA
0640 517 9110	ELASTOMERIC COATING	1,086.000	SF
0650 518(B)0300	SEALED EXPANSION JOINTS	64.000	LF
0660 523(A)3200	SEALER CRACK PREPARATION	192.000	LF
0670 523(B)3300	SEALER RESIN	2.200	GAL
0003	BRIDGE 'A' - ADD ALTERNATE NO. 1		
0860 531 6301	(PL) AESTHETIC ARCH (STRUCTURAL)	1.000	LSUM
0865 531 6302	(PL) AESTHETIC ARCH (ELECTRICAL)	1.000	LSUM
0004	TRAFFIC SIGNING AND STRIPING		
0690 804(A)2200	STRUCTURAL CONCRETE	1.000	CY
0700 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0710 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0720 850(A)1200	SHEET ALUMINUM SIGNS	61.000	SF
0730 851(B)2305	2"@3.65 GALV.STL.PIPE POST	24.000	LF
0740 851(C)2415	2" SQUARE TUBE POST	7.000	LF
0750 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	1,155.000	LF
0760 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	21.000	LF
0005	TRAFFIC CONTROL		
0770 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	5,265.000	SD
0780 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,265.000	SD
0790 880(E)6600	WARNING LIGHTS(TYPE A)	10,530.000	SD
0800 880(F)6700	DRUMS	6,435.000	SD
0006	LIGHTING		
0810 809 7110	ENHANCEMENT LIGHTING (COMPLETE)	1.000	LSUM

Proposal:260187

Let Date:October 22, 2026

Call Order:243

J/P Num:30444(12)

Proj. Num:STP-255E(764)PM

Counties:OKLAHOMA

Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL PATH)

PEDESTRIAN BRIDGE (S LINCOLN BLVD):

OVER THE OKLAHOMA RIVER, IN THE CITY OF OKLAHOMA CITY.

PROJECT LENGTH = 0.266 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0007	STAKING		
0820 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION		
0830 640(A)1210	FIELD OFFICE	1.000	EA
0840 641 2110	MOBILIZATION	1.000	LSUM