

Proposal:260234
J/P Num:28809(04)
Counties:LEFLORE

Let Date:October 15, 2026
Proj. Num:SRS-140E(217)ST

Call Order:120

Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL TRAIL)
CITY STREETS (GRADY AVE/MCKENNA ST/CLAYTON AVE):
AT MULTIPLE LOCATIONS IN THE CITY OF POTEAU.
PROJECT LENGTH = 1.292 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(B)1300	SELECTIVE CLEARING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	3,251.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	487.000	CY
0040 221(B)2300	TEMPORARY SILT FENCE	7,088.000	LF
0050 221(E)2600	TEMPORARY SILT DIKE	203.000	LF
0060 230(A)7200	SOLID SLAB SODDING	5,124.100	SY
0070 303(A)1200	AGGREGATE BASE TYPE A	1,063.600	CY
0080 310(B)5300	SUBGRADE, METHOD B	6,563.800	SY
0090 325 0100	SEPARATOR FABRIC	500.000	SY
0100 326(B)1300	GEOGRID REINFORCEMENT	500.000	SY
0110 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	665.900	TON
0120 414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	24.000	SY
0130 414(F)5700	PARTIAL DEPTH P.C.C. PATCH (PLACEMENT)	11.900	SY
0140 414(G)5800	P.C. CONCRETE FOR PAVEMENT	6.200	CY
0150 510(A)1230	BLOCK RETAINING WALL & CAP	102.800	SF
0160 510(C)1440	SLOPE WALL (5")	53.200	SY
0170 609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	14.000	LF
0180 610(A)5200	4" CONCRETE SIDEWALK	57.500	SY
0190 610(A)5210	5" CONCRETE SIDEWALK	606.900	SY
0200 610(I)6000	TACTILE WARNING DEVICE-NEW	300.000	SF
0210 611(L)1600	JUNCTION BOXES	48.900	CF
0220 612(A)3200	MANHOLES ADJUST TO GRADE	3.000	EA
0230 613(A)5216	24" R.C.PIPE CLASS III	6.000	LF
0240 613(A)5224	36" R.C.PIPE CLASS III	4.000	LF
0250 613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	30.000	LF
0260 613(B)5536	48" CORR. GALV. STEEL PIPE	30.000	LF
0270 613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0280 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0290 613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0300 613(L)6736	48" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0310 613(P)7400	18" GALV. STEEL CULVERT END SEC. RND.	2.000	EA
0320 616(P)4160	18" HDPE PIPE	22.600	LF
0330 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0340 619(B)6300	REMOVAL OF HEADWALL	2.000	EA
0350 619(B)6356	REMOVAL OF CURB AND GUTTER	14.000	LF
0360 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	41.600	SY
0370 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	11.900	SY
0380 619(B)6440	REMOVAL OF EXISTING PIPE	24.500	LF
0390 624 3100	(PL) ORNAMENTAL FENCE	950.000	LF
0400 631(A)9210	(SP)REMOVABLE BOLLARD	13.000	EA

Proposal:260234
J/P Num:28809(04)
Counties:LEFLORE

Let Date:October 15, 2026
Proj. Num:SRS-140E(217)ST

Call Order:120

Description:PEDESTRIAN IMPROVEMENTS (MULTIMODAL TRAIL)
CITY STREETS (GRADY AVE/MCKENNA ST/CLAYTON AVE):
AT MULTIPLE LOCATIONS IN THE CITY OF POTEAU.
PROJECT LENGTH = 1.292 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002 TRAFFIC			
0410 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0420 850(A)1200	SHEET ALUMINUM SIGNS	300.500	SF
0430 851(C)2415	2" SQUARE TUBE POST	636.000	LF
0440 855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	1,439.900	LF
0450 855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	290.000	LF
0460 855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	20.000	EA
0470 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	495.000	SD
0480 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,350.000	SD
0490 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	30.000	SD
0500 880(E)6600	WARNING LIGHTS(TYPE A)	975.000	SD
0510 880(F)6700	DRUMS	975.000	SD
0003 STAKING			
0520 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004 CONSTRUCTION			
0530 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0540 641 2100	MOBILIZATION	1.000	LSUM