

Proposal:260248
J/P Num:32701(04)
Counties:CREEK

Let Date:October 15, 2026
Proj. Num:STP-219B(122)PM

Call Order:110

Description:RETAINING AND SOUND WALLS

SH-117: FROM 3.8 MILES WEST OF THE US-75 JUNCTION,
EXTEND EAST IN SAPULPA.
PROJECT LENGTH= 0.239 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	1,719.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 221(B)2300	TEMPORARY SILT FENCE	664.000	LF
0050 221(G)2800	TEMPORARY FIBER LOG	84.000	LF
0060 230(A)7200	SOLID SLAB SODDING	5,234.000	SY
0070 233(A)0200	VEGETATIVE MULCHING	1.080	AC
0080 241 3100	MOWING	3.070	AC
0090 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	10.000	TON
0100 407(B)7300	TACK COAT	1,159.000	GAL
0110 411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	1,360.000	TON
0120 412 3100	COLD MILLING PAVEMENT	12,416.000	SY
0130 504(E)5500	CONCRETE PARAPET	2,111.000	LF
0140 509(A)0200	CLASS AA CONCRETE	1,189.000	CY
0150 509(D)0500	CLASS C CONCRETE	18.000	CY
0160 510(C)1440	SLOPE WALL (5")	10,401.000	SY
0170 511(B)2300	EPOXY COATED REINFORCING STEEL	95,790.000	LB
0180 609(B)4330	1'-8" COMB.CRB.& GUT.(6" BARRIER)	2,367.000	LF
0190 611(I)1000	RPLC INLT FRM&GRT(SSIF-FRM,CIG-GRT-VG-F)	6.000	EA
0200 611(M)1700	REPLACEMENT OF CAST IRON HOOD	16.000	EA
0210 612(C)3400	INLET ADJUST TO GRADE	3.000	EA
0220 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0230 619(B)6352	REMOVAL OF FENCE	581.000	LF
0240 619(B)6356	REMOVAL OF CURB AND GUTTER	2,531.000	LF
0250 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	291.000	SY
0260 619(B)6396	REMOVAL OF GUARDRAIL	972.000	LF
0270 619(B)6404	REMOVAL OF SIDEWALK	1,087.000	SY
0280 619(B)6408	REMOVAL OF CONCRETE SLOPE PROTECTION	7,318.000	SY
0290 619(C)6600	SAWING PAVEMENT	3,544.000	LF
0300 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,080.000	LF
0310 624(E)3625	FENCE-STYLE CLF (6'HIGH, CLASS B)	974.000	LF
0320 629(A)7200	MAILBOX INSTALLATION-SINGLE	3.000	EA
0330 629(B)7300	MAILBOX INSTALLATION-MULTIPLE	1.000	EA
0340 629(C)7400	REMOVAL OF MAILBOX INSTALLATION	5.000	EA
0350 629(E)7600	MAILBOX	5.000	EA
0360 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	22.000	EA
0002 WALL A1			
0370 501(G)1800	CLSM BACKFILL	200.000	CY
0380 504(F)5600	HANDRAILING	1,028.400	LF
0390 509(D)0510	CLASS C CONCRETE	57.300	CY
0400 510(A)1210	RETAINING WALL	1,806.300	SY
0410 510(D)1500	GRAFFITI TREATMENT	16,256.600	SF
0420 514(A)5200	PILES, FURNISHED	3,486.000	LF
0430 514(K)6200	(PL)PILOT HOLES	1,523.300	LF
0440 542 9101	(PL)INSTALLATION OF BRIDGE ITEMS	77.000	EA

Proposal:260248
J/P Num:32701(04)
Counties:CREEK

Let Date:October 15, 2026
Proj. Num:STP-219B(122)PM

Call Order:110

Description:RETAINING AND SOUND WALLS

SH-117: FROM 3.8 MILES WEST OF THE US-75 JUNCTION,
 EXTEND EAST IN SAPULPA.

PROJECT LENGTH= 0.239 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 WALL A2			
0450 504(F)5600	HANDRAILING	441.300	LF
0460 509(D)0510	CLASS C CONCRETE	25.000	CY
0470 510(D)1510	MSE RETAINING WALL	651.900	SY
0004 WALL B			
0480 501(G)1800	CLSM BACKFILL	200.000	CY
0490 504(F)5600	HANDRAILING	980.000	LF
0500 509(D)0510	CLASS C CONCRETE	54.600	CY
0510 510(A)1210	RETAINING WALL	1,616.500	SY
0520 510(D)1500	GRAFFITI TREATMENT	14,548.800	SF
0530 514(A)5200	PILES, FURNISHED	2,758.000	LF
0540 514(K)6200	(PL)PILOT HOLES	1,006.500	LF
0550 542 9101	(PL)INSTALLATION OF BRIDGE ITEMS	92.000	EA
0005 TRAFFIC CONTROL			
0560 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	5,060.000	LF
0570 857(E)9610	(PL)C/L CONST.ZONE PAV.MARKERS(YELLOW)	20.000	EA
0580 857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	1,012.000	EA
0590 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	3,200.000	LF
0600 857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	13.000	EA
0610 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,550.000	LF
0620 880(A)6220	ARROW DISPLAY(TYPE C)	1,680.000	SD
0630 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	27,720.000	SD
0640 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,920.000	SD
0650 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,560.000	SD
0660 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	11,760.000	SD
0670 880(E)6607	WARNING LIGHTS(TYPE B)	25,200.000	SD
0680 880(E)6616	WARNING LIGHTS(TYPE D)	47,880.000	SD
0690 880(F)6700	DRUMS	47,880.000	SD
0700 880(G)6805	CHANNELIZER CONES	126,000.000	SD
0710 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	868.000	SD
0006 SIGNING AND STRIPING			
0720 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0730 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	4,800.000	LF
0740 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	6.000	EA
0007 STAKING			
0750 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008 CONSTRUCTION			
0760 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0770 641 2110	MOBILIZATION	1.000	LSUM