

Proposal:260249**Let Date:**October 15, 2026**Call Order:**115**J/P Num:**36918(04)**Proj. Num:**HSIPG-221F(071)TR**Counties:**CRAIG, DELAWARE, MAYES, OSAGE, PAWNEE, ROGERS,
TULSA**Description:**SAFETY IMPROVEMENT (GUARDRAIL)

SH-2/SH-28/SH-85A/SH-20/SH-127/SH-18/SH-125/SH-82/SH-10/US-64:

AT MULTIPLE LOCATIONS IN DISTRICT VIII.

PROJECT LENGTH = 2.255 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	1,501.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	665.000	CY
0040 205(A)6210	TYPE A-SALVAGED TOPSOIL	2,080.000	CY
0050 221(B)2300	TEMPORARY SILT FENCE	14,087.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	1,638.000	LF
0070 230(A)7200	SOLID SLAB SODDING	14,915.000	SY
0080 233(E)0600	(SP) HYDROMULCH	14,915.000	SY
0090 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	5,401.000	TON
0100 407(B)7300	TACK COAT	444.000	GAL
0110 408 8100	PRIME COAT	1,431.000	GAL
0120 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,311.000	TON
0130 501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	17.000	CY
0140 509(B)0300	CLASS A CONCRETE	59.000	CY
0150 511(A)2200	REINFORCING STEEL	3,013.000	LB
0160 613(A)5216	24" R.C.PIPE CLASS III	6.000	LF
0170 613(B)5504	15" CORR. GALV. STEEL PIPE	12.000	LF
0180 613(L)6704	15" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0190 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0200 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0210 619(B)6396	REMOVAL OF GUARDRAIL	100.000	LF
0220 619(C)6600	SAWING PAVEMENT	11,276.000	LF
0230 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	7,312.500	LF
0240 623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
0250 623(G)1820	GUARDRAIL END TREATMENT (31")	29.000	EA
0260 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
0270 629(D)7500	REMOVE AND RESET MAILBOX	2.000	EA
0002	BRIDGE		
0280 504(E)5520	42" F-SHAPED PARAPET	60.000	LF
0290 619(B)6476	REMOVAL OF EXISTING PARAPET	23.000	LF
0003	TRAFFIC SIGNING		
0300 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	4.000	EA
0310 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	35.000	EA
0320 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	6.000	EA
0330 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	178.000	EA
0340 870(C)1300	SAND FILLED IMPACT ATTEN.MODULE REMOVAL	1.000	LSUM
0350 871(A)2200	IMPACT ATTENUATOR	2.000	EA

Proposal:260249

Let Date:October 15, 2026

Call Order:115

J/P Num:36918(04)

Proj. Num:HSIPG-221F(071)TR

Counties:CRAIG, DELAWARE, MAYES, OSAGE, PAWNEE, ROGERS,
TULSA

Description:SAFETY IMPROVEMENT (GUARDRAIL)

SH-2/SH-28/SH-85A/SH-20/SH-127/SH-18/SH-125/SH-82/SH-10/US-64:

AT MULTIPLE LOCATIONS IN DISTRICT VIII.

PROJECT LENGTH = 2.255 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004	TRAFFIC CONTROL		
0360 876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	480.000	SD
0370 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	250.000	LF
0380 880(A)6220	ARROW DISPLAY(TYPE C)	30.000	SD
0390 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	4,860.000	SD
0400 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,480.000	SD
0410 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,900.000	SD
0420 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,280.000	SD
0430 880(E)6600	WARNING LIGHTS(TYPE A)	6,600.000	SD
0440 880(E)6616	WARNING LIGHTS(TYPE D)	13,920.000	SD
0450 880(F)6700	DRUMS	13,920.000	SD
0460 880(I)7000	FLAGGER	450.000	SD
0470 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	640.000	HOURL
0480 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD
0005	STAKING		
0490 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION		
0500 641 2110	MOBILIZATION	1.000	LSUM