

Proposal:260252**Let Date:**October 15, 2026**Call Order:**130**J/P Num:**31274(04)**Proj. Num:**CIRB-248C(068)RB**Counties:**MARSHALL**Description:**GRADE, DRAIN AND SURFACE

COUNTY ROAD (TEXOMA PARK ROAD): FROM 1.0 MILE
SOUTH OF THE US-70 INTERSECTION, EXTEND SOUTH
NEAR LAKE TEXOMA STATE PARK.
PROJECT LENGTH = 2.092 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	9,535.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	1,027.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	8,687.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	616.000	LF
0070 221(G)2800	TEMPORARY FIBER LOG	324.000	LF
0080 230(A)7200	SOLID SLAB SODDING	29,240.000	SY
0090 233(A)0200	VEGETATIVE MULCHING	6.050	AC
0100 241 3100	MOWING	12.100	AC
0110 307(K)4200	STABILIZED SUBGRADE	21,112.000	SY
0120 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,189.000	TON
0130 407(A)7200	FOG SEAL	1,394.000	GAL
0140 407(B)7300	TACK COAT	2,734.000	GAL
0150 408 8100	PRIME COAT	7,434.000	GAL
0160 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	6,142.000	TON
0170 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	4,007.000	TON
0180 412 3100	COLD MILLING PAVEMENT	16,370.000	SY
0190 509(D)0500	CLASS C CONCRETE	167.000	CY
0200 601(A)1100	TYPE I PLAIN RIPRAP	28.000	TON
0210 609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	5,940.000	LF
0220 610(B)5310	6" CONCRETE DRIVEWAY	891.000	SY
0230 611(G)9004	INLET CDI RCP DES. 2	3.000	EA
0240 611(G)9008	INLET CDI RCP DES. 3	2.000	EA
0250 611(G)9020	INLET CDI RCP DES. 6	1.000	EA
0260 611(H)0684	ADD'L DEPTH IN INLET CDI RCP DES. 2	7.110	VF
0270 611(H)0688	ADD'L DEPTH IN INLET CDI RCP DES. 3	3.260	VF
0280 611(H)0700	ADD'L DEPTH IN INLET CDI RCP DES. 6	2.280	VF
0290 613(A)5208	18" R.C.PIPE CLASS III	76.000	LF
0300 613(A)5216	24" R.C.PIPE CLASS III	158.000	LF
0310 613(A)5220	30" R.C.PIPE CLASS III	90.000	LF
0320 613(A)5232	48" R.C.PIPE CLASS III	56.000	LF
0330 613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	44.000	LF
0340 613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	348.000	LF
0350 613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	160.000	LF
0360 613(A)5378	58" X 36" R.C.PIPE ARCH CLASS A-III	40.000	LF
0370 613(E)5965	15" CORRUGATED POLYPROPYLENE PIPE	1,266.000	LF
0380 613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	4.000	EA
0390 613(L)6664	58" X 36" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0400 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0410 613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0420 613(L)6736	48" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0430 613(M)6960	TYPE A4 CULVERT END TREATMENT	92.000	EA
0440 613(M)6964	TYPE B4 CULVERT END TREATMENT	7.000	EA
0450 613(M)6968	TYPE C4 CULVERT END TREATMENT	1.000	EA

Proposal:260252**Let Date:**October 15, 2026**Call Order:**130**J/P Num:**31274(04)**Proj. Num:**CIRB-248C(068)RB**Counties:**MARSHALL**Description:**GRADE, DRAIN AND SURFACE

COUNTY ROAD (TEXOMA PARK ROAD): FROM 1.0 MILE
SOUTH OF THE US-70 INTERSECTION, EXTEND SOUTH
NEAR LAKE TEXOMA STATE PARK.
PROJECT LENGTH = 2.092 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0460 616(P)4161	18" CORRUGATED HDPE PIPE	510.000	LF
0470 616(P)4164	24" HDPE PIPE	56.000	LF
0480 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0490 619(B)6352	REMOVAL OF FENCE	1,061.000	LF
0500 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	9,559.000	SY
0510 619(B)6440	REMOVAL OF EXISTING PIPE	2,150.000	LF
0520 619(C)6600	SAWING PAVEMENT	16,370.000	LF
0530 624(A)3200	FENCE-STYLE WWF	215.000	LF
0540 624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	252.000	LF
0550 624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	108.000	LF
0560 629(A)7200	MAILBOX INSTALLATION-SINGLE	34.000	EA
0570 629(B)7300	MAILBOX INSTALLATION-MULTIPLE	7.000	EA
0580 629(C)7400	REMOVAL OF MAILBOX INSTALLATION	49.000	EA
0590 629(E)7600	MAILBOX	49.000	EA
0002	TEMPORARY TRAFFIC		
0600 104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	30.000	DAY
0610 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,440.000	SD
0620 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	720.000	SD
0630 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,440.000	SD
0640 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,440.000	SD
0650 880(E)6600	WARNING LIGHTS(TYPE A)	4,320.000	SD
0003	PERMANENT TRAFFIC		
0660 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	23.000	EA
0670 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
0680 850(A)1200	SHEET ALUMINUM SIGNS	132.190	SF
0690 851(C)2415	2" SQUARE TUBE POST	350.000	LF
0700 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	44,240.000	LF
0710 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	24.000	LF
0004	STAKING		
0720 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION		
0730 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0740 641 2110	MOBILIZATION	1.000	LSUM