Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	216,729.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	56,116.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	33,971.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	38.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	749.000	LF
0080	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	29.000	EA
0090	230(A)7200	SOLID SLAB SODDING	186,911.000	SY
0100	233(A)0200	VEGETATIVE MULCHING	38.620	AC
0110	241 3100	MOWING	77.240	AC
0120	303(A)1200	AGGREGATE BASE TYPE A	24,076.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	117,653.000	SY
0140	326(C)1100	(SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	127,266.000	SY
0150	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	24,607.000	TON
0160	406 6100	OPEN GRADED FRICTION SURFACE COURSE	1,951.000	TON
0170	407(B)7300	TACK COAT	28,830.000	GAL
0180	408 8100	PRIME COAT	72,537.000	GAL
0190	409(A)9200	FABRIC REINFORCEMENT	8,246.000	SY
0200	409(B)9300	BITUMINOUS BINDER	1,650.000	GAL
0210	411(G)1800	RICH BOTTOM LAYER	12,007.000	TON
0220	411(L)2404	BMD, TYPE B3 (PG 64-22 OK)	38,118.000	TON
0230	411(L)2412	BMD, TYPE B3 (PG 76-28 OK)	5,645.000	TON
0240	411(L)2424	BMD, TYPE B4 (PG 64-22 OK)	6,979.000	TON
0250	411(L)2432	BMD, TYPE B4 (PG 76-28 OK)	6,262.000	TON
0260	412 3100	COLD MILLING PAVEMENT	38,769.000	SY
0270	414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	16,458.000	SY
0280	414(G)5800	P.C. CONCRETE FOR PAVEMENT	2,743.000	CY
0290	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	3,211.000	CY
0300	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0310	509(A)0200	CLASS AA CONCRETE	1,752.000	CY
0320	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	2.000	CY
0330	509(D)0500	CLASS C CONCRETE	1,105.000	CY
0340	510(D)1510	MSE RETAINING WALL	1,031.000	SY
0350	511(A)2200	REINFORCING STEEL	262,521.000	LB
0360	601(A)1100	TYPE I PLAIN RIPRAP	697.000	TON
0370	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	229.000	TON
0380	609(B)4375	2'-8" COMB.CRB.& GUT.(8" BARRIER)	11,133.000	LF
0390	610(B)5310	6" CONCRETE DRIVEWAY	2,120.000	SY
0400	611(A)7215	MANHOLE (5' DIA.)	15.000	EA
0410	611(A)7220	MANHOLE (6' DIA.)	13.000	EA
0420	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	3.000	VF
0430	611(B)7310	ADD'L.DEPTH IN MANHOLE (6' DIA.)	14.000	VF
0440	611(G)0350	INLET (SMD-TYPE 1)	23.000	EA
0450	611(G)0354	INLET (SMD-TYPE 2)	6.000	EA
0460	611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0470	611(G)7758	INLET CI DES. 2 (B)	18.000	EA

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0480	611(G)7766	INLET CI DES. 2 (D)	4.000	EA
0490	611(G)7770	INLET CI DES. 2 (2B)	1.000	EA
0500	611(G)7786	INLET CI DES. 3 (STD)	2.000	EA
0510	611(G)7798	INLET CI DES. 3 (2B)	2.000	EA
0520	611(G)7806	INLET CI DES. 3 (2D)	1.000	EA
0530	611(G)7930	INLET GPI TYPE 1 (DES. 1)	2.000	EA
0540	611(G)7966	INLET GPI TYPE 2 (DES. 10)	1.000	EA
0550	611(G)8028	INLET CDI RCB DES. 8	1.000	EA
0560	611(G)8040	INLET CDI RCB DES. 11	1.000	EA
0570	611(G)9012	INLET CDI RCP DES. 4	1.000	EA
0580	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	56.000	VF
0590	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	16.000	VF
0600	611(H)0470	ADD'L DEPTH IN INLET GPI TYPE 1	3.000	VF
0610	611(H)0548	ADD'L DEPTH IN INLET CDI RCB DES. 8	2.000	VF
0620	611(H)0560	ADD'L DEPTH IN INLET CDI RCB DES. 11	2.000	VF
0630	611(H)0692	ADD'L DEPTH IN INLET CDI RCP DES. 4	6.000	VF
0640	611(H)0980	ADD'L DEPTH IN INLET SMD TYPE 1	1.000	VF
0650	611(L)1600	JUNCTION BOXES	73.000	CF
0660	613(A)5208	18" R.C.PIPE CLASS III	122.000	LF
0670	613(A)5216	24" R.C.PIPE CLASS III	3,580.000	LF
0680	613(A)5220	30" R.C.PIPE CLASS III	1,094.000	LF
0690	613(A)5224	36" R.C.PIPE CLASS III	214.000	LF
0700	613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	66.000	LF
0710	613(B)5540	54" CORR. GALV. STEEL PIPE	124.000	LF
0720	613(B)5544	60" CORR. GALV. STEEL PIPE	227.000	LF
0730	613(B)5636	71" X 47" CORR. GALV. STEEL PIPE ARCH	198.000	LF
0740	613(H)6210	8" PERFORATED PIPE UNDERDRAIN ROUND	387.000	LF
0750	613(I)6315	8" NON-PERF.PIPE UNDERDRAIN RND.	129.000	LF
0760	613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	10,935.000	LF
0770	613(K)6500	EDGE DRAIN OUTLET LATERAL-NONPERFORATED	1,094.000	LF
0780	613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0790	613(M)6960	TYPE A4 CULVERT END TREATMENT	2.000	EA
0800	613(M)6964	TYPE B4 CULVERT END TREATMENT	1.000	EA
0810	613(M)7004	TYPE A6 CULVERT END TREATMENT	1.000	EA
0820	613(Q)7500	OUTLET LATERAL HEADWALL	39.000	EA
0830	616(P)4136	6" HDPE PIPE	150.000	LF
0840	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0850	619(B)6356	REMOVAL OF CURB AND GUTTER	546.000	LF
0860	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	16,458.000	SY
0870	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	46,418.000	SY
0880	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	793.000	SY
0890	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	4,028.000	SY
0900	619(B)6396	REMOVAL OF GUARDRAIL	2,444.000	LF
0910	619(B)6436	REMOVAL OF CONCRETE DITCH LINER	2,808.000	LF
0920	619(B)6464	REMOVAL OF 6" CONCRETE DIVIDING STRIP	20.000	SY
0930	619(C)6600	SAWING PAVEMENT	23,976.000	LF
0940	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	1,150.000	LF

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0950	623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	2.000	EA
0960	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0970	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	6.000	EA
0980	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	4,007.000	LF
0990	629(A)7200	MAILBOX INSTALLATION-SINGLE	9.000	EA
1000	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	2.000	EA
1010	629(E)7600	MAILBOX	14.000	EA
0002	BRIDGE 'A'			
1020	202(A)2210	UNCLASSIFIED EXCAVATION	3,250.000	CY
1030	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	286.000	CY
1040	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1050	509(A)0210	CLASS AA CONCRETE	689.200	CY
1060	511(A)2210	REINFORCING STEEL	89,940.000	LB
1070	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE 'B'			
1080	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	330.000	CY
1090	501(G)1800	CLSM BACKFILL	258.000	CY
1100	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1110	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	654.000	LF
1120	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	642.000	LF
1130	504(A)5200	APPROACH SLAB	393.400	SY
1140	504(B)5300	SAW-CUT GROOVING	1,782.000	SY
1150	504(E)5520	42" F-SHAPED PARAPET	559.800	LF
1160	506(A)7200	STRUCTURAL STEEL	2,280.000	LB
1170	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
1180	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
1190	509(A)0210	CLASS AA CONCRETE	354.700	CY
1200	509(B)0320	CLASS A CONCRETE	254.900	CY
1210	509(D)0510	CLASS C CONCRETE	14.000	CY
1220	510(C)1450	SLOPE WALL (5")	904.000	SY
1230	511 2100	MECHANICAL SPLICES	1,026.000	EA
1240	511(A)2210	REINFORCING STEEL	2,200.000	LB
1250	511(B)2310	EPOXY COATED REINFORCING STEEL	116,220.000	LB
1260	513(B)4300	CLASS B BRIDGE DECK REPAIR	40.000	SY
1270	513(C)4400	CLASS C BRIDGE DECK REPAIR	40.000	SY
1280	514(A)5210	PILES, FURNISHED (HP 10X42)	230.000	LF
1290	514(A)5220	PILES, FURNISHED (HP 12X53)	973.000	LF
1300	514(B)5310	PILES, DRIVEN (HP 10X42)	230.000	LF
1310	514(B)5320	PILES, DRIVEN (HP 12X53)	973.000	LF
1320	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1330	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	882.000	SY
1340	516(A)8235	DRILLED SHAFTS 54" DIAMETER	352.000	LF
1350	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1360	517 9110	ELASTOMERIC COATING	2,016.000	SF
1370	518(B)0300	SEALED EXPANSION JOINTS	60.000	LF
1380	523(A)3200	SEALER CRACK PREPARATION	496.000	LF
1390	523(B)3300	SEALER RESIN	5.100	GAL
1400	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	266.000	LF
1410	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	64.000	LF
1420	613(Q)7500	OUTLET LATERAL HEADWALL	2.000	EA
1430	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0004	BRIDGE 'C'			
1440	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	330.000	CY
1450	501(G)1800	CLSM BACKFILL	258.000	CY
1460	502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
1470	503(A)4220	PRESTRESSED CONCRETE BEAMS (TYPE II)	654.000	LF
1480	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	642.000	LF
1490	504(A)5200	APPROACH SLAB	393.400	SY
1500	504(B)5300	SAW-CUT GROOVING	1,782.000	SY
1510	504(E)5520	42" F-SHAPED PARAPET	559.800	LF
1520	506(A)7200	STRUCTURAL STEEL	2,280.000	LB
1530	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
1540	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
1550	509(A)0210	CLASS AA CONCRETE	354.700	CY
1560	509(B)0320	CLASS A CONCRETE	254.900	CY
1570	509(D)0510	CLASS C CONCRETE	10.000	CY
1580	510(C)1450	SLOPE WALL (5")	904.000	SY
1590	511 2100	MECHANICAL SPLICES	1,026.000	EA
1600	511(A)2210	REINFORCING STEEL	2,200.000	LB
1610	511(B)2310	EPOXY COATED REINFORCING STEEL	116,220.000	LB
1620	513(B)4300	CLASS B BRIDGE DECK REPAIR	40.000	SY
1630	513(C)4400	CLASS C BRIDGE DECK REPAIR	40.000	SY
1640	514(A)5210	PILES, FURNISHED (HP 10X42)	230.000	LF
1650	514(A)5220	PILES, FURNISHED (HP 12X53)	973.000	LF
1660	514(B)5310	PILES, DRIVEN (HP 10X42)	230.000	LF
1670	514(B)5320	PILES, DRIVEN (HP 12X53)	973.000	LF
1680	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
1690	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	882.000	SY
1700	516(A)8235	DRILLED SHAFTS 54" DIAMETER	364.000	LF
1710	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1720	517 9110	ELASTOMERIC COATING	2,016.000	SF
1730	518(B)0300	SEALED EXPANSION JOINTS	60.000	LF
1740	523(A)3200	SEALER CRACK PREPARATION	496.000	LF
1750	523(B)3300	SEALER RESIN	5.100	GAL
1760	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	266.000	LF
1770	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	44.000	LF
1780	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0005	SIGNING, STRIPING, AND SAFETY			
1790	413(A)4200	RUMBLE STRIP-METHOD HMA-CON	23,839.000	LF
1800	509(D)0500	CLASS C CONCRETE	35.000	CY
1810	511(A)2200	REINFORCING STEEL	1,405.000	LB
1820	516(A)8230	DRILLED SHAFTS 48" DIAMETER	88.000	LF
1830	516(A)8235	DRILLED SHAFTS 54" DIAMETER	54.000	LF
1840	619(B)6432	REMOVAL OF CABLE BARRIER	4,239.000	LF
1850	628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	4,239.000	LF
1860	628(C)7400	END ANCHORS	4.000	EA
1870	628(E)7600	CABLE BARRIER TENSION METER	1.000	EA
1880	804(A)2200	STRUCTURAL CONCRETE	14.000	CY
1890	804(B)2300	REINFORCING STEEL	1,696.000	LB
1900	805(A)3240	(PL)REMOVAL OF OVHD.SIGN STR. & SIGNS	1.000	LSUM
1910	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	42.000	EA
1920	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	10.000	EA
1930	850(A)1200	SHEET ALUMINUM SIGNS	1,108.000	SF
1940	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	950.000	SF
1950	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	862.000	SF
1960	851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	295.000	LF
1970	851(C)2415	2" SQUARE TUBE POST	1,363.000	LF
1980	852(D)3579	OVHD.SN.STR., MONOTUBE B9	1.000	EA
1990	852(E)3622	OVHD.SN.STR., MONOTUBE C2	1.000	EA
2000	852(E)3623	OVHD.SN.STR., MONOTUBE C3	2.000	EA
2010	853 5100	DELINEATORS(TYPE 1, CODE 1)	14.000	EA
2020	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	34.000	EA
2030	855(A)7205	(SP) TRAFFIC STRIPE(PLASTIC)(6" WIDE)	27,667.000	LF
2040	855(A)7213	(SP) TRAFFIC STRIPE(PLASTIC)(12" WIDE)	3,479.000	LF
2050	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	23,642.000	LF
2060	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,497.000	LF
2070	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	174.000	LF
2080	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	49.000	EA
2090	856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	10.000	EA
2100	858(A)0212	PAVE.MARKERS CLASS A TYPE 2	170.000	EA
2110	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	95.000	EA

Proposal:260254 **Let Date:**January 14, 2027 **Call Order:**542
J/P Num:32802(04) **Proj. Num:**NHPPI-3500(181)FP
Counties:MCCLAIN
Description:INTERCHANGE
I-35: OVER SH-74 (GRANT STREET), 1 MILE NORTH OF WEST ADAMS STREET IN PURCELL.
PROJECT LENGTH = 1.183 MILES

Line #		Item Description	Quantity	Unit
0006	TRAFFIC CONTROL			
2120	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	126.000	SD
2130	857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	104,918.000	LF
2140	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	52,590.000	LF
2150	871(B)2300	CONST.ZONE IMPACT ATTEN.	1,683.000	SD
2160	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	15,632.000	LF
2170	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	30,787.000	LF
2180	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	11,777.000	SD
2190	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,207.000	SD
2200	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	12,285.000	SD
2210	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,145.000	SD
2220	880(E)6600	WARNING LIGHTS(TYPE A)	7,821.000	SD
2230	880(E)6607	WARNING LIGHTS(TYPE B)	8,048.000	SD
2240	880(E)6616	WARNING LIGHTS(TYPE D)	46,328.000	SD
2250	880(F)6700	DRUMS	31,804.000	SD
2260	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	240.000	HOUR
2270	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,076.000	SD
0007	STAKING			
2280	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
2290	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
2300	640(A)1210	FIELD OFFICE	1.000	EA
2310	641 2110	MOBILIZATION	1.000	LSUM