

Proposal:260255**Let Date:**October 15, 2026**Call Order:**145**J/P Num:**31302(04)**Proj. Num:**STP-246C(074)CI**Counties:**MCINTOSH**Description:**GRADE, DRAIN, AND SURFACE

COUNTY ROAD (PIERCE ROAD/EW-109):

FROM 4.1 MILES WEST OF THE SH-150 INTERSECTION,

EXTEND EAST NEAR LAKE EUFAULA STATE PARK.

PROJECT LENGTH = 4.162 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	46,922.000	CY
0030 202(F)2700	EMBANKMENTS	36,434.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	4,440.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	1,939.000	LF
0070 230(A)7200	SOLID SLAB SODDING	98,904.000	SY
0080 233(A)0200	VEGETATIVE MULCHING	21.000	AC
0090 241 3100	MOWING	42.000	AC
0100 303(A)1200	AGGREGATE BASE TYPE A	311.000	CY
0110 307(K)4200	STABILIZED SUBGRADE	69,696.000	SY
0120 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	463.000	TON
0130 407(B)7300	TACK COAT	5,034.000	GAL
0140 408 8100	PRIME COAT	24,395.000	GAL
0150 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	15,244.000	TON
0160 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	7,451.000	TON
0170 501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	103.000	CY
0180 509(A)0200	CLASS AA CONCRETE	339.000	CY
0190 509(D)0500	CLASS C CONCRETE	2,090.000	CY
0200 511(A)2200	REINFORCING STEEL	28,862.000	LB
0210 601(A)1100	TYPE I PLAIN RIPRAP	4,887.000	TON
0220 613(A)5208	18" R.C.PIPES CLASS III	170.000	LF
0230 613(A)5216	24" R.C.PIPES CLASS III	146.000	LF
0240 613(A)5224	36" R.C.PIPES CLASS III	58.000	LF
0250 613(A)5358	28" X 18" R.C.PIPES ARCH CLASS A-III	128.000	LF
0260 613(B)5508	18" CORR. GALV. STEEL PIPE	1,834.000	LF
0270 613(B)5516	24" CORR. GALV. STEEL PIPE	46.000	LF
0280 613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	1,216.000	LF
0290 613(B)5612	28" X 20" CORR. GALV. STEEL PIPE ARCH	66.000	LF
0300 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	6.000	EA
0310 613(L)6728	36" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0320 613(M)6900	TYPE A3 CULVERT END TREATMENT	107.000	EA
0330 613(M)6904	TYPE B3 CULVERT END TREATMENT	4.000	EA
0340 613(M)6924	TYPE BB3 CULVERT END TREATMENT	2.000	EA
0350 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0360 619(B)6352	REMOVAL OF FENCE	26,120.000	LF
0370 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	50,376.000	SY
0380 619(B)6396	REMOVAL OF GUARDRAIL	424.000	LF
0390 619(C)6600	SAWING PAVEMENT	1,221.000	LF
0400 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	75.000	LF
0410 623(G)1820	GUARDRAIL END TREATMENT (31")	12.000	EA
0420 624(A)3200	FENCE-STYLE WWF	4,886.000	LF
0430 624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	18,253.000	LF
0440 624(C)3410	FENCE-STYLE SWF (6 BARBED WIRE)	2,683.000	LF
0450 629(A)7200	MAILBOX INSTALLATION-SINGLE	17.000	EA

Proposal:260255**Let Date:**October 15, 2026**Call Order:**145**J/P Num:**31302(04)**Proj. Num:**STP-246C(074)CI**Counties:**MCINTOSH**Description:**GRADE, DRAIN, AND SURFACE

COUNTY ROAD (PIERCE ROAD/EW-109):

FROM 4.1 MILES WEST OF THE SH-150 INTERSECTION,

EXTEND EAST NEAR LAKE EUFAULA STATE PARK.

PROJECT LENGTH = 4.162 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0460 629(B)7300	MAILBOX INSTALLATION-MULTIPLE	5.000	EA
0470 629(C)7400	REMOVAL OF MAILBOX INSTALLATION	31.000	EA
0480 629(D)7500	REMOVE AND RESET MAILBOX	1.000	EA
0490 629(E)7600	MAILBOX	31.000	EA
0002 TRAFFIC			
0500 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
0510 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0520 850(A)1200	SHEET ALUMINUM SIGNS	66.260	SF
0530 851(C)2415	2" SQUARE TUBE POST	84.000	LF
0540 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	87,908.000	LF
0550 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	120.000	LF
0560 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,400.000	SD
0570 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	600.000	SD
0580 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,400.000	SD
0590 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0600 880(E)6600	WARNING LIGHTS(TYPE A)	3,600.000	SD
0003 STAKING			
0610 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004 CONSTRUCTION			
0620 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0630 641 2110	MOBILIZATION	1.000	LSUM