

Proposal:260256

Let Date:October 15, 2026

Call Order:150

J/P Num:38082(04)

Proj. Num:STP-255N(635)AG

Counties:OKLAHOMA

Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	6,462.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 221(B)2300	TEMPORARY SILT FENCE	1,950.000	LF
0050 221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	14.000	EA
0060 230(A)7200	SOLID SLAB SODDING	7,819.000	SY
0070 233(A)0200	VEGETATIVE MULCHING	2.590	AC
0080 241 3100	MOWING	5.180	AC
0090 307(K)4200	STABILIZED SUBGRADE	15,779.000	SY
0100 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	246.000	TON
0110 407(C)7500	NT TACK MATERIAL	50.000	GAL
0120 408 8100	PRIME COAT	3,862.000	GAL
0130 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	149.000	TON
0140 411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	1,563.000	TON
0150 412 3100	COLD MILLING PAVEMENT	11,851.000	SY
0160 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	2,927.000	SY
0170 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	11,659.000	SY
0180 414(G)5800	P.C. CONCRETE FOR PAVEMENT	3,975.000	CY
0190 501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	5.000	CY
0200 509(A)0200	CLASS AA CONCRETE	12.000	CY
0210 509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.000	CY
0220 509(D)0500	CLASS C CONCRETE	13.000	CY
0230 511(A)2200	REINFORCING STEEL	2,114.000	LB
0240 609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	2,351.000	LF
0250 609(B)4345	1'-8" COMB.CRB.& GUT.(8" BARRIER)	1,605.000	LF
0260 610(A)5200	4" CONCRETE SIDEWALK	1,174.000	SY
0270 610(B)5320	8" CONCRETE DRIVEWAY	1,666.000	SY
0280 610(C)5410	6" CONCRETE DIVIDING STRIP	85.000	SY
0290 610(I)6000	TACTILE WARNING DEVICE-NEW	200.000	SF
0300 610(J)6100	(PL) STAMPED CONCRETE FINISH	119.000	SY
0310 611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0320 611(G)0264	INLET W/SMALL JCT. BOX, CI, DES.2	1.000	EA
0330 611(G)7754	INLET CI DES. 2 (STD)	1.000	EA
0340 611(G)7794	INLET CI DES. 3 (D)	1.000	EA
0350 611(G)7802	INLET CI DES. 3 (B-D)	1.000	EA
0360 611(G)8032	INLET CDI RCB DES. 9	1.000	EA
0370 611(L)1600	JUNCTION BOXES	195.000	CF
0380 612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0390 612(E)3600	VALVE BOXES ADJUST TO GRADE	5.000	EA
0400 612(I)4010	WATER METER RELOCATION	4.000	EA
0410 613(A)5208	18" R.C.PIPE CLASS III	9.000	LF
0420 613(A)5216	24" R.C.PIPE CLASS III	44.000	LF
0430 613(A)5220	30" R.C.PIPE CLASS III	79.000	LF
0440 613(A)5358	28" X 18" R.C.PIPE ARCH CLASS A-III	50.000	LF
0450 613(A)5370	43" X 26" R.C.PIPE ARCH CLASS A-III	50.000	LF
0460 613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	1.000	EA

Proposal:260256

Let Date:October 15, 2026

Call Order:150

J/P Num:38082(04)

Proj. Num:STP-255N(635)AG

Counties:OKLAHOMA

Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS

CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION

OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.

PROJECT LENGTH= 0.602 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0470 613(L)6648	43" X 26" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0480 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0490 616(D)2768	12" X 6" TAPPING SLEEVE	1.000	EA
0500 616(D)2812	6" TAPPING VALVE AND BOX	1.000	EA
0510 616(G)3111	FIRE HYDRANT AND ASSEMBLY	1.000	EA
0520 616(G)3115	FLUSH FIRE HYDRANTS	1.000	EA
0530 616(S)4405	6" PLUG	1.000	EA
0540 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0550 619(B)6356	REMOVAL OF CURB AND GUTTER	3,851.000	LF
0560 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,309.000	SY
0570 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	9,947.000	SY
0580 619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	2,292.000	SY
0590 619(B)6404	REMOVAL OF SIDEWALK	386.000	SY
0600 619(B)6448	REMOVAL OF FIRE HYDRANT	1.000	EA
0610 619(B)6492	REMOVE WATER METER AND METER CAN	2.000	EA
0620 619(B)6496	REMOVAL OF GATE VALVE AND BOX	1.000	EA
0630 619(C)6600	SAWING PAVEMENT	3,423.000	LF

Proposal:260256**Let Date:**October 15, 2026**Call Order:**150**J/P Num:**38082(04)**Proj. Num:**STP-255N(635)AG**Counties:**OKLAHOMA**Description:**INTERSECTION MODIFICATION AND TRAFFIC SIGNALS

CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION

OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.

PROJECT LENGTH= 0.602 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	TRAFFIC		
0640 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	475.000	LF
0650 802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	635.000	LF
0660 802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	150.000	LF
0670 803(A)1210	PULL BOX(SIZE I)	3.000	EA
0680 803(A)1220	PULL BOX(SIZE II)	5.000	EA
0690 804(A)2200	STRUCTURAL CONCRETE	53.870	CY
0700 804(B)2300	REINFORCING STEEL	7,694.800	LB
0710 805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0720 805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0730 806(A)4240	32'MH POLE 25'TS & 10'LMA(G.STL.)	1.000	EA
0740 806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
0750 806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	1.000	EA
0760 806(A)4260	32'MH POLE 50'TS & 10'LMA(G.STL.)	1.000	EA
0770 806(A)4264	32'MH POLE,55'TS & 10'LMA(G.STL.)	1.000	EA
0780 806(A)4312	POLE & 25' TS MST.ARM(G.STL.)	1.000	EA
0790 806(A)4336	POLE & 55'T.S.MST.ARM(G.STL.)	1.000	EA
0800 806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	2.000	EA
0810 806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	9.000	EA
0820 809(A)7200	ROADWAY LUMINAIRE	5.000	EA
0830 811 9120	1/C NO.6 ELECT.COND.	400.000	LF
0840 811 9130	1/C NO.10 ELECT.COND.	2,700.000	LF
0850 825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	2.000	EA
0860 828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0870 830 2100	PEDESTRIAN PUSH BUTTON	16.000	EA
0880 831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	16.000	EA
0890 831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	18.000	EA
0900 831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	6.000	EA
0910 831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	1.000	EA
0920 831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	1.000	EA
0930 833 5100	BACKPLATE	28.000	EA
0940 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	5,880.000	LF
0950 834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	128.000	LF
0960 834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,450.000	LF
0970 834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	200.000	LF
0980 840(B)0300	E.P.S. OPTICAL DETECTOR	6.000	EA
0990 840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	1,296.000	LF
1000 840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	1.000	EA
1010 840(D)0510	E.P.S. 4 CHANNEL PHASE SELECTOR	1.000	EA
1020 850(A)1200	SHEET ALUMINUM SIGNS	167.500	SF

Proposal:260256

Let Date:October 15, 2026

Call Order:150

J/P Num:38082(04)

Proj. Num:STP-255N(635)AG

Counties:OKLAHOMA

Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS

CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION

OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.

PROJECT LENGTH= 0.602 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 TRAFFIC SIGNING AND STRIPING			
1030 804(A)2200	STRUCTURAL CONCRETE	0.600	CY
1040 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
1050 850(A)1200	SHEET ALUMINUM SIGNS	44.540	SF
1060 851(B)2305	2"@3.65 GALV.STL.PIPE POST	133.500	LF
1070 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	12,130.000	LF
1080 856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	100.000	LF
1090 856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	1,000.000	LF
1100 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,250.000	LF
1110 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	28.000	EA
1120 856(B)8315	(SP) TRAFFIC STRIPE(PLURAL-COMP)(WORDS)	3.000	EA
1130 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	15,000.000	LF
0004 TRAFFIC LIGHTING			
1140 802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	1,550.000	LF
1150 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	3,075.000	LF
1160 803(A)1200	PULL BOX	53.000	EA
1170 804(A)2200	STRUCTURAL CONCRETE	34.440	CY
1180 804(B)2300	REINFORCING STEEL	5,964.000	LB
1190 806(D)4616	40' MTG.HT.HL.PTP.(G.STL.)	21.000	EA
1200 811 9115	1/C NO.4 ELECT.COND.	16,100.000	LF
1210 811 9135	1/C NO.12 ELECT.COND.	2,100.000	LF
0005 TRAFFIC CONTROL			
1220 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	21,500.000	LF
1230 857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	6.000	EA
1240 857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	85,798.000	LF
1250 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	90,000.000	LF
1260 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	5,000.000	EA
1270 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	5,000.000	EA
1280 871(B)2300	CONST.ZONE IMPACT ATTEN.	210.000	SD
1290 871(C)2410	RELOCATION OF IMPACT ATTENUATOR	17.000	EA
1300 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	665.000	LF
1310 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	1,255.000	LF
1320 880(A)6210	ARROW DISPLAY(TYPE B)	360.000	SD
1330 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,760.000	SD
1340 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	10,740.000	SD
1350 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,660.000	SD
1360 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	7,170.000	SD
1370 880(E)6607	WARNING LIGHTS(TYPE B)	18,000.000	SD
1380 880(E)6616	WARNING LIGHTS(TYPE D)	15,000.000	SD
1390 880(F)6700	DRUMS	15,000.000	SD
1400 880(G)6805	CHANNELIZER CONES	6,030.000	SD
1410 880(N)7500	(SP) TEMP. TRAFF. SIGNAL SPAN WIRE EQUIP	1.000	LSUM
1420 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	420.000	SD

Proposal:260256

Let Date:October 15, 2026

Call Order:150

J/P Num:38082(04)

Proj. Num:STP-255N(635)AG

Counties:OKLAHOMA

Description:INTERSECTION MODIFICATION AND TRAFFIC SIGNALS
CITY STREET (S DOUGLAS BOULEVARD): AT THE INTERSECTION
OF SE 29TH ST, 0.23 MILES NORTH OF I-40 IN THE CITY OF MIDWEST CITY.
PROJECT LENGTH= 0.602 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0006 STAKING			
1430 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007 CONSTRUCTION			
1440 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1450 641 2100	MOBILIZATION	1.000	LSUM