

Proposal:260259

Let Date:October 22, 2026

Call Order:270

J/P Num:19983(11)

Proj. Num:STP-166C(202)PM

Counties:ROGERS, WAGONER

Description:INTERCHANGE

US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.

PROJECT LENGTH = 1.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	129,830.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	235,849.000	CY
0040 202(E)2600	SELECT BORROW	500.000	CY
0050 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060 221(B)2300	TEMPORARY SILT FENCE	17,357.000	LF
0070 221(C)2400	TEMPORARY SEDIMENT FILTER	17.000	EA
0080 221(D)2500	TEMPORARY SEDIMENT BASIN	9.000	EA
0090 221(E)2600	TEMPORARY SILT DIKE	5,488.000	LF
0100 221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	198.000	CY
0110 229 6100	DITCH LINER PROTECTION	9,588.000	LF
0120 230(A)7200	SOLID SLAB SODDING	94,252.000	SY
0130 232(A)9200	SEEDING METHOD A	31.780	AC
0140 233(A)0200	VEGETATIVE MULCHING	31.780	AC
0150 241 3100	MOWING	254.240	AC
0160 242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0170 303(B)1300	AGGREGATE BASE TYPE B	14,720.000	CY
0180 307(K)4200	STABILIZED SUBGRADE	67,288.000	SY
0190 325 0100	SEPARATOR FABRIC	78,854.000	SY
0200 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	8,456.000	TON
0210 408 8100	PRIME COAT	15,437.000	GAL
0220 411(L)2404	BMD, TYPE B3 (PG 64-22 OK)	8,728.000	TON
0230 411(L)2408	BMD, TYPE B3 (PG 70-28 OK)	2,245.000	TON
0240 411(L)2424	BMD, TYPE B4 (PG 64-22 OK)	533.000	TON
0250 411(L)2428	BMD, TYPE B4 (PG 70-28 OK)	894.000	TON
0260 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	13,595.000	SY
0270 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	24,863.000	SY
0280 414(G)5800	P.C. CONCRETE FOR PAVEMENT	10,147.000	CY
0290 501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	75.000	CY
0300 504(E)5520	42" F-SHAPED PARAPET	1,309.000	LF
0310 509(A)0200	CLASS AA CONCRETE	214.000	CY
0320 509(D)0500	CLASS C CONCRETE	894.000	CY
0330 511(A)2200	REINFORCING STEEL	27,570.000	LB
0340 601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	220.000	TON
0350 602(C)2410	FILTER FABRIC	147.000	SY
0360 610(B)5310	6" CONCRETE DRIVEWAY	36.000	SY
0370 610(C)5410	6" CONCRETE DIVIDING STRIP	997.000	SY
0380 611(A)7210	MANHOLE (4' DIA.)	1.000	EA
0390 613(A)5216	24" R.C.Pipe CLASS III	421.000	LF
0400 613(A)5220	30" R.C.Pipe CLASS III	125.000	LF
0410 613(B)5508	18" CORR. GALV. STEEL PIPE	203.000	LF
0420 613(B)5516	24" CORR. GALV. STEEL PIPE	221.000	LF
0430 613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	152.000	LF
0440 613(L)6608	21" X 15" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0450 613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	3.000	EA
0460 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	5.000	EA

Proposal:260259

Let Date:October 22, 2026

Call Order:270

J/P Num:19983(11)

Proj. Num:STP-166C(202)PM

Counties:ROGERS, WAGONER

Description:INTERCHANGE

US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.

PROJECT LENGTH = 1.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0470 613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0480 613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0490 613(M)7004	TYPE A6 CULVERT END TREATMENT	1.000	EA
0500 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0510 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	10,676.000	SY
0520 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	16,587.000	SY
0530 619(B)6400	REMOVAL OF CURB	200.000	LF
0540 619(C)6600	SAWING PAVEMENT	1,970.000	LF
0550 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	87.500	LF
0560 623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
0570 623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0580 624(A)3200	FENCE-STYLE WWF	5,659.000	LF
0590 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	6.000	EA
0600 871(A)2200	IMPACT ATTENUATOR	6.000	EA
0002	BRIDGE 'B' - NBI NO. 30082		
0610 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	110.000	CY
0620 501(G)1800	CLSM BACKFILL	198.200	CY
0630 503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	701.000	LF
0640 503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,076.000	LF
0650 504(A)5200	APPROACH SLAB	293.400	SY
0660 504(B)5300	SAW-CUT GROOVING	1,814.900	SY
0670 504(E)5520	42" F-SHAPED PARAPET	692.000	LF
0680 506(A)7200	STRUCTURAL STEEL	2,030.000	LB
0690 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0700 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	36.000	EA
0710 507(C)8400	ELASTOMERIC BEARING PADS	36.000	EA
0720 509 0100	SPECIAL CONCRETE FINISH	2,404.000	SY
0730 509(A)0210	CLASS AA CONCRETE	499.900	CY
0740 509(B)0320	CLASS A CONCRETE	380.400	CY
0750 510(C)1450	SLOPE WALL (5")	827.000	SY
0760 511(A)2210	REINFORCING STEEL	4,120.000	LB
0770 511(B)2310	EPOXY COATED REINFORCING STEEL	237,720.000	LB
0780 514(A)5210	PILES, FURNISHED (HP 10X42)	513.000	LF
0790 514(B)5310	PILES, DRIVEN (HP 10X42)	513.000	LF
0800 514(G)5800	METAL PILE SHOES	18.000	EA
0810 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0820 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	945.000	SY
0830 516(A)8255	DRILLED SHAFTS 84" DIAMETER	328.000	LF
0840 516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
0850 517 9110	ELASTOMERIC COATING	1,156.000	SF
0860 523(A)3200	SEALER CRACK PREPARATION	440.000	LF
0870 523(B)3300	SEALER RESIN	14.000	GAL
0880 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	240.000	LF
0890 613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	80.000	LF

Proposal:260259

Let Date:October 22, 2026

Call Order:270

J/P Num:19983(11)

Proj. Num:STP-166C(202)PM

Counties:ROGERS, WAGONER

Description:INTERCHANGE

US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.

PROJECT LENGTH = 1.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003	TRAFFIC CONTROL		
0900 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	35,046.000	LF
0910 857(B)9300	CONSTRUCTION TRAFFIC STR.(PAINT)(ARROWS)	8.000	EA
0920 857(E)9620	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-1	100.000	EA
0930 857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	17.000	EA
0940 857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	53,928.000	LF
0950 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	5,130.000	EA
0960 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	3,150.000	EA
0970 871(B)2300	CONST.ZONE IMPACT ATTEN.	1,200.000	SD
0980 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,750.000	LF
0990 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	6,890.000	LF
1000 880(A)6220	ARROW DISPLAY(TYPE C)	675.000	SD
1010 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	24,645.000	SD
1020 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	13,185.000	SD
1030 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	8,310.000	SD
1040 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	15,405.000	SD
1050 880(D)6500	VERTICAL PANELS	84,000.000	SD
1060 880(E)6607	WARNING LIGHTS(TYPE B)	39,120.000	SD
1070 880(F)6700	DRUMS	106,395.000	SD
1080 880(I)7000	FLAGGER	35.000	SD
1090 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	840.000	hour
1100 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	2,038.000	SD
0004	TRAFFIC SIGNING AND STRIPING		
1110 804(A)2200	STRUCTURAL CONCRETE	21.000	CY
1120 804(B)2300	REINFORCING STEEL	2,846.000	LB
1130 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
1140 850(A)1200	SHEET ALUMINUM SIGNS	346.000	SF
1150 850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	691.000	SF
1160 851(A)2200	4"@13 GALV.STL.WD.FLANGE BM.POST	29.000	LF
1170 851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	429.000	LF
1180 851(B)2305	2"@3.65 GALV.STL.PIPE POST	114.000	LF
1190 851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	240.000	LF
1200 851(C)2415	2" SQUARE TUBE POST	128.000	LF
1210 851(C)2420	2 1/4" SQUARE TUBE POST	276.000	LF
1220 853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	77.000	EA
1230 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	57,685.000	LF
1240 856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	3,874.000	LF
1250 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	51.000	LF
1260 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	12.000	EA
1270 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	164.000	EA
1280 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	89.000	EA
0005	STAKING		
1290 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:260259

Let Date:October 22, 2026

Call Order:270

J/P Num:19983(11)

Proj. Num:STP-166C(202)PM

Counties:ROGERS, WAGONER

Description:INTERCHANGE

US-412: AT SH-412P, 6.6 MILES WEST OF THE SH-88 INTERCHANGE
NEAR FAIR OAKS.

PROJECT LENGTH = 1.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0006 CONSTRUCTION			
1300 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1310 640(A)1210	FIELD OFFICE	1.000	EA
1320 641 2110	MOBILIZATION	1.000	LSUM