

Proposal:260261
J/P Num:38169(04)
Counties:TILLMAN

Let Date:October 15, 2026
Proj. Num:STP-271D(085)CI

Call Order:170

Description:BRIDGE AND APPROACHES

COUNTY ROAD (EW-1950): OVER COOPER CREEK,
 3.25 MILES EAST OF THE TEXAS STATE LINE NEAR DAVIDSON.
 PROJECT LENGTH = 0.236 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(H)2900	EARTHWORK	1.000	LSUM
0030 221(B)2300	TEMPORARY SILT FENCE	700.000	LF
0040 221(E)2600	TEMPORARY SILT DIKE	350.000	LF
0050 230(A)7200	SOLID SLAB SODDING	6,700.000	SY
0060 233(A)0200	VEGETATIVE MULCHING	1.390	AC
0070 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	702.000	TON
0080 509(D)0500	CLASS C CONCRETE	10.000	CY
0090 601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	2,428.000	TON
0100 613(B)5516	24" CORR. GALV. STEEL PIPE	60.000	LF
0110 613(M)6904	TYPE B3 CULVERT END TREATMENT	2.000	EA
0002 BRIDGE 'A'			
0120 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	230.600	CY
0130 501(F)1700	GRANULAR BACKFILL	109.600	CY
0140 503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	419.000	LF
0150 504(D)5410	CONCRETE RAIL (TR3)	291.300	LF
0160 506(A)7200	STRUCTURAL STEEL	780.000	LB
0170 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	4.000	EA
0180 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	4.000	EA
0190 509(A)0210	CLASS AA CONCRETE	93.400	CY
0200 509(B)0320	CLASS A CONCRETE	83.200	CY
0210 511(A)2210	REINFORCING STEEL	35,662.000	LB
0220 514(A)5210	PILES, FURNISHED (HP 10X42)	146.000	LF
0230 514(A)5220	PILES, FURNISHED (HP 12X53)	455.000	LF
0240 514(B)5310	PILES, DRIVEN (HP 10X42)	146.000	LF
0250 514(B)5320	PILES, DRIVEN (HP 12X53)	455.000	LF
0260 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0270 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	4,938.000	TON
0280 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	66.000	LF
0290 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	40.000	LF
0295 619(B)6440	REMOVAL OF EXISTING PIPE	60.000	LF
0310 623(F)1748	GUARDRAIL ANCHOR UNIT (TYPE II)	4.000	EA
0003 TRAFFIC			
0320 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	480.000	SD
0330 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	720.000	SD
0340 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,200.000	SD
0350 880(E)6600	WARNING LIGHTS(TYPE A)	2,640.000	SD
0004 STAKING			
0360 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005 CONSTRUCTION			
0370 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0380 641 2110	MOBILIZATION	1.000	LSUM