Proposal:260262 **Let Date:**January 14, 2027 **Call Order:**578
J/P Num:33310(04) **Proj. Num:**STP-272B(451)IG
Counties:TULSA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
CITY STREET (OLIVE AVENUE): FROM 0.1 MILES
SOUTH OF WEST KENOSHA STREET, EXTEND
NORTH IN BROKEN ARROW.
PROJECT LENGTH = 1.005 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	7,080.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	843.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	5,180.000	LF
0060	221(C)2400	TEMPORARY SEDIMENT FILTER	45.000	EA
0070	221(E)2600	TEMPORARY SILT DIKE	133.000	LF
0080	221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	124.000	CY
0090	230(A)7200	SOLID SLAB SODDING	24,094.000	SY
0100	232(A)9200	SEEDING METHOD A	3.000	AC
0110	240(A)2230	REMOVING TREES 25" & MORE IN DIAMETER	3.000	EA
0120	303(A)1200	AGGREGATE BASE TYPE A	4,762.000	CY
0130	307(K)4200	STABILIZED SUBGRADE	17,702.000	SY
0140	325 0100	SEPARATOR FABRIC	23,757.000	SY
0150	326(A)1200	GEOTEXTILE REINFORCEMENT	3,701.000	SY
0160	326(B)1300	GEOGRID REINFORCEMENT	23,757.000	SY
0170	409(A)9200	FABRIC REINFORCEMENT	17,412.000	SY
0180	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	7,885.000	TON
0190	411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	3,310.000	TON
0200	411(E)1610	SUPERPAVE, TYPE S6(PG 70-28 OK)	649.000	TON
0210	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,047.000	TON
0220	412 3100	COLD MILLING PAVEMENT	11,558.000	SY
0230	504(F)5600	HANDRAILING	15.000	LF
0240	509(A)0200	CLASS AA CONCRETE	72.000	CY
0250	509(B)0300	CLASS A CONCRETE	26.000	CY
0260	511(A)2200	REINFORCING STEEL	14,625.000	LB
0270	514(H)5900	SHEET PILING, FURNISHED	525.000	SY
0280	514(I)6000	SHEET PILING, DRIVEN	525.000	SY
0290	514(J)6100	TEMPORARY SHEET PILING	1.000	LSUM
0300	601(A)1100	TYPE I PLAIN RIPRAP	242.000	TON
0310	601(I)1700	FILTER FABRIC (RIPRAP)	3,235.000	SY
0320	609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	8,949.000	LF
0330	610(A)5200	4" CONCRETE SIDEWALK	2,000.000	SY
0340	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	1,625.000	SY
0350	610(I)6000	TACTILE WARNING DEVICE-NEW	240.000	SF
0360	611(A)7210	MANHOLE (4' DIA.)	6.000	EA
0370	611(A)7215	MANHOLE (5' DIA.)	2.000	EA
0380	611(A)7220	MANHOLE (6' DIA.)	1.000	EA
0390	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	1.000	VF
0400	611(B)7305	ADD'L.DEPTH IN MANHOLE (5' DIA.)	3.000	VF
0410	611(B)7310	ADD'L.DEPTH IN MANHOLE (6' DIA.)	3.000	VF
0420	611(G)0350	INLET (SMD-TYPE 1)	3.000	EA
0430	611(G)7700	SPECIAL INLET DRAIN	32.000	EA
0440	611(G)7758	INLET CI DES. 2 (B)	1.000	EA
0450	611(G)7786	INLET CI DES. 3 (STD)	3.000	EA

Proposal:260262 **Let Date:**January 14, 2027 **Call Order:**578
J/P Num:33310(04) **Proj. Num:**STP-272B(451)IG
Counties:TULSA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
CITY STREET (OLIVE AVENUE): FROM 0.1 MILES SOUTH OF WEST KENOSHA STREET, EXTEND NORTH IN BROKEN ARROW.
PROJECT LENGTH = 1.005 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0460	611(G)7794	INLET CI DES. 3 (D)	2.000	EA
0470	611(H)0400	ADDITIONAL DEPTH IN INLET	12.000	VF
0480	611(H)0414	ADD'L DEPTH IN INLET CI DES. 2	2.000	VF
0490	611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	5.000	VF
0500	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0510	612(E)3600	VALVE BOXES ADJUST TO GRADE	1.000	EA
0520	612(F)3700	METER BOXES ADJUST TO GRADE	1.000	EA
0530	613(A)5204	15" R.C.PIPE CLASS III	2,159.000	LF
0540	613(A)5208	18" R.C.PIPE CLASS III	536.000	LF
0550	613(A)5216	24" R.C.PIPE CLASS III	255.000	LF
0560	613(A)5224	36" R.C.PIPE CLASS III	153.000	LF
0570	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0580	613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0590	616(P)4160	18" HDPE PIPE	850.000	LF
0600	616(P)4164	24" HDPE PIPE	385.000	LF
0610	616(P)4170	30" HDPE PIPE	65.000	LF
0620	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0630	619(B)6352	REMOVAL OF FENCE	25.000	LF
0640	619(B)6356	REMOVAL OF CURB AND GUTTER	1,784.000	LF
0650	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,255.000	SY
0660	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	5,907.000	SY
0670	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,565.000	SY
0680	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	578.000	SY
0690	619(B)6404	REMOVAL OF SIDEWALK	497.000	SY
0700	619(C)6600	SAWING PAVEMENT	9,658.000	LF
0710	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	25.000	LF
0002	BRIDGE			
0720	202(A)2210	UNCLASSIFIED EXCAVATION	2,000.000	CY
0730	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	843.000	CY
0740	501(G)1800	CLSM BACKFILL	30.000	CY
0750	504(F)5600	HANDRAILING	104.000	LF
0760	509(A)0210	CLASS AA CONCRETE	623.000	CY
0770	511(A)2210	REINFORCING STEEL	117,210.000	LB
0780	601(A)1110	TYPE I PLAIN RIPRAP	1,660.000	TON
0790	601(I)1700	FILTER FABRIC (RIPRAP)	2,545.000	SY
0800	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260262 **Let Date:**January 14, 2027 **Call Order:**578
J/P Num:33310(04) **Proj. Num:**STP-272B(451)IG
Counties:TULSA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
CITY STREET (OLIVE AVENUE): FROM 0.1 MILES
SOUTH OF WEST KENOSHA STREET, EXTEND
NORTH IN BROKEN ARROW.
PROJECT LENGTH = 1.005 MILES

Line #		Item Description	Quantity	Unit
0003	TRAFFIC PERMANENT			
0810	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	126.000	LF
0820	802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	288.000	LF
0830	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	32.000	LF
0840	803(A)1210	PULL BOX(SIZE I)	3.000	EA
0850	803(A)1220	PULL BOX(SIZE II)	1.000	EA
0860	804(A)2200	STRUCTURAL CONCRETE	15.000	CY
0870	804(B)2300	REINFORCING STEEL	2,024.000	LB
0880	805(A)3248	(PL)REMOVAL OF EXISTING SIGNS	1.000	LSUM
0890	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0900	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	5.000	EA
0910	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
0920	806(A)4256	32'MH POLE 45'TS & 10'LMA(G.STL.)	1.000	EA
0930	806(A)4328	POLE & 45' TS MST.ARM(G.STL.)	1.000	EA
0940	806(A)4332	POLE & 50' TS MST.ARM(G.STL.)	1.000	EA
0950	806(B)4400	6' MTG.HT.TS PED.POLE(G.STL.)	3.000	EA
0960	806(B)4404	8' MTG.HT.TS PED.POLE(G.STL.)	4.000	EA
0970	809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0980	811 9130	1/C NO.10 ELECT.COND.	1,128.000	LF
0990	811 9135	1/C NO.12 ELECT.COND.	1,537.000	LF
1000	823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	360.000	SD
1010	825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
1020	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1030	830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
1040	831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
1050	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	8.000	EA
1060	831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	4.000	EA
1070	833 5100	BACKPLATE	12.000	EA
1080	834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,110.000	LF
1090	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	426.000	LF
1100	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	245.000	LF
1110	834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	510.000	LF
1120	838(A)8200	(SP)DETECTION SYSTEM (OVER-HEIGHT)	4.000	EA
1130	850(A)1200	SHEET ALUMINUM SIGNS	215.000	SF
1140	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	96.000	SF
1150	851(C)2415	2" SQUARE TUBE POST	363.000	LF
1160	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	15,550.000	LF
1170	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	153.000	LF
1180	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	668.000	LF
1190	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	38.000	EA
1200	890 1110	(PL)TRAFFIC ITEMS	4.000	EA

Proposal:260262 **Let Date:**January 14, 2027 **Call Order:**578
J/P Num:33310(04) **Proj. Num:**STP-272B(451)IG
Counties:TULSA
Description:GRADE, DRAIN, BRIDGE AND SURFACE
CITY STREET (OLIVE AVENUE): FROM 0.1 MILES SOUTH OF WEST KENOSHA STREET, EXTEND NORTH IN BROKEN ARROW.
PROJECT LENGTH = 1.005 MILES

	Line #		Item Description	Quantity	Unit
0004	TRAFFIC TEMPORARY				
	1210	850(D)1510	SPECIAL SIGNS	4.000	EA
	1220	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	20,835.000	LF
	1230	857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	16,134.000	LF
	1240	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	160.000	LF
	1250	880(A)6200	ARROW DISPLAY(TYPE A)	690.000	SD
	1260	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	8,760.000	SD
	1270	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,885.000	SD
	1280	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,405.000	SD
	1290	880(C)6415	BARRICADES(TYPE III)	2,775.000	EA
	1300	880(E)6600	WARNING LIGHTS(TYPE A)	5,550.000	SD
	1310	880(F)6700	DRUMS	8,160.000	SD
	1320	880(G)6800	TUBE CHANNELIZERS	56,550.000	SD
	1330	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,740.000	SD
0005	STAKING				
	1340	642(A)3200	CONSTRUCTION STAKING LEVEL I	1.000	LSUM
0006	CONSTRUCTION				
	1350	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
	1360	641 2110	MOBILIZATION	1.000	LSUM
0007	NON-PARTICIPATING (WATERLINE)				
	1370	611(A)7201	SPECIAL MANHOLE	1.000	EA
	1380	615(A)1256	24" POLYVINYL CHLORIDE (PVC) PIPE	1,013.000	LF
	1390	616(C)2435	1" COPPER WATER SERVICE PIPE (LONG)	2.000	EA
	1400	616(D)2678	24" GATE VALVE	4.000	EA
	1410	616(D)2800	STANDARD VALVE BOX	2.000	EA
	1420	616(D)2804	VALVE BOX EXTENSION	7.000	EA
	1430	616(E)2905	1" CORPORATION STOPS	2.000	EA
	1440	616(F)3010	METER INSTALLATION 1"	2.000	EA
	1450	616(I)3342	42" STEEL CASING	100.000	LF
	1460	616(K)3536	24" SOLID SLEEVE	6.000	EA
	1470	616(Q)4220	24" 45 DEGREE BEND	14.000	EA