

Proposal:260263**Let Date:**October 15, 2026**Call Order:**175**J/P Num:**33460(04)**Proj. Num:**NHPP-273N(110)FP**Counties:**WAGONER**Description:**RESURFACE (ASPHALT)SH-51: FROM 0.6 MILES SOUTHEAST OF THE SH-351
(MUSKOGEE TURNPIKE) INTERCHANGE, EXTEND SOUTHEAST
IN BROKEN ARROW.

PROJECT LENGTH= 5.00 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010	407(B)7300 TACK COAT	18,527.000	GAL
0020	411(L)2432 BMD, TYPE B4 (PG 76-28 OK)	23,976.000	TON
0030	412 3100 COLD MILLING PAVEMENT	217,963.000	SY
0002	TRAFFIC		
0040	413(A)4210 RUMBLE STRIP-CENTERLINE HMA-CON	51,788.000	LF
0050	413(B)4310 RUMBLE STRIP-METHOD HMA-CYC	51,788.000	LF
0060	828(B)0300 LOOP DETECTOR WIRE	500.000	LF
0070	856(A)8207 (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	135,542.500	LF
0080	856(A)8215 (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	2,710.000	LF
0090	856(A)8219 (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	498.000	LF
0100	856(B)8307 (SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	202.000	EA
0110	880(A)6220 ARROW DISPLAY(TYPE C)	90.000	SD
0120	880(B)6300 CONSTRUCTION SIGNS 0 TO 6.25 SF	1,395.000	SD
0130	880(B)6310 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	540.000	SD
0140	880(B)6320 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,530.000	SD
0150	880(C)6410 CONSTRUCTION BARRICADES(TYPE III)	450.000	SD
0160	880(E)6600 WARNING LIGHTS(TYPE A)	450.000	SD
0170	880(F)6700 DRUMS	1,530.000	SD
0180	880(G)6805 CHANNELIZER CONES	9,540.000	SD
0190	882(A)8210 PORT.CHANGEABLE MESSAGE SIGN	118.000	SD