

Proposal:260266**Let Date:**October 22, 2026**Call Order:**018**J/P Num:**36892(04)**Proj. Num:**IN-MC-77**Counties:**PITTSBURG**Description:**BRIDGE AND APPROACHES

INDIAN NATION TURNPIKE: BRIDGE NO. 36.45 (MP 67.70)

OVER SH-31 AND UNION PACIFIC RAILROAD, 1.7 MILES

SOUTHEAST OF THE US-270 INTERCHANGE NEAR McALESTER.

PROJECT LENGTH = 0.394 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	166.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	150.000	CY
0040 205(A)6210	TYPE A-SALVAGED TOPSOIL	114.000	CY
0050 221(B)2300	TEMPORARY SILT FENCE	1,466.000	LF
0060 221(C)2400	TEMPORARY SEDIMENT FILTER	2.000	EA
0070 230(A)7200	SOLID SLAB SODDING	815.000	SY
0080 307(K)4200	STABILIZED SUBGRADE	2,866.000	SY
0090 310(B)5300	SUBGRADE, METHOD B	918.000	SY
0100 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	39.000	TON
0110 407(B)7300	TACK COAT	465.000	GAL
0120 408 8100	PRIME COAT	714.000	GAL
0130 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	577.000	TON
0140 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	396.000	TON
0150 412 3100	COLD MILLING PAVEMENT	583.000	SY
0160 413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	1,879.000	LF
0170 413(D)4510	RUMBLE STRIP METHOD PCC-CYC	399.000	LF
0180 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	673.000	SY
0190 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,062.000	SY
0200 414(G)5800	P.C. CONCRETE FOR PAVEMENT	398.000	CY
0210 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,062.000	SY
0230 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	2,142.000	SY
0240 619(B)6396	REMOVAL OF GUARDRAIL	926.000	LF
0250 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	800.000	LF
0260 623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0270 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0280 624(A)3200	FENCE-STYLE WWF	517.000	LF
0290 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	17.000	EA

Proposal:260266**Let Date:**October 22, 2026**Call Order:**018**J/P Num:**36892(04)**Proj. Num:**IN-MC-77**Counties:**PITTSBURG**Description:**BRIDGE AND APPROACHES

INDIAN NATION TURNPIKE: BRIDGE NO. 36.45 (MP 67.70)

OVER SH-31 AND UNION PACIFIC RAILROAD, 1.7 MILES

SOUTHEAST OF THE US-270 INTERCHANGE NEAR McALESTER.

PROJECT LENGTH = 0.394 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE		
0300 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	395.000	CY
0310 501(G)1800	CLSM BACKFILL	429.200	CY
0320 502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0330 504(A)5200	APPROACH SLAB	669.900	SY
0340 504(B)5300	SAW-CUT GROOVING	2,932.000	SY
0350 504(E)5520	42" F-SHAPED PARAPET	635.600	LF
0360 506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	1,089,740.000	LB
0370 507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	10.000	EA
0380 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	20.000	EA
0390 509(A)0210	CLASS AA CONCRETE	549.700	CY
0400 509(B)0320	CLASS A CONCRETE	361.500	CY
0410 509(D)0510	CLASS C CONCRETE	20.000	CY
0420 510(C)1450	SLOPE WALL (5")	1,125.000	SY
0430 510(D)1510	MSE RETAINING WALL	370.000	SY
0440 511 2100	MECHANICAL SPLICES	96.000	EA
0450 511(A)2210	REINFORCING STEEL	1,300.000	LB
0460 511(B)2310	EPOXY COATED REINFORCING STEEL	198,234.000	LB
0470 513(B)4300	CLASS B BRIDGE DECK REPAIR	100.000	SY
0480 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	863.000	SY
0490 516(A)8210	DRILLED SHAFTS 24" DIAMETER	186.000	LF
0500 516(A)8220	DRILLED SHAFTS 36" DIAMETER	665.000	LF
0510 516(A)8235	DRILLED SHAFTS 54" DIAMETER	156.000	LF
0520 516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0530 517 9110	ELASTOMERIC COATING	1,617.000	SF
0540 518(B)0300	SEALED EXPANSION JOINTS	171.670	LF
0550 523(A)3200	SEALER CRACK PREPARATION	600.000	LF
0560 523(B)3300	SEALER RESIN	6.600	GAL
0570 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	176.000	LF
0580 613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	46.000	LF
0590 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0600 622(A)0210	1 1/2" PIPE RAILING	232.000	LF
0610 624(E)3640	FENCE-STYLE CLF (8'HIGH, CLASS A)	204.000	LF

Proposal:260266**Let Date:**October 22, 2026**Call Order:**018**J/P Num:**36892(04)**Proj. Num:**IN-MC-77**Counties:**PITTSBURG**Description:**BRIDGE AND APPROACHES

INDIAN NATION TURNPIKE: BRIDGE NO. 36.45 (MP 67.70)

OVER SH-31 AND UNION PACIFIC RAILROAD, 1.7 MILES

SOUTHEAST OF THE US-270 INTERCHANGE NEAR McALESTER.

PROJECT LENGTH = 0.394 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003	TRAFFIC CONTROL		
0620 104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	150.000	DAY
0630 509(A)0200	CLASS AA CONCRETE	57.000	CY
0640 619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	1,841.000	LF
0650 628 7100	INSTALLATION OF CABLE BARRIER SYSTEM	2,089.000	LF
0660 628(C)7400	END ANCHORS	2.000	EA
0670 857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	30,653.000	LF
0680 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	750.000	LF
0690 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	750.000	LF
0700 880(A)6220	ARROW DISPLAY(TYPE C)	667.000	SD
0710 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	16,375.000	SD
0720 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,038.000	SD
0730 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	14,406.000	SD
0740 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,462.000	SD
0750 880(E)6600	WARNING LIGHTS(TYPE A)	9,454.000	SD
0760 880(F)6700	DRUMS	33,508.000	SD
0770 880(G)6800	TUBE CHANNELIZERS	23,100.000	SD
0780 880(I)7000	FLAGGER	120.000	SD
0790 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	674.000	HOURL
0800 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	702.000	SD
0004	SIGNING AND STRIPPING		
0810 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	12,702.000	LF
0820 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	43,352.000	LF
0005	TRAFFIC LIGHTING		
0830 802(A)0210	1" GALV.STEEL ELECT.COND. EXPOSED	437.000	LF
0840 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	60.000	LF
0850 802(E)0600	JUNCTION BOX(6" X 6" X 4")	9.000	EA
0860 803(A)1200	PULL BOX	1.000	EA
0870 809(B)7300	UNDERPASS LUMINAIRE	6.000	EA
0880 810(A)8200	SERVICE POLE	1.000	EA
0006	STAKING		
0890 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION		
0900 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0910 641 2100	MOBILIZATION	1.000	LSUM