

**Proposal:**260268**Let Date:**October 22, 2026**Call Order:**205**J/P Num:**33967(04)**Proj. Num:**STP-211D(090)CI**Counties:**CHEROKEE**Description:**GRADE, DRAIN, BRIDGE AND SURFACE

COUNTY ROAD (S 510 ROAD):

FROM THE INTERSECTION OF SOUTH INDIAN ROAD,

EXTEND SOUTHEAST NEAR PETTIT.

PROJECT LENGTH = 0.686 MILES

| <u>Line #</u>   | <u>Item Description</u>                  | <u>Quantity</u> | <u>Unit</u> |
|-----------------|------------------------------------------|-----------------|-------------|
| <b>0001</b>     | <b>ROADWAY</b>                           |                 |             |
| 0010 201(A)1200 | CLEARING AND GRUBBING                    | 1.000           | LSUM        |
| 0020 202(A)2200 | UNCLASSIFIED EXCAVATION                  | 2,541.000       | CY          |
| 0030 202(D)2500 | UNCLASSIFIED BORROW                      | 51,391.000      | CY          |
| 0040 205(A)6200 | TYPE A-SALVAGED TOPSOIL                  | 1.000           | LSUM        |
| 0050 221(B)2300 | TEMPORARY SILT FENCE                     | 5,305.000       | LF          |
| 0060 221(E)2600 | TEMPORARY SILT DIKE                      | 182.000         | LF          |
| 0070 230(A)7200 | SOLID SLAB SODDING                       | 32,053.000      | SY          |
| 0080 233(A)0200 | VEGETATIVE MULCHING                      | 9.340           | AC          |
| 0090 307(K)4200 | STABILIZED SUBGRADE                      | 11,991.000      | SY          |
| 0100 311(C)6400 | PROCESS EXISTING BASE & SURFACE,METHOD C | 2,580.000       | LF          |
| 0110 402(E)2600 | TRAFFIC BOUND SURFACE COURSE TYPE E      | 1,516.000       | TON         |
| 0120 407(B)7300 | TACK COAT                                | 738.000         | GAL         |
| 0130 408 8100   | PRIME COAT                               | 4,195.000       | GAL         |
| 0140 411(B)1330 | SUPERPAVE, TYPE S3(PG 64-22 OK)          | 2,241.000       | TON         |
| 0150 411(C)1430 | SUPERPAVE, TYPE S4(PG 64-22 OK)          | 1,196.000       | TON         |
| 0160 501(A)1200 | STRUCTURAL EXCAVATION UNCLASSIFIED       | 60.000          | CY          |
| 0170 509(A)0200 | CLASS AA CONCRETE                        | 287.950         | CY          |
| 0180 509(D)0500 | CLASS C CONCRETE                         | 12.000          | CY          |
| 0190 511(A)2200 | REINFORCING STEEL                        | 38,508.000      | LB          |
| 0200 601(A)1100 | TYPE I PLAIN RIPRAP                      | 568.000         | TON         |
| 0210 601(B)1200 | TYPE I PLAIN RIPRAP WITH FILTER BLANKET  | 192.000         | TON         |
| 0220 609(B)4360 | 2'-8" COMB.CRB.& GUT.(6" BARRIER)        | 1,032.000       | LF          |
| 0230 610(B)5300 | 6" CONCRETE DRIVEWAY (H.E.S.)            | 49.000          | SY          |
| 0240 613(A)5216 | 24" R.C.PIPE CLASS III                   | 212.000         | LF          |
| 0250 613(B)5500 | 12" CORR. GALV. STEEL PIPE               | 72.000          | LF          |
| 0260 613(B)5508 | 18" CORR. GALV. STEEL PIPE               | 26.000          | LF          |
| 0270 613(L)6700 | 12" PREFAB. CULVERT END SEC., ROUND      | 2.000           | EA          |
| 0280 613(L)6708 | 18" PREFAB. CULVERT END SEC., ROUND      | 2.000           | EA          |
| 0290 613(L)6716 | 24" PREFAB. CULVERT END SEC., ROUND      | 6.000           | EA          |
| 0300 619(A)6200 | REMOVAL OF STRUCTURES & OBSTRUCTIONS     | 1.000           | LSUM        |
| 0310 619(B)6352 | REMOVAL OF FENCE                         | 525.000         | LF          |
| 0320 619(B)6364 | REMOVAL OF ASPHALT PAVEMENT              | 8,900.000       | SY          |
| 0330 619(B)6380 | REMOVAL OF CONCRETE DRIVEWAY             | 19.000          | SY          |
| 0340 619(B)6440 | REMOVAL OF EXISTING PIPE                 | 214.000         | LF          |
| 0350 619(B)6472 | REMOVAL OF EXISTING SLAB                 | 322.000         | SY          |
| 0360 619(C)6600 | SAWING PAVEMENT                          | 143.000         | LF          |
| 0370 623(A)1200 | BEAM GUARDRAIL W-BEAM SINGLE             | 1,175.000       | LF          |
| 0380 623(F)1712 | GUARDRAIL ANCHOR UNIT (TYPE B)           | 8.000           | EA          |
| 0390 624(A)3200 | FENCE-STYLE WWF                          | 469.000         | LF          |
| 0400 624(H)3900 | (PL) GATE                                | 1.000           | EA          |
| 0410 629(A)7200 | MAILBOX INSTALLATION-SINGLE              | 1.000           | EA          |
| 0420 629(C)7400 | REMOVAL OF MAILBOX INSTALLATION          | 1.000           | EA          |
| 0430 629(E)7600 | MAILBOX                                  | 1.000           | EA          |

**Proposal:**260268**Let Date:**October 22, 2026**Call Order:**205**J/P Num:**33967(04)**Proj. Num:**STP-211D(090)CI**Counties:**CHEROKEE**Description:**GRADE, DRAIN, BRIDGE AND SURFACE

COUNTY ROAD (S 510 ROAD):

FROM THE INTERSECTION OF SOUTH INDIAN ROAD,

EXTEND SOUTHEAST NEAR PETTIT.

PROJECT LENGTH = 0.686 MILES

| <u>Line #</u>            | <u>Item Description</u>                        | <u>Quantity</u> | <u>Unit</u> |
|--------------------------|------------------------------------------------|-----------------|-------------|
| <b>0002 BRIDGE</b>       |                                                |                 |             |
| 0440 202(A)2210          | UNCLASSIFIED EXCAVATION                        | 140.000         | CY          |
| 0450 501(A)1210          | STRUCTURAL EXCAVATION UNCLASSIFIED             | 64.000          | CY          |
| 0460 501(C)1400          | SUBSTRUCTURE EXCAVATION ROCK                   | 450.000         | CY          |
| 0470 509(A)0210          | CLASS AA CONCRETE                              | 580.500         | CY          |
| 0480 511(A)2210          | REINFORCING STEEL                              | 96,560.000      | LB          |
| 0490 601(B)1210          | TYPE I PLAIN RIPRAP WITH FILTER BLANKET        | 135.000         | TON         |
| <b>0003 TRAFFIC</b>      |                                                |                 |             |
| 0500 805(A)3252          | (PL)REMOVAL OF EXISTING SIGNS                  | 2.000           | EA          |
| 0510 805(D)3528          | (PL)REMOVE & RESET EXISTING SIGNS              | 2.000           | EA          |
| 0520 823 6100            | (SP)PORTABLE TRAFFIC SIGNAL SYSTEM             | 480.000         | SD          |
| 0530 850(A)1200          | SHEET ALUMINUM SIGNS                           | 9.000           | SF          |
| 0540 856(A)8203          | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE) | 7,252.000       | LF          |
| 0550 857(A)9200          | CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)      | 1,200.000       | LF          |
| 0560 877(B)4300          | DELIVER PORTABLE LONGITUDINAL BARRIER          | 3,626.000       | LF          |
| 0570 877(C)4400          | RELOCATION OF PORT. LONGITUDINAL BARRIER       | 4,610.000       | LF          |
| 0580 880(B)6300          | CONSTRUCTION SIGNS 0 TO 6.25 SF                | 1,680.000       | SD          |
| 0590 880(B)6320          | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF         | 2,400.000       | SD          |
| 0600 880(C)6410          | CONSTRUCTION BARRICADES(TYPE III)              | 2,880.000       | SD          |
| 0610 880(E)6600          | WARNING LIGHTS(TYPE A)                         | 2,640.000       | SD          |
| 0620 880(F)6700          | DRUMS                                          | 3,600.000       | SD          |
| 0630 880(I)7000          | FLAGGER                                        | 60.000          | SD          |
| <b>0004 STAKING</b>      |                                                |                 |             |
| 0640 642(B)3300          | CONSTRUCTION STAKING LEVEL II                  | 1.000           | LSUM        |
| <b>0005 CONSTRUCTION</b> |                                                |                 |             |
| 0650 220 1100            | SWPPP DOCUMENTATION AND MANAGEMENT             | 1.000           | LSUM        |
| 0660 641 2110            | MOBILIZATION                                   | 1.000           | LSUM        |