

Proposal:260269

Let Date:October 22, 2026

Call Order:210

J/P Num:33502(04)

Proj. Num:STP-211C(108)CI

Counties:CHEROKEE

Description:GRADE, DRAIN, BRIDGE, AND SURFACE

COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	43,834.000	CY
0030 202(B)2300	MUCK EXCAVATION	700.000	CY
0040 202(C)2400	ROCK EXCAVATION	132,306.000	CY
0050 202(D)2500	UNCLASSIFIED BORROW	855.000	CY
0060 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0070 221(B)2300	TEMPORARY SILT FENCE	3,575.000	LF
0080 221(E)2600	TEMPORARY SILT DIKE	350.000	LF
0090 230(A)7200	SOLID SLAB SODDING	64,338.000	SY
0100 232(A)9200	SEEDING METHOD A	13.300	AC
0110 233(A)0200	VEGETATIVE MULCHING	8.590	AC
0120 241 3100	MOWING	17.180	AC
0130 303(A)1200	AGGREGATE BASE TYPE A	4,565.000	CY
0140 311(D)6500	PROCESS EXISTING BASE & SURFACE,METHOD D	4,980.000	LF
0150 325 0100	SEPARATOR FABRIC	24,108.000	SY
0160 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	5,846.000	TON
0170 407(B)7300	TACK COAT	1,557.000	GAL
0180 408 8100	PRIME COAT	13,006.000	GAL
0190 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,558.000	TON
0200 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,346.000	TON
0210 501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	38.000	CY
0220 509(A)0200	CLASS AA CONCRETE	159.000	CY
0230 509(D)0500	CLASS C CONCRETE	227.000	CY
0240 511(A)2200	REINFORCING STEEL	12,211.000	LB
0250 601(A)1100	TYPE I PLAIN RIPRAP	1,785.000	TON
0260 613(A)5378	58" X 36" R.C.PIPE ARCH CLASS A-III	74.000	LF
0270 613(B)5508	18" CORR. GALV. STEEL PIPE	1,040.000	LF
0280 613(B)5528	36" CORR. GALV. STEEL PIPE	32.000	LF
0290 613(B)5544	60" CORR. GALV. STEEL PIPE	34.000	LF
0300 613(B)5556	78" CORR. GALV. STEEL PIPE	432.000	LF
0310 613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	100.000	LF
0320 613(B)5616	35" X 24" CORR. GALV. STEEL PIPE ARCH	72.000	LF
0330 613(L)6664	58" X 36" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0340 613(M)6960	TYPE A4 CULVERT END TREATMENT	18.000	EA
0350 613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0360 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0370 619(B)6352	REMOVAL OF FENCE	4,607.000	LF
0380 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	12,119.000	SY
0390 619(B)6396	REMOVAL OF GUARDRAIL	203.000	LF
0400 619(B)6440	REMOVAL OF EXISTING PIPE	447.000	LF
0410 619(C)6600	SAWING PAVEMENT	246.000	LF
0420 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0430 623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0440 623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0450 624(A)3200	FENCE-STYLE WWF	1,777.000	LF
0460 624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	1,129.000	LF

Proposal:260269

Let Date:October 22, 2026

Call Order:210

J/P Num:33502(04)

Proj. Num:STP-211C(108)CI

Counties:CHEROKEE

Description:GRADE, DRAIN, BRIDGE, AND SURFACE

COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0470 624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	862.000	LF
0480 629(A)7200	MAILBOX INSTALLATION-SINGLE	7.000	EA
0490 629(C)7400	REMOVAL OF MAILBOX INSTALLATION	7.000	EA
0500 629(E)7600	MAILBOX	7.000	EA
0002	BRIDGE		
0510 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	300.000	CY
0520 501(F)1700	GRANULAR BACKFILL	538.000	CY
0530 504(A)5200	APPROACH SLAB	321.100	SY
0540 504(B)5300	SAW-CUT GROOVING	499.500	SY
0550 504(D)5410	CONCRETE RAIL (TR3)	267.000	LF
0560 506(A)7200	STRUCTURAL STEEL	39,990.000	LB
0570 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	5.000	EA
0580 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	5.000	EA
0590 509(A)0210	CLASS AA CONCRETE	58.900	CY
0600 509(B)0320	CLASS A CONCRETE	316.200	CY
0610 511(A)2210	REINFORCING STEEL	59,360.000	LB
0620 514(A)5240	PILES, FURNISHED (HP 14X73)	936.000	LF
0630 514(B)5340	PILES, DRIVEN (HP 14X73)	936.000	LF
0640 514(K)6200	(PL)PILOT HOLES	884.000	LF
0650 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0660 518(B)0300	SEALED EXPANSION JOINTS	54.080	LF
0670 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	356.000	TON
0680 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	164.000	LF
0690 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	69.000	LF
0700 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC		
0710 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
0720 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0730 850(A)1200	SHEET ALUMINUM SIGNS	16.610	SF
0740 851(C)2415	2" SQUARE TUBE POST	21.000	LF
0750 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0760 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	18,400.000	LF
0770 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	24.000	LF
0780 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	4,600.000	LF
0790 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,300.000	SD
0800 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	60.000	SD
0810 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,620.000	SD
0820 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,600.000	SD
0830 880(E)6600	WARNING LIGHTS(TYPE A)	8,100.000	SD
0840 880(G)6800	TUBE CHANNELIZERS	45,000.000	SD
0850 880(I)7000	FLAGGER	120.000	SD
0860 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	900.000	SD

Proposal:260269**Let Date:**October 22, 2026**Call Order:**210**J/P Num:**33502(04)**Proj. Num:**STP-211C(108)CI**Counties:**CHEROKEE**Description:**GRADE, DRAIN, BRIDGE, AND SURFACE

COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004	WATERLINE - INDIAN ROAD / CHEROKEE		
0870 616(D)2514	1" AIR RELIEF VALVE & VAULT	1.000	EA
0880 616(D)2568	2" VALVES	3.000	EA
0890 616(D)2740	2" TAPPING SLEEVE	1.000	EA
0900 616(G)3130	2" FLUSH HYDRANT	1.000	EA
0910 616(I)3368	6" HDPE CASING	180.000	LF
0920 616(J)3467	10" DIRECTIONAL BORE	180.000	LF
0930 616(M)3700	INSTALL WATER LINE	1.000	LSUM
0940 616(N)3800	SERVICE CONNECTION (SHORT)	3.000	EA
0950 616(N)3810	WET CONNECTION (2")	1.000	EA
0960 616(O)3935	2" 90 DEGREE FITTING	2.000	EA
0970 616(P)4108	2" HDPE PIPE	2,060.000	LF
0980 616(T)4490	2" TEE	1.000	EA
0990 616(U)4698	2" MECHANICAL JOINT RESTRAINT	10.000	EA
1000 616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
1010 616(V)4810	PRESSURE AND LEAKAGE TEST	2,125.000	LF
0005	WATERLINE - INDIAN ROAD / STICKCROSS MOUNTAIN		
1020 616(D)2576	4" VALVES	2.000	EA
1030 616(D)2744	4" X 4" TAPPING SLEEVE	2.000	EA
1040 616(I)3369	8" HDPE CASING	140.000	LF
1050 616(J)3467	10" DIRECTIONAL BORE	180.000	LF
1060 616(M)3700	INSTALL WATER LINE	1.000	LSUM
1070 616(N)3800	SERVICE CONNECTION (SHORT)	2.000	EA
1080 616(N)3815	WET CONNECTION (4")	2.000	EA
1090 616(P)4128	4" HDPE PIPE	600.000	LF
1100 616(Q)4205	4" 45 DEGREE BEND	8.000	EA
1110 616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
1120 616(V)4810	PRESSURE AND LEAKAGE TEST	670.000	LF
0006	STAKING		
1130 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION		
1140 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1150 641 2110	MOBILIZATION	1.000	LSUM