Proposal:260269 **Let Date:**January 21, 2027 **Call Order:**608
J/P Num:33502(04) **Proj. Num:**STP-211C(108)CI
Counties:CHEROKEE
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	43,834.000	CY
0030	202(B)2300	MUCK EXCAVATION	700.000	CY
0040	202(C)2400	ROCK EXCAVATION	132,306.000	CY
0050	202(D)2500	UNCLASSIFIED BORROW	855.000	CY
0060	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0070	221(B)2300	TEMPORARY SILT FENCE	3,575.000	LF
0080	221(E)2600	TEMPORARY SILT DIKE	350.000	LF
0090	230(A)7200	SOLID SLAB SODDING	64,338.000	SY
0100	232(A)9200	SEEDING METHOD A	13.300	AC
0110	233(A)0200	VEGETATIVE MULCHING	8.590	AC
0120	241 3100	MOWING	17.180	AC
0130	303(A)1200	AGGREGATE BASE TYPE A	4,565.000	CY
0140	311(D)6500	PROCESS EXISTING BASE & SURFACE,METHOD D	4,980.000	LF
0150	325 0100	SEPARATOR FABRIC	24,108.000	SY
0160	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	5,846.000	TON
0170	407(B)7300	TACK COAT	1,557.000	GAL
0180	408 8100	PRIME COAT	13,006.000	GAL
0190	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	4,558.000	TON
0200	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	2,346.000	TON
0210	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	38.000	CY
0220	509(A)0200	CLASS AA CONCRETE	159.000	CY
0230	509(D)0500	CLASS C CONCRETE	227.000	CY
0240	511(A)2200	REINFORCING STEEL	12,211.000	LB
0250	601(A)1100	TYPE I PLAIN RIPRAP	1,785.000	TON
0260	613(A)5378	58" X 36" R.C.PIPE ARCH CLASS A-III	74.000	LF
0270	613(B)5508	18" CORR. GALV. STEEL PIPE	1,040.000	LF
0280	613(B)5528	36" CORR. GALV. STEEL PIPE	32.000	LF
0290	613(B)5544	60" CORR. GALV. STEEL PIPE	34.000	LF
0300	613(B)5556	78" CORR. GALV. STEEL PIPE	432.000	LF
0310	613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	100.000	LF
0320	613(B)5616	35" X 24" CORR. GALV. STEEL PIPE ARCH	72.000	LF
0330	613(L)6664	58" X 36" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0340	613(M)6960	TYPE A4 CULVERT END TREATMENT	18.000	EA
0350	613(M)6964	TYPE B4 CULVERT END TREATMENT	2.000	EA
0360	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0370	619(B)6352	REMOVAL OF FENCE	4,607.000	LF
0380	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	12,119.000	SY
0390	619(B)6396	REMOVAL OF GUARDRAIL	203.000	LF
0400	619(B)6440	REMOVAL OF EXISTING PIPE	447.000	LF
0410	619(C)6600	SAWING PAVEMENT	246.000	LF
0420	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0430	623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0440	623(G)1800	GUARDRAIL END TREATMENT (GET)	4.000	EA
0450	624(A)3200	FENCE-STYLE WWF	1,777.000	LF
0460	624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	1,129.000	LF

Proposal:260269 **Let Date:**January 21, 2027 **Call Order:**608
J/P Num:33502(04) **Proj. Num:**STP-211C(108)CI
Counties:CHEROKEE
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0470	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	862.000	LF
0480	629(A)7200	MAILBOX INSTALLATION-SINGLE	7.000	EA
0490	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	7.000	EA
0500	629(E)7600	MAILBOX	7.000	EA
0002	BRIDGE			
0510	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	300.000	CY
0520	501(F)1700	GRANULAR BACKFILL	538.000	CY
0530	504(A)5200	APPROACH SLAB	321.100	SY
0540	504(B)5300	SAW-CUT GROOVING	499.500	SY
0550	504(D)5410	CONCRETE RAIL (TR3)	267.000	LF
0560	506(A)7200	STRUCTURAL STEEL	39,990.000	LB
0570	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	5.000	EA
0580	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	5.000	EA
0590	509(A)0210	CLASS AA CONCRETE	58.900	CY
0600	509(B)0320	CLASS A CONCRETE	316.200	CY
0610	511(A)2210	REINFORCING STEEL	59,360.000	LB
0620	514(A)5240	PILES, FURNISHED (HP 14X73)	936.000	LF
0630	514(B)5340	PILES, DRIVEN (HP 14X73)	936.000	LF
0640	514(K)6200	(PL)PILOT HOLES	884.000	LF
0650	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0660	518(B)0300	SEALED EXPANSION JOINTS	54.080	LF
0670	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	356.000	TON
0680	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	164.000	LF
0690	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	69.000	LF
0700	619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	TRAFFIC			
0710	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
0720	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0730	850(A)1200	SHEET ALUMINUM SIGNS	16.610	SF
0740	851(C)2415	2" SQUARE TUBE POST	21.000	LF
0750	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0760	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	18,400.000	LF
0770	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	24.000	LF
0780	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	4,600.000	LF
0790	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,300.000	SD
0800	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	60.000	SD
0810	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,620.000	SD
0820	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	3,600.000	SD
0830	880(E)6600	WARNING LIGHTS(TYPE A)	8,100.000	SD
0840	880(G)6800	TUBE CHANNELIZERS	45,000.000	SD
0850	880(I)7000	FLAGGER	120.000	SD
0860	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	900.000	SD

Proposal:260269 **Let Date:**January 21, 2027 **Call Order:**608
J/P Num:33502(04) **Proj. Num:**STP-211C(108)CI
Counties:CHEROKEE
Description:GRADE, DRAIN, BRIDGE, AND SURFACE
COUNTY ROAD (SOUTH INDIAN ROAD): FROM 3.6 MILES SOUTH
OF THE SH-82 JUNCTION, EXTEND NORTH NEAR LAKE TENKILLER.
PROJECT LENGTH = 0.871 MILES

Line #		Item Description	Quantity	Unit
0004	WATERLINE - INDIAN ROAD / CHEROKEE			
0870	616(D)2514	1" AIR RELIEF VALVE & VAULT	1.000	EA
0880	616(D)2568	2" VALVES	3.000	EA
0890	616(D)2740	2" TAPPING SLEEVE	1.000	EA
0900	616(G)3130	2” FLUSH HYDRANT	1.000	EA
0910	616(I)3368	6" HDPE CASING	180.000	LF
0920	616(J)3467	10” DIRECTIONAL BORE	180.000	LF
0930	616(M)3700	INSTALL WATER LINE	1.000	LSUM
0940	616(N)3800	SERVICE CONNECTION (SHORT)	3.000	EA
0950	616(N)3810	WET CONNECTION (2")	1.000	EA
0960	616(O)3935	2" 90 DEGREE FITTING	2.000	EA
0970	616(P)4108	2" HDPE PIPE	2,060.000	LF
0980	616(T)4490	2" TEE	1.000	EA
0990	616(U)4698	2" MECHANICAL JOINT RESTRAINT	10.000	EA
1000	616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
1010	616(V)4810	PRESSURE AND LEAKAGE TEST	2,125.000	LF
0005	WATERLINE - INDIAN ROAD / STICKROSS MOUNTAIN			
1020	616(D)2576	4" VALVES	2.000	EA
1030	616(D)2744	4" X 4" TAPPING SLEEVE	2.000	EA
1040	616(I)3369	8" HDPE CASING	140.000	LF
1050	616(J)3467	10” DIRECTIONAL BORE	180.000	LF
1060	616(M)3700	INSTALL WATER LINE	1.000	LSUM
1070	616(N)3800	SERVICE CONNECTION (SHORT)	2.000	EA
1080	616(N)3815	WET CONNECTION (4")	2.000	EA
1090	616(P)4128	4" HDPE PIPE	600.000	LF
1100	616(Q)4205	4" 45 DEGREE BEND	8.000	EA
1110	616(V)4800	HYDROSTATIC PRESSURE TESTING & DISINFECT	1.000	LSUM
1120	616(V)4810	PRESSURE AND LEAKAGE TEST	670.000	LF
0006	STAKING			
1130	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION			
1140	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1150	641 2110	MOBILIZATION	1.000	LSUM