

Proposal:260274

Let Date:October 22, 2026

Call Order:245

J/P Num:33860(07)

Proj. Num:STP-255F(770)PM

Counties:OKLAHOMA

Description:TRAFFIC SIGNING

I-44: AT MULTIPLE LOCATIONS IN
OKLAHOMA CITY.

PROJECT LENGTH= 12.09 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	TRAFFIC SIGNING AND STRIPING		
0010 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	55.000	TON
0020 509(A)0200	CLASS AA CONCRETE	11.200	CY
0030 509(D)0500	CLASS C CONCRETE	34.150	CY
0040 511(A)2200	REINFORCING STEEL	1,885.000	LB
0050 516(A)8230	DRILLED SHAFTS 48" DIAMETER	128.000	LF
0060 516(A)8235	DRILLED SHAFTS 54" DIAMETER	396.000	LF
0070 516(A)8240	DRILLED SHAFTS 60" DIAMETER	127.000	LF
0080 619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	425.000	LF
0090 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	440.000	LF
0100 623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	2.000	EA
0110 623(G)1800	GUARDRAIL END TREATMENT (GET)	3.000	EA
0120 627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	425.000	LF
0130 805(A)3236	(PL)REMOVAL OF OVERHEAD SIGN STRUCTURE	9.000	EA
0140 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	25.000	EA
0150 805(D)3536	(PL)REMOVE & RESET GROUND MOUNTED SIGN	1.000	EA
0160 850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	4,913.500	SF
0170 852(D)3582	OVHD.SN.STR., MONOTUBE B12	1.000	EA
0180 852(D)3584	OVHD.SN.STR., MONOTUBE B14	1.000	EA
0190 852(D)3587	OVHD.SN.STR., MONOTUBE B17	2.000	EA
0200 852(D)3590	OVHD.SN.STR., MONOTUBE B20	3.000	EA
0210 852(E)3623	OVHD.SN.STR., MONOTUBE C3	2.000	EA
0220 852(E)3624	OVHD.SN.STR., MONOTUBE C4	1.000	EA
0230 852(E)3626	OVHD.SN.STR., MONOTUBE C6	2.000	EA
0240 852(E)3629	OVHD.SN.STR., MONOTUBE C9	1.000	EA
0250 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	9.000	EA
0260 870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	95.000	EA
0002	TEMPORARY TRAFFIC CONTROL		
0270 876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	400.000	SD
0280 880(A)6220	ARROW DISPLAY(TYPE C)	150.000	SD
0290 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,900.000	SD
0300 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,200.000	SD
0310 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,800.000	SD
0320 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	900.000	SD
0330 880(E)6600	WARNING LIGHTS(TYPE A)	5,400.000	SD
0340 880(E)6616	WARNING LIGHTS(TYPE D)	7,500.000	SD
0350 880(F)6700	DRUMS	7,500.000	SD
0360 880(G)6805	CHANNELIZER CONES	19,500.000	SD
0370 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	3,000.000	hour
0380 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	600.000	SD
0003	STAKING		
0390 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0004	CONSTRUCTION		
0400 641 2100	MOBILIZATION	1.000	LSUM