

Proposal:260276
J/P Num:38035(04)
Counties:OSAGE

Let Date:October 22, 2026
Proj. Num:TAP-257D(097)TP

Call Order:265

Description:PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
 CITY STREET (EAST BROADWAY): FROM THE INTERSECTION OF LAKE DRIVE,
 EXTEND WEST IN THE TOWN OF PRUE.
 PROJECT LENGTH = 0.092 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 202(A)2200	UNCLASSIFIED EXCAVATION	222.000	CY
0020 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0030 221(E)2600	TEMPORARY SILT DIKE	35.000	LF
0040 230(A)7200	SOLID SLAB SODDING	1,131.000	SY
0050 303(A)1200	AGGREGATE BASE TYPE A	3.000	CY
0060 509(D)0500	CLASS C CONCRETE	7.000	CY
0070 610(A)5200	4" CONCRETE SIDEWALK	222.000	SY
0080 610(B)5310	6" CONCRETE DRIVEWAY	14.000	SY
0090 610(I)6000	TACTILE WARNING DEVICE-NEW	52.000	SF
0100 613(E)5961	12" CORRUGATED POLYPROPYLENE PIPE	32.000	LF
0110 613(E)5965	15" CORRUGATED POLYPROPYLENE PIPE	16.000	LF
0120 613(T)7800	STANDARD BEDDING MATERIAL, CLASS C	31.000	CY
0002	TRAFFIC - BASE BID		
0130 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0140 850(A)1200	SHEET ALUMINUM SIGNS	35.000	SF
0150 851(C)2420	2 1/4" SQUARE TUBE POST	48.000	LF
0160 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	144.000	LF
0170 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	270.000	SD
0003	TRAFFIC - ADD ALTERNATE #1		
0180 850(A)1200	SHEET ALUMINUM SIGNS	18.000	SF
0190 851(C)2420	2 1/4" SQUARE TUBE POST	24.000	LF
0004	TRAFFIC - ADD ALTERNATE #2		
0200 850(A)1200	SHEET ALUMINUM SIGNS	18.000	SF
0210 851(C)2420	2 1/4" SQUARE TUBE POST	24.000	LF
0005	TRAFFIC - ADD ALTERNATE #3		
0220 836 7110	RECTANGULAR RAPID FLASHING BEACON	2.000	EA
0006	TRAFFIC - ADD ALTERNATE #4		
0230 836 7110	RECTANGULAR RAPID FLASHING BEACON	2.000	EA
0007	STAKING		
0240 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION		
0250 641 2110	MOBILIZATION	1.000	LSUM