

Proposal:260280
J/P Num:35808(04)
Counties:LOGAN

Let Date:October 15, 2026
Proj. Num:STP-242B(131)PM

Call Order:127

Description:INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010	201(A)1200 CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200 UNCLASSIFIED EXCAVATION	8,431.000	CY
0030	202(D)2500 UNCLASSIFIED BORROW	3,231.000	CY
0040	205(A)6200 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300 TEMPORARY SILT FENCE	2,856.000	LF
0060	221(E)2600 TEMPORARY SILT DIKE	182.000	LF
0070	221(F)2710 TEMPORARY ROCK FILTER DAM TYPE 2	36.150	CY
0080	230(A)7200 SOLID SLAB SODDING	38,890.000	SY
0090	232(B)9300 SEEDING METHOD B	8.030	AC
0100	233(E)0600 (SP) HYDROMULCH	38,888.000	SY
0110	241 3100 MOWING	16.070	AC
0120	307(K)4200 STABILIZED SUBGRADE	10,625.000	SY
0130	402(E)2600 TRAFFIC BOUND SURFACE COURSE TYPE E	367.000	TON
0140	407(B)7300 TACK COAT	1,537.000	GAL
0150	408 8100 PRIME COAT	3,719.000	GAL
0160	409(A)9200 FABRIC REINFORCEMENT	1,721.000	SY
0170	409(B)9300 BITUMINOUS BINDER	688.400	GAL
0180	411(L)2404 BMD, TYPE B3 (PG 64-22 OK)	2,512.000	TON
0190	411(L)2408 BMD, TYPE B3 (PG 70-28 OK)	599.000	TON
0200	411(L)2424 BMD, TYPE B4 (PG 64-22 OK)	615.000	TON
0210	411(L)2428 BMD, TYPE B4 (PG 70-28 OK)	977.000	TON
0220	412 3100 COLD MILLING PAVEMENT	5,160.000	SY
0230	501(A)1200 STRUCTURAL EXCAVATION UNCLASSIFIED	35.000	CY
0240	509(A)0200 CLASS AA CONCRETE	27.000	CY
0250	511(A)2200 REINFORCING STEEL	4,072.000	LB
0260	602(B)2310 REVETMENT MATTRESSES	1,278.000	SY
0270	619(A)6200 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0280	619(B)6360 REMOVAL OF CONCRETE PAVEMENT	324.000	SY
0290	619(B)6364 REMOVAL OF ASPHALT PAVEMENT	5,484.000	SY
0300	619(B)6396 REMOVAL OF GUARDRAIL	1,510.000	LF
0310	619(B)6436 REMOVAL OF CONCRETE DITCH LINER	883.000	LF
0320	619(C)6600 SAWING PAVEMENT	3,870.000	LF
0330	624(C)3405 FENCE-STYLE SWF (5 BARBED WIRE)	563.000	LF

Proposal:260280
J/P Num:35808(04)
Counties:LOGAN

Let Date:October 15, 2026
Proj. Num:STP-242B(131)PM

Call Order:127

Description:INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002 SIGNING AND STRIPING			
0340 413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	2,690.000	LF
0350 413(B)4300	RUMBLE STRIP-METHOD HMA-CYC GROUP	3.000	EAGP
0360 413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	3,694.000	LF
0370 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	9.000	EA
0380 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0390 850(A)1200	SHEET ALUMINUM SIGNS	133.190	SF
0400 851(B)2325	4"@10.79 GALV.STL.PIPE POST	75.000	LF
0410 851(C)2420	2 1/4" SQUARE TUBE POST	140.000	LF
0420 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	13,586.000	LF
0430 856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	440.000	LF
0440 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	34.000	LF
0450 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	12.000	EA
0003 SIGNAL (INTERSECTION CONFLICT WARNING SYSTEM)			
0460 802(A)0230	1 1/2" GALV. STEEL ELECT COND EXPOSED	10.000	LF
0470 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,170.000	LF
0480 802(B)0356	3" PVC SCH. 80 PLASTIC CONDUIT BORED	350.000	LF
0490 803(A)1230	PULL BOX(SIZE III)	3.000	EA
0500 811 9130	1/C NO.10 ELECT.COND.	570.000	LF
0510 824(D)7500	(SP)COMMUNICATION CABINET, POLE MOUNTED	1.000	EA
0520 828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0530 831 3104	1WAY1SEC.ADJ.SIG.HD.S-8	8.000	EA
0540 833 5100	BACKPLATE	8.000	EA
0550 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,220.000	LF
0560 834(C)6410	UNDERGROUND COMMUNICATION CABLE	1,495.000	LF
0570 836 7100	REGULATORY OR WARNING SIGN ASSEMBLY	4.000	EA
0004 TRAFFIC LIGHTING			
0580 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	140.000	LF
0590 802(B)0356	3" PVC SCH. 80 PLASTIC CONDUIT BORED	170.000	LF
0600 803(A)1210	PULL BOX(SIZE I)	2.000	EA
0610 803(A)1230	PULL BOX(SIZE III)	2.000	EA
0620 804(A)2200	STRUCTURAL CONCRETE	3.280	CY
0630 804(B)2300	REINFORCING STEEL	568.000	LB
0640 805(A)3228	(PL)REMOVAL OF LIGHT POLE	1.000	EA
0650 806(C)4512	40' MTG & 10' HLMA(G.STL.)	2.000	EA
0660 807 5120	BREAKAWAY BASE (DES. B)	2.000	EA
0670 809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0680 810(A)8200	SERVICE POLE	1.000	EA
0690 811 9120	1/C NO.6 ELECT.COND.	915.000	LF
0700 811 9135	1/C NO.12 ELECT.COND.	220.000	LF

Proposal:260280
J/P Num:35808(04)
Counties:LOGAN

Let Date:October 15, 2026
Proj. Num:STP-242B(131)PM

Call Order:127

Description:INTERSECTION MODIFICATION
SH-33: FROM 3.8 MILES WEST OF THE US-77 INTERSECTION,
EXTEND EAST NEAR GUTHRIE.
PROJECT LENGTH = 0.366 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0005 TRAFFIC CONTROL			
0710 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	24,584.000	LF
0720 857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	36,674.000	LF
0730 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	265.000	EA
0740 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	227.000	EA
0750 871(B)2300	CONST.ZONE IMPACT ATTEN.	960.000	SD
0760 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,091.000	LF
0770 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,091.000	LF
0780 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	10,410.000	SD
0790 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	9,780.000	SD
0800 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,090.000	SD
0810 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	480.000	SD
0820 880(E)6607	WARNING LIGHTS(TYPE B)	7,770.000	SD
0830 880(E)6616	WARNING LIGHTS(TYPE D)	6,900.000	SD
0840 880(F)6700	DRUMS	6,900.000	SD
0850 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,854.000	SD
0006 STAKING			
0860 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007 CONSTRUCTION			
0870 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0880 641 2110	MOBILIZATION	1.000	LSUM