

Proposal:260281**Let Date:**October 15, 2026**Call Order:**162**J/P Num:**35441(04)**Proj. Num:**STP-263C(115)CI**Counties:**POTTAWATOMIE**Description:**WIDEN, RESURFACE, AND BRIDGE

COUNTY ROAD (MOCCASIN TRAIL / EW 109 ROAD):
 FROM 6.92 MILES EAST OF THE SH-18 INTERSECTION,
 EXTEND EAST NEAR PRAGUE.
 PROJECT LENGTH = 4.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	33,121.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 221(B)2300	TEMPORARY SILT FENCE	24,425.000	LF
0050 221(E)2600	TEMPORARY SILT DIKE	2,044.000	LF
0060 221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	1,725.000	CY
0070 230(A)7200	SOLID SLAB SODDING	52,654.000	SY
0080 233(A)0200	VEGETATIVE MULCHING	10.880	AC
0090 303(A)1200	AGGREGATE BASE TYPE A	6,080.000	CY
0100 325 0100	SEPARATOR FABRIC	16,189.000	SY
0110 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	734.000	TON
0120 407(B)7300	TACK COAT	5,536.000	GAL
0130 408 8100	PRIME COAT	22,493.000	GAL
0140 409(A)9200	FABRIC REINFORCEMENT	14,087.000	SY
0150 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	5,919.000	TON
0160 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	11,586.000	TON
0170 411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	202.000	TON
0180 412 3100	COLD MILLING PAVEMENT	48,992.000	SY
0190 509(A)0200	CLASS AA CONCRETE	5.000	CY
0200 509(D)0500	CLASS C CONCRETE	50.000	CY
0210 511(A)2200	REINFORCING STEEL	351.000	LB
0220 601(A)1100	TYPE I PLAIN RIPRAP	100.000	TON
0230 611(G)7974	INLET GPI TYPE 2 (DES. 11A)	2.000	EA
0240 613(B)5508	18" CORR. GALV. STEEL PIPE	737.000	LF
0250 613(B)5516	24" CORR. GALV. STEEL PIPE	309.000	LF
0260 613(B)5524	30" CORR. GALV. STEEL PIPE	193.000	LF
0270 613(B)5536	48" CORR. GALV. STEEL PIPE	30.000	LF
0280 613(B)5552	72" CORR. GALV. STEEL PIPE	60.000	LF
0290 613(B)5624	49" X 33" CORR. GALV. STEEL PIPE ARCH	27.000	LF
0300 613(L)6652	49" X 33" PREFAB. CULVERT END SEC., ARCH	2.000	EA
0310 613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	42.000	EA
0320 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	14.000	EA
0330 613(L)6724	30" PREFAB. CULVERT END SEC., ROUND	12.000	EA
0340 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0350 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	295.000	SY
0360 619(C)6600	SAWING PAVEMENT	15,848.000	LF
0370 624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	1,020.000	LF
0380 624(D)3500	GATE, GALVANIZED STEEL	1.000	EA
0390 629(D)7500	REMOVE AND RESET MAILBOX	17.000	EA

Proposal:260281**Let Date:**October 15, 2026**Call Order:**162**J/P Num:**35441(04)**Proj. Num:**STP-263C(115)CI**Counties:**POTTAWATOMIE**Description:**WIDEN, RESURFACE, AND BRIDGE

COUNTY ROAD (MOCCASIN TRAIL / EW 109 ROAD):
 FROM 6.92 MILES EAST OF THE SH-18 INTERSECTION,
 EXTEND EAST NEAR PRAGUE.
 PROJECT LENGTH = 4.015 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE 'A' - NBI NO. 33462		
0400 202(A)2210	UNCLASSIFIED EXCAVATION	3,340.000	CY
0410 501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	334.000	CY
0420 502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0430 509(A)0210	CLASS AA CONCRETE	669.400	CY
0440 511(A)2210	REINFORCING STEEL	97,450.000	LB
0450 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003	SIGNING AND STRIPING		
0460 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0470 850(A)1200	SHEET ALUMINUM SIGNS	121.000	SF
0480 851(C)2415	2" SQUARE TUBE POST	276.000	LF
0490 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	85,050.000	LF
0500 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	2.000	EA
0004	TRAFFIC CONTROL		
0510 857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	2,400.000	LF
0520 871(B)2300	CONST.ZONE IMPACT ATTEN.	360.000	SD
0530 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	988.000	LF
0540 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	5,760.000	SD
0550 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,880.000	SD
0560 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,320.000	SD
0570 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,920.000	SD
0580 880(E)6600	WARNING LIGHTS(TYPE A)	7,920.000	SD
0590 880(F)6700	DRUMS	3,600.000	SD
0600 880(G)6805	CHANNELIZER CONES	36,000.000	SD
0610 880(I)7000	FLAGGER	480.000	SD
0620 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	480.000	SD
0005	STAKING		
0630 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION		
0640 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0650 641 2110	MOBILIZATION	1.000	LSUM