

Proposal:260282**Let Date:**October 15, 2026**Call Order:**164**J/P Num:**32365(04)**Proj. Num:**STP-264C(116)CI**Counties:**PUSHMATAHA**Description:**BRIDGE AND APPROACHES

COUNTY ROAD (N 4443 ROAD): OVER LITTLE RIVER,
 0.50 MILES SOUTH OF THE SH-144 JUNCTION NEAR ANTLERS.
 PROJECT LENGTH = 0.435 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	10,670.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 210 0100	OBLITERATING ABANDONED ROAD	1,417.000	LF
0050 221(B)2300	TEMPORARY SILT FENCE	651.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	119.000	LF
0070 230(A)7200	SOLID SLAB SODDING	13,066.000	SY
0080 233(A)0200	VEGETATIVE MULCHING	2.700	AC
0090 303(A)1200	AGGREGATE BASE TYPE A	1,289.000	CY
0100 325 0100	SEPARATOR FABRIC	6,323.000	SY
0110 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	914.000	TON
0120 407(B)7300	TACK COAT	375.000	GAL
0130 408 8100	PRIME COAT	4,077.000	GAL
0140 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	852.000	TON
0150 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	588.000	TON
0160 412 3100	COLD MILLING PAVEMENT	1,637.000	SY
0170 509(D)0500	CLASS C CONCRETE	54.000	CY
0180 613(B)5516	24" CORR. GALV. STEEL PIPE	164.000	LF
0190 613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	10.000	EA
0200 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0210 619(C)6600	SAWING PAVEMENT	79.000	LF
0220 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0230 623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000	EA
0240 623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0250 624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	2,406.000	LF

Proposal:260282

Let Date:October 15, 2026

Call Order:164

J/P Num:32365(04)

Proj. Num:STP-264C(116)CI

Counties:PUSHMATAHA

Description:BRIDGE AND APPROACHES

COUNTY ROAD (N 4443 ROAD): OVER LITTLE RIVER,
0.50 MILES SOUTH OF THE SH-144 JUNCTION NEAR ANTLERS.
PROJECT LENGTH = 0.435 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002 BRIDGE			
0260 202(A)2210	UNCLASSIFIED EXCAVATION	120.000	CY
0270 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	190.000	CY
0280 501(F)1700	GRANULAR BACKFILL	88.000	CY
0290 503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,196.000	LF
0300 504(B)5300	SAW-CUT GROOVING	976.000	SY
0310 504(D)5410	CONCRETE RAIL (TR3)	866.400	LF
0320 506(A)7200	STRUCTURAL STEEL	1,560.000	LB
0330 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0340 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0350 509(A)0210	CLASS AA CONCRETE	309.100	CY
0360 509(B)0320	CLASS A CONCRETE	144.200	CY
0370 511(A)2210	REINFORCING STEEL	90,410.000	LB
0380 514(A)5210	PILES, FURNISHED (HP 10X42)	94.000	LF
0390 514(A)5220	PILES, FURNISHED (HP 12X53)	281.000	LF
0400 514(B)5310	PILES, DRIVEN (HP 10X42)	94.000	LF
0410 514(B)5320	PILES, DRIVEN (HP 12X53)	281.000	LF
0420 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0430 516(A)8230	DRILLED SHAFTS 48" DIAMETER	126.000	LF
0440 516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0450 518(B)0300	SEALED EXPANSION JOINTS	58.340	LF
0460 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	2,185.000	TON
0470 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
0480 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	64.000	LF
0490 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0003 TRAFFIC			
0500 850(A)1200	SHEET ALUMINUM SIGNS	102.000	SF
0510 851(C)2415	2" SQUARE TUBE POST	302.000	LF
0520 853 5110	DELINEATORS(TYPE 1, CODE 3)	4.000	EA
0530 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	12.000	EA
0540 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	9,200.000	LF
0550 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,160.000	SD
0560 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	960.000	SD
0570 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,680.000	SD
0580 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,400.000	SD
0590 880(E)6600	WARNING LIGHTS(TYPE A)	2,400.000	SD
0004 STAKING			
0600 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005 CONSTRUCTION			
0610 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0620 641 2110	MOBILIZATION	1.000	LSUM