

Proposal:260284
J/P Num:38973(04)
Counties:NOBLE

Let Date:October 22, 2026
Proj. Num:C-MC-46

Call Order:012

Description:BRIDGE REHABILITATION

CIMMARON TURNPIKE / US 412 (OTA ACCESS): OVER TRIBUTARY
TO RED ROCK CREEK, 1.11 MILES EAST OF US-77 NEAR PERRY.
PROJECT LENGTH= 0.413 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 202(A)2200	UNCLASSIFIED EXCAVATION	50.000	CY
0020 202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 221(B)2300	TEMPORARY SILT FENCE	1,200.000	LF
0050 230(A)7200	SOLID SLAB SODDING	4,000.000	SY
0060 310(B)5300	SUBGRADE, METHOD B	1,667.000	SY
0070 408 8100	PRIME COAT	1,239.000	GAL
0080 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	93.000	TON
0090 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	1,667.000	SY
0100 414(G)5800	P.C. CONCRETE FOR PAVEMENT	417.000	CY
0110 619(B)6352	REMOVAL OF FENCE	225.000	LF
0120 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,948.000	SY
0130 619(B)6396	REMOVAL OF GUARDRAIL	530.000	LF
0140 619(B)6436	REMOVAL OF CONCRETE DITCH LINER	181.000	LF
0150 619(C)6600	SAWING PAVEMENT	2,000.000	LF
0160 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	475.000	LF
0170 623(G)1820	GUARDRAIL END TREATMENT (31")	2.000	EA
0180 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0190 624(C)3400	FENCE-STYLE SWF (4 BARBED WIRE)	230.000	LF
0200 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	13.000	EA
0002	BRIDGE "A"		
0210 501(G)1800	CLSM BACKFILL	222.000	CY
0220 504(A)5200	APPROACH SLAB	731.200	SY
0230 504(B)5300	SAW-CUT GROOVING	1,637.300	SY
0240 504(E)5520	42" F-SHAPED PARAPET	355.000	LF
0250 506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	348,460.000	LB
0260 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	12.000	EA
0270 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	12.000	EA
0280 509(A)0210	CLASS AA CONCRETE	222.700	CY
0290 509(D)0510	CLASS C CONCRETE	10.000	CY
0300 511(B)2310	EPOXY COATED REINFORCING STEEL	51,990.000	LB
0310 513(B)4300	CLASS B BRIDGE DECK REPAIR	15.000	SY
0320 513(C)4400	CLASS C BRIDGE DECK REPAIR	5.000	SY
0330 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,076.000	SY
0340 517 9110	ELASTOMERIC COATING	666.000	SF
0350 518(B)0310	EXPANSION JOINT SYSTEM	85.000	LF
0360 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	79.000	LF
0370 520(C)1400	EPOXY RESIN, ABOVE WATER	6.400	GAL
0380 521(A)2200	PNEUMATICALLY PLACED MORTAR	5.200	SY
0390 523(A)3200	SEALER CRACK PREPARATION	188.000	LF
0400 523(B)3300	SEALER RESIN	2.200	GAL
0410 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	8.200	SY
0420 619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260284
J/P Num:38973(04)
Counties:NOBLE

Let Date:October 22, 2026
Proj. Num:C-MC-46

Call Order:012

Description:BRIDGE REHABILITATION

CIMMARON TURNPIKE / US 412 (OTA ACCESS): OVER TRIBUTARY
 TO RED ROCK CREEK, 1.11 MILES EAST OF US-77 NEAR PERRY.
 PROJECT LENGTH= 0.413 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 TRAFFIC			
0430 619(B)6432	REMOVAL OF CABLE BARRIER	2,427.000	LF
0440 628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	2,370.000	LF
0450 628(C)7400	END ANCHORS	4.000	EA
0460 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	2.000	EA
0470 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	25,200.000	LF
0480 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,200.000	LF
0004 TRAFFIC CONTROL			
0490 857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	31,420.000	LF
0500 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	469.000	EA
0510 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	1,039.000	EA
0520 871(B)2300	CONST.ZONE IMPACT ATTEN.	40.000	SD
0530 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,900.000	LF
0540 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,000.000	LF
0550 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,850.000	SD
0560 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,390.000	SD
0570 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,010.000	SD
0580 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	940.000	SD
0590 880(E)6600	WARNING LIGHTS(TYPE A)	14,880.000	SD
0600 880(E)6607	WARNING LIGHTS(TYPE B)	3,700.000	SD
0610 880(F)6700	DRUMS	16,730.000	SD
0620 880(G)6810	TUBE CHANNELIZERS	326.000	EA
0630 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	740.000	HOURL
0640 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	398.000	SD
0005 STAKING			
0650 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006 CONSTRUCTION			
0660 641 2100	MOBILIZATION	1.000	LSUM