Proposal:260285 **Let Date:**December 17, 2026 **Call Order:**065
J/P Num:37100(53) **Proj. Num:**EWC-28810A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE AND SURFACE
TPK :TOBY KEITH EXPRESSWAY (OTA ACCESS): 0.5 MILES SOUTH
FROM I-40 INTERCHANGE AT SE 89TH STREET IN OKLAHOMA CITY.
PROJECT LENGTH = 0.531 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY - OTA			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	15,259.000	CY
0030	202(C)2400	ROCK EXCAVATION	57,034.000	CY
0040	202(D)2500	UNCLASSIFIED BORROW	2,500.000	CY
0050	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0060	221(B)2300	TEMPORARY SILT FENCE	2,000.000	LF
0070	221(C)2410	REINFORCED SILT FENCE	1,085.000	LF
0080	221(E)2600	TEMPORARY SILT DIKE	1,302.000	LF
0090	221(F)2700	TEMPORARY ROCK FILTER DAM TYPE 1	8.000	CY
0100	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0110	230(A)7200	SOLID SLAB SODDING	60,498.000	SY
0120	233(E)0600	(SP) HYDROMULCH	30,678.000	SY
0130	241 3100	MOWING	25.000	AC
0140	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0150	613(B)5524	30" CORR. GALV. STEEL PIPE	268.000	LF
0002	ROADWAY - CITY OF OKLAHOMA CITY			
0160	202(A)2200	UNCLASSIFIED EXCAVATION	31,732.000	CY
0170	202(D)2500	UNCLASSIFIED BORROW	2,500.000	CY
0180	307(K)4200	STABILIZED SUBGRADE	9,559.000	SY
0190	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	44.000	TON
0200	407(B)7300	TACK COAT	567.000	GAL
0210	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,613.000	TON
0220	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,083.000	TON
0230	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	32.000	CY
0240	509(A)0200	CLASS AA CONCRETE	84.000	CY
0250	509(D)0500	CLASS C CONCRETE	317.000	CY
0260	511(A)2200	REINFORCING STEEL	10,456.000	LB
0270	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	23.000	TON
0280	610(B)5310	6" CONCRETE DRIVEWAY	49.000	SY
0290	611(G)0354	INLET (SMD-TYPE 2)	2.000	EA
0300	613(A)5216	24" R.C.PIPE CLASS III	59.000	LF
0310	613(B)5508	18" CORR. GALV. STEEL PIPE	182.000	LF
0320	613(B)5516	24" CORR. GALV. STEEL PIPE	150.000	LF
0330	613(B)5524	30" CORR. GALV. STEEL PIPE	100.000	LF
0340	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0350	613(M)6960	TYPE A4 CULVERT END TREATMENT	6.000	EA
0360	613(M)6968	TYPE C4 CULVERT END TREATMENT	1.000	EA
0370	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0380	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	7,283.000	SY
0390	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	97.000	SY
0400	619(B)6386	REMOVAL OF GRAVEL DRIVEWAY	1,831.000	SY
0410	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	175.000	LF
0420	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0430	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0440	624(A)3200	FENCE-STYLE WWF	630.000	LF

Proposal:260285 **Let Date:**December 17, 2026 **Call Order:**065
J/P Num:37100(53) **Proj. Num:**EWC-28810A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE AND SURFACE
TPK :TOBY KEITH EXPRESSWAY (OTA ACCESS): 0.5 MILES SOUTH
FROM I-40 INTERCHANGE AT SE 89TH STREET IN OKLAHOMA CITY.
PROJECT LENGTH = 0.531 MILES

Line #		Item Description	Quantity	Unit
0002	ROADWAY - CITY OF OKLAHOMA CITY			
0450	624(C)3405	FENCE-STYLE SWF (5 BARBED WIRE)	350.000	LF
0460	624(E)3600	FENCE-STYLE CLF (4'HIGH, CLASS A)	345.000	LF
0470	629(B)7300	MAILBOX INSTALLATION-MULTIPLE	1.000	EA
0480	629(C)7400	REMOVAL OF MAILBOX INSTALLATION	1.000	EA
0490	629(E)7600	MAILBOX	2.000	EA
0500	853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	12.000	EA
0003	BRIDGE "DD"			
0510	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	115.000	CY
0520	501(C)1400	SUBSTRUCTURE EXCAVATION ROCK	90.000	CY
0530	501(G)1800	CLSM BACKFILL	132.000	CY
0540	503(A)4230	PRESTRESSED CONCRETE BEAMS (TYPE III)	474.800	LF
0550	503(A)4270	PRESTRESSED CONCRETE BEAMS (TYPE J BT)	854.800	LF
0560	504(A)5200	APPROACH SLAB	227.800	SY
0570	504(B)5300	SAW-CUT GROOVING	1,405.300	SY
0580	504(D)5420	CONCRETE RAIL (TR4)	790.400	LF
0590	506(A)7200	STRUCTURAL STEEL	2,840.000	LB
0600	507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0610	507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	24.000	EA
0620	507(C)8400	ELASTOMERIC BEARING PADS	24.000	EA
0630	509(A)0210	CLASS AA CONCRETE	365.500	CY
0640	509(B)0320	CLASS A CONCRETE	239.500	CY
0650	510(C)1450	SLOPE WALL (5")	734.000	SY
0660	511(A)2210	REINFORCING STEEL	6,270.000	LB
0670	511(B)2310	EPOXY COATED REINFORCING STEEL	151,490.000	LB
0680	514(A)5210	PILES, FURNISHED (HP 10X42)	426.000	LF
0690	514(B)5310	PILES, DRIVEN (HP 10X42)	426.000	LF
0700	514(K)6200	(PL)PILOT HOLES	140.000	LF
0710	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0720	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,917.000	SY
0730	516(A)8240	DRILLED SHAFTS 60" DIAMETER	102.000	LF
0740	516(A)8250	DRILLED SHAFTS 72" DIAMETER	36.000	LF
0750	516(C)8400	CROSSHOLE SONIC LOGGING	3.000	EA
0760	523(A)3200	SEALER CRACK PREPARATION	196.800	LF
0770	523(B)3300	SEALER RESIN	2.200	GAL
0780	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0790	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	155.000	LF
0800	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	83.000	LF

Proposal:260285 **Let Date:**December 17, 2026 **Call Order:**065
J/P Num:37100(53) **Proj. Num:**EWC-28810A
Counties:CLEVELAND
Description:GRADE, DRAIN, BRIDGE AND SURFACE
TPK :TOBY KEITH EXPRESSWAY (OTA ACCESS): 0.5 MILES SOUTH
FROM I-40 INTERCHANGE AT SE 89TH STREET IN OKLAHOMA CITY.
PROJECT LENGTH = 0.531 MILES

Line #		Item Description	Quantity	Unit
0004	TRAFFIC SIGNING AND STRIPING - OTA			
0810	804(A)2200	STRUCTURAL CONCRETE	4.000	CY
0820	804(B)2300	REINFORCING STEEL	516.000	LB
0830	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	4.000	EA
0840	850(A)1200	SHEET ALUMINUM SIGNS	44.000	SF
0850	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	213.000	SF
0860	851(A)2210	6"@20 GALV.STL.WD.FLANGE BM.POST	101.000	LF
0870	851(C)2430	2 1/2" SQUARE TUBE POST	42.000	LF
0005	TRAFFIC SIGNING AND STRIPING - CITY OF OKLAHOMA CITY			
0880	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	6.000	EA
0890	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	1.000	EA
0900	850(A)1200	SHEET ALUMINUM SIGNS	34.000	SF
0910	851(C)2430	2 1/2" SQUARE TUBE POST	56.000	LF
0920	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	10,493.000	LF
0006	TRAFFIC CONTROL - OTA			
0930	871(A)2200	IMPACT ATTENUATOR	1.000	EA
0940	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	1,625.000	LF
0950	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	100.000	LF
0960	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,470.000	SD
0970	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,440.000	SD
0980	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,092.000	SD
0990	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,520.000	SD
1000	880(E)6600	WARNING LIGHTS(TYPE A)	5,040.000	SD
1010	880(E)6607	WARNING LIGHTS(TYPE B)	1,092.000	SD
1020	880(E)6610	WARNING LIGHTS(TYPE C)	60.000	SD
1030	880(F)6700	DRUMS	60.000	SD
1040	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,440.000	HOUR
1050	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	582.000	SD
0007	STAKING			
1060	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION			
1070	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1080	641 2110	MOBILIZATION	1.000	LSUM