Proposal: 260286 **Let Date:** December 17, 2026 **Call Order:** 070
J/P Num: 37100(50) **Proj. Num:** EWC-28510A
Counties: CLEVELAND
Description: BRIDGE AND APPROACHES
TOBY KEITH EXPRESSWAY (OTA ACCESS): OVER SE 104TH STREET,
1.5 MILES SOUTH OF THE I-40 INTERCHANGE IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.340 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	9,562.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	105,650.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	2,000.000	LF
0060	221(C)2410	REINFORCED SILT FENCE	3,382.000	LF
0070	221(E)2600	TEMPORARY SILT DIKE	798.000	LF
0080	221(F)2710	TEMPORARY ROCK FILTER DAM TYPE 2	13.000	CY
0090	221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	5.000	EA
0100	230(A)7200	SOLID SLAB SODDING	51,668.000	SY
0110	233(E)0600	(SP) HYDROMULCH	72,116.000	SY
0120	241 3100	MOWING	22.000	AC
0130	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0140	509(D)0500	CLASS C CONCRETE	256.000	CY
0150	611(A)7210	MANHOLE (4' DIA.)	3.000	EA
0160	611(B)7300	ADD'L.DEPTH IN MANHOLE (4' DIA.)	15.000	VF
0170	611(G)0354	INLET (SMD-TYPE 2)	5.000	EA
0180	613(A)5216	24" R.C.PIPE CLASS III	622.000	LF
0190	613(B)5508	18" CORR. GALV. STEEL PIPE	66.000	LF
0200	613(L)6716	24" PREFAB. CULVERT END SEC., ROUND	5.000	EA
0210	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220	624(A)3200	FENCE-STYLE WWF	3,169.000	LF

Proposal:260286 **Let Date:**December 17, 2026 **Call Order:**070
J/P Num:37100(50) **Proj. Num:**EWC-28510A
Counties:CLEVELAND
Description:BRIDGE AND APPROACHES
TOBY KEITH EXPRESSWAY (OTA ACCESS): OVER SE 104TH STREET,
1.5 MILES SOUTH OF THE I-40 INTERCHANGE IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.340 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE "BB"			
0230	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	475.000	CY
0240	501(G)1800	CLSM BACKFILL	211.200	CY
0250	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	3,773.600	LF
0260	504(A)5200	APPROACH SLAB	273.400	SY
0270	504(B)5300	SAW-CUT GROOVING	3,466.800	SY
0280	504(E)5520	42" F-SHAPED PARAPET	1,642.400	LF
0290	506(A)7200	STRUCTURAL STEEL	4,160.000	LB
0300	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	30.000	EA
0310	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	50.000	EA
0320	509(A)0210	CLASS AA CONCRETE	856.000	CY
0330	509(B)0320	CLASS A CONCRETE	536.500	CY
0340	511(A)2210	REINFORCING STEEL	13,020.000	LB
0350	511(B)2310	EPOXY COATED REINFORCING STEEL	343,540.000	LB
0360	514(A)5210	PILES, FURNISHED (HP 10X42)	205.000	LF
0370	514(A)5220	PILES, FURNISHED (HP 12X53)	646.000	LF
0380	514(B)5310	PILES, DRIVEN (HP 10X42)	205.000	LF
0390	514(B)5320	PILES, DRIVEN (HP 12X53)	646.000	LF
0400	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0410	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	6,404.000	SY
0420	516(A)8240	DRILLED SHAFTS 60" DIAMETER	632.000	LF
0430	516(A)8250	DRILLED SHAFTS 72" DIAMETER	264.000	LF
0440	516(C)8400	CROSSHOLE SONIC LOGGING	7.000	EA
0450	517 9110	ELASTOMERIC COATING	3,204.000	SF
0460	518(B)0310	EXPANSION JOINT SYSTEM	120.000	LF
0470	523(A)3200	SEALER CRACK PREPARATION	152.000	LF
0480	523(B)3300	SEALER RESIN	1.600	GAL
0490	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0500	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	7,610.000	TON
0510	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
0520	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF

Proposal:260286 **Let Date:**December 17, 2026 **Call Order:**070
J/P Num:37100(50) **Proj. Num:**EWC-28510A
Counties:CLEVELAND
Description:BRIDGE AND APPROACHES
TOBY KEITH EXPRESSWAY (OTA ACCESS): OVER SE 104TH STREET,
1.5 MILES SOUTH OF THE I-40 INTERCHANGE IN THE CITY OF OKLAHOMA CITY.
PROJECT LENGTH = 0.340 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE "CC"			
0530	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	450.000	CY
0540	501(G)1800	CLSM BACKFILL	211.900	CY
0550	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	3,773.600	LF
0560	504(A)5200	APPROACH SLAB	273.400	SY
0570	504(B)5300	SAW-CUT GROOVING	3,466.800	SY
0580	504(E)5520	42" F-SHAPED PARAPET	1,642.400	LF
0590	506(A)7200	STRUCTURAL STEEL	4,160.000	LB
0600	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	30.000	EA
0610	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	50.000	EA
0620	509(A)0210	CLASS AA CONCRETE	856.000	CY
0630	509(B)0320	CLASS A CONCRETE	536.600	CY
0640	511(A)2210	REINFORCING STEEL	13,020.000	LB
0650	511(B)2310	EPOXY COATED REINFORCING STEEL	343,540.000	LB
0660	514(A)5210	PILES, FURNISHED (HP 10X42)	185.000	LF
0670	514(A)5220	PILES, FURNISHED (HP 12X53)	575.000	LF
0680	514(B)5310	PILES, DRIVEN (HP 10X42)	185.000	LF
0690	514(B)5320	PILES, DRIVEN (HP 12X53)	575.000	LF
0700	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0710	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	6,404.000	SY
0720	516(A)8240	DRILLED SHAFTS 60" DIAMETER	622.000	LF
0730	516(A)8250	DRILLED SHAFTS 72" DIAMETER	258.000	LF
0740	516(C)8400	CROSSHOLE SONIC LOGGING	7.000	EA
0750	517 9110	ELASTOMERIC COATING	3,204.000	SF
0760	518(B)0310	EXPANSION JOINT SYSTEM	120.000	LF
0770	523(A)3200	SEALER CRACK PREPARATION	152.000	LF
0780	523(B)3300	SEALER RESIN	1.600	GAL
0790	535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0800	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	84.000	LF
0810	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
0004	TRAFFIC CONTROL			
0820	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	16,500.000	SD
0830	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	5,550.000	SD
0840	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	550.000	SD
0850	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	70.000	SD
0860	880(E)6600	WARNING LIGHTS(TYPE A)	690.000	SD
0870	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	660.000	HOUR
0880	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	578.000	SD
0005	STAKING			
0890	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION			
0900	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0910	641 2110	MOBILIZATION	1.000	LSUM