

Proposal:260287**Let Date:**November 12, 2026**Call Order:**028**J/P Num:**36894(04)**Proj. Num:**IN-MC-79**Counties:**MCINTOSH**Description:**BRIDGE REHABILITATION

OTA ACCESS INDIAN NATION TURNPIKE (SH-375):
 OVER NORTH CANADIAN RIVER, 8 MILES SOUTH
 OF THE I-40 INTERCHANGE NEAR VERNON.
 PROJECT LENGTH = 0.265 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	100.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	420.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	572.000	LF
0060 230(A)7200	SOLID SLAB SODDING	1,820.000	SY
0070 233(A)0200	VEGETATIVE MULCHING	0.270	AC
0080 241 3100	MOWING	0.540	AC
0090 303(A)1200	AGGREGATE BASE TYPE A	220.000	CY
0100 307(K)4200	STABILIZED SUBGRADE	1,402.000	SY
0110 310(B)5300	SUBGRADE, METHOD B	352.000	SY
0120 325 0100	SEPARATOR FABRIC	1,497.000	SY
0130 408 8100	PRIME COAT	429.000	GAL
0140 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	20.000	TON
0150 413(C)4400	RUMBLE STRIP-METHOD PCC-CON	1,008.000	LF
0160 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	723.000	SY
0170 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	810.000	SY
0180 414(G)5800	P.C. CONCRETE FOR PAVEMENT	366.000	CY
0190 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,510.000	SY
0200 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	100.000	SY
0210 619(B)6396	REMOVAL OF GUARDRAIL	152.000	LF
0220 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	100.000	LF
0230 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0240 625(B)4300	REMOVE AND RECONSTRUCT FENCE	480.000	LF
0250 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	8.000	EA

Proposal:260287

Let Date:November 12, 2026

Call Order:028

J/P Num:36894(04)

Proj. Num:IN-MC-79

Counties:MCINTOSH

Description:BRIDGE REHABILITATION

OTA ACCESS INDIAN NATION TURNPIKE (SH-375):
OVER NORTH CANADIAN RIVER, 8 MILES SOUTH
OF THE I-40 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.265 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE		
0260 201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
0270 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0280 501(G)1800	CLSM BACKFILL	130.000	CY
0290 503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	11,960.000	LF
0300 504(A)5200	APPROACH SLAB	394.800	SY
0310 504(B)5300	SAW-CUT GROOVING	9,853.600	SY
0320 504(E)5520	42" F-SHAPED PARAPET	2,498.000	LF
0330 506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	10,264.000	LB
0340 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	120.000	EA
0350 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	120.000	EA
0360 509(A)0210	CLASS AA CONCRETE	2,511.900	CY
0370 509(B)0320	CLASS A CONCRETE	20.000	CY
0380 509(D)0510	CLASS C CONCRETE	6.000	CY
0390 511(B)2310	EPOXY COATED REINFORCING STEEL	490,520.000	LB
0400 513(A)4200	CLASS A BRIDGE DECK REPAIR	110.000	SY
0410 513(B)4300	CLASS B BRIDGE DECK REPAIR	74.000	SY
0420 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	25,387.000	SY
0430 517 9110	ELASTOMERIC COATING	4,567.000	SF
0440 518(B)0310	EXPANSION JOINT SYSTEM	432.000	LF
0450 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	952.000	LF
0460 520(C)1400	EPOXY RESIN, ABOVE WATER	80.000	GAL
0470 521(A)2200	PNEUMATICALLY PLACED MORTAR	201.000	SY
0480 523(A)3200	SEALER CRACK PREPARATION	1,557.000	LF
0490 523(B)3300	SEALER RESIN	18.000	GAL
0500 524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	239.000	SF
0510 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	465.000	SY
0520 619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC CONTROL		
0530 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	41,770.000	LF
0540 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	41,770.000	LF
0550 871(B)2300	CONST.ZONE IMPACT ATTEN.	2,780.000	SD
0560 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	7,850.000	LF
0570 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	7,850.000	LF
0580 880(A)6220	ARROW DISPLAY(TYPE C)	2,400.000	SD
0590 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,000.000	SD
0600 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,160.000	SD
0610 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,200.000	SD
0620 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	9,600.000	SD
0630 880(E)6600	WARNING LIGHTS(TYPE A)	19,800.000	SD
0640 880(F)6700	DRUMS	51,080.000	SD
0650 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	600.000	HOURL
0660 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	800.000	SD

Proposal:260287

Let Date:November 12, 2026

Call Order:028

J/P Num:36894(04)

Proj. Num:IN-MC-79

Counties:MCINTOSH

Description:BRIDGE REHABILITATION

OTA ACCESS INDIAN NATION TURNPIKE (SH-375):
OVER NORTH CANADIAN RIVER, 8 MILES SOUTH
OF THE I-40 INTERCHANGE NEAR VERNON.
PROJECT LENGTH = 0.265 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004	TRAFFIC - SIGNING AND STRIPING		
0670 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	43,890.000	LF
0005	TRAFFIC - CABLE BARRIER		
0680 509(A)0200	CLASS AA CONCRETE	27.220	CY
0690 619(B)6432	REMOVAL OF CABLE BARRIER	3,275.000	LF
0700 628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	3,275.000	LF
0710 628(C)7400	END ANCHORS	4.000	EA
0006	STAKING		
0720 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007	CONSTRUCTION		
0730 641 2100	MOBILIZATION	1.000	LSUM