

Proposal:260288
J/P Num:31893(04)
Counties:CARTER

Let Date:November 12, 2026
Proj. Num:NHPP-210N(113)PM

Call Order:300

Description:BRIDGE AND APPROACHES

SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
 OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
 PROJECT LENGTH = 0.306 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	13,534.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	23,418.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(C)2410	REINFORCED SILT FENCE	2,864.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	1,722.000	LF
0070 221(F)2730	TEMPORARY ROCK FILTER DAM TYPE 4	9.000	CY
0080 221(H)2900	(PL)TEMPORARY INLET SEDIMENT FILTER	2.000	EA
0090 230(A)7200	SOLID SLAB SODDING	15,740.000	SY
0100 232(A)9200	SEEDING METHOD A	3.250	AC
0110 233(A)0200	VEGETATIVE MULCHING	3.250	AC
0120 241 3100	MOWING	6.500	AC
0130 242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0140 303(A)1200	AGGREGATE BASE TYPE A	1,103.000	CY
0150 307(K)4200	STABILIZED SUBGRADE	5,215.000	SY
0160 325 0100	SEPARATOR FABRIC	5,313.000	SY
0170 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	332.000	TON
0180 408 8100	PRIME COAT	3,322.000	GAL
0190 409(A)9200	FABRIC REINFORCEMENT	142.000	SY
0200 411(B)1300	SUPERPAVE, TYPE S3(PG 76-28 OK)	852.000	TON
0210 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,128.000	TON
0220 411(C)1400	SUPERPAVE, TYPE S4(PG 76-28 OK)	657.000	TON
0230 411(C)1420	SUPERPAVE, TYPE S4(PG 70-28 OK)	2,041.000	TON
0240 411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,000.000	TON
0250 412 3100	COLD MILLING PAVEMENT	19,067.000	SY
0260 502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0270 504(E)5520	42" F-SHAPED PARAPET	202.250	LF
0280 509(B)0300	CLASS A CONCRETE	95.400	CY
0290 509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	2.000	CY
0300 509(D)0500	CLASS C CONCRETE	78.000	CY
0310 510(A)1200	RETAINING WALL	694.000	SY
0320 511(B)2300	EPOXY COATED REINFORCING STEEL	18,076.000	LB
0330 514(A)5220	PILES, FURNISHED (HP 12X53)	5,555.000	LF
0340 514(B)5320	PILES, DRIVEN (HP 12X53)	5,555.000	LF
0350 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0360 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	648.000	SY
0370 601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	64.000	TON
0380 602(C)2410	FILTER FABRIC	48.000	SY
0390 609(B)4370	2'-8" COMB.CRB.& GUT.(6" MNTBLE)	136.000	LF
0400 609(C)4420	BITUMINOUS CURBING	1,000.000	LF
0410 610(B)5310	6" CONCRETE DRIVEWAY	23.000	SY
0420 611(G)9000	INLET CDI RCP DES. 1	1.000	EA
0430 613(A)5208	18" R.C.PIPE CLASS III	158.000	LF
0440 613(A)5350	22" X 13" R.C.PIPE ARCH CLASS A-III	7.000	LF
0450 613(L)6612	22" X 13" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0460 613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	1.000	EA

Proposal:260288
J/P Num:31893(04)
Counties:CARTER

Let Date:November 12, 2026
Proj. Num:NHPP-210N(113)PM

Call Order:300

Description:BRIDGE AND APPROACHES

SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0470 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0480 619(B)6356	REMOVAL OF CURB AND GUTTER	145.000	LF
0490 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	74.000	SY
0500 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	5,119.000	SY
0510 619(B)6396	REMOVAL OF GUARDRAIL	2,109.000	LF
0520 619(C)6600	SAWING PAVEMENT	948.000	LF
0530 620(C)8410	CONTRACTOR HEALTH SAFETY PLAN	1.000	LSUM
0540 620(C)8430	CONTAMINATED MATERIALS MANAGEMENT PLAN	1.000	LSUM
0550 622(A)0200	PIPE RAILING	405.000	LF
0560 623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0570 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	812.500	LF
0580 623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0590 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0600 624(A)3200	FENCE-STYLE WWF	640.000	LF

Proposal:260288
J/P Num:31893(04)
Counties:CARTER

Let Date:November 12, 2026
Proj. Num:NHPP-210N(113)PM

Call Order:300

Description:BRIDGE AND APPROACHES

SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
 OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
 PROJECT LENGTH = 0.306 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE 'A'		
0610 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	3,155.000	CY
0620 501(G)1800	CLSM BACKFILL	2,880.700	CY
0630 504(A)5200	APPROACH SLAB	1,200.400	SY
0640 504(B)5300	SAW-CUT GROOVING	3,819.200	SY
0650 504(E)5520	42" F-SHAPED PARAPET	1,351.500	LF
0660 506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	1,581,650.000	LB
0670 506(A)7230	STRUCTURAL STEEL A36	332.000	LB
0680 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	16.000	EA
0690 509(A)0210	CLASS AA CONCRETE	883.000	CY
0700 509(B)0320	CLASS A CONCRETE	1,837.800	CY
0710 510(C)1450	SLOPE WALL (5")	2,070.000	SY
0720 511(A)2210	REINFORCING STEEL	43,323.000	LB
0730 511(B)2310	EPOXY COATED REINFORCING STEEL	505,050.000	LB
0740 514(A)5210	PILES, FURNISHED (HP 10X42)	332.000	LF
0750 514(A)5220	PILES, FURNISHED (HP 12X53)	3,646.000	LF
0760 514(B)5310	PILES, DRIVEN (HP 10X42)	332.000	LF
0770 514(B)5320	PILES, DRIVEN (HP 12X53)	3,646.000	LF
0780 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0790 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,816.000	SY
0800 516(A)8240	DRILLED SHAFTS 60" DIAMETER	210.000	LF
0810 516(A)8250	DRILLED SHAFTS 72" DIAMETER	266.000	LF
0820 516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0830 517 9110	ELASTOMERIC COATING	1,672.000	SF
0840 518(B)0300	SEALED EXPANSION JOINTS	273.000	LF
0850 523(A)3200	SEALER CRACK PREPARATION	819.000	LF
0860 523(B)3300	SEALER RESIN	5.400	GAL
0870 542 9111	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE A)	1.000	EA
0880 542 9121	(PL)INSTALLATION OF BRIDGE ITEMS(TYPE B)	7.000	EA
0890 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	824.000	LF
0900 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	120.000	LF
0910 619(D)6700	REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM
0920 624(E)3640	FENCE-STYLE CLF (8'HIGH, CLASS A)	480.000	LF

Proposal:260288
J/P Num:31893(04)
Counties:CARTER

Let Date:November 12, 2026
Proj. Num:NHPP-210N(113)PM

Call Order:300

Description:BRIDGE AND APPROACHES

SH-142: OVER THE BNSF RAILROAD, 0.5 MILES NORTH
OF THE SH-199 INTERSECTION IN THE CITY OF ARDMORE.
PROJECT LENGTH = 0.306 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 TRAFFIC CONTROL			
0930 104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	250.000	DAY
0940 823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	226.000	SD
0950 854(A)6201	(SP) TRAFFIC STRIPE(PAINT)(4" WIDE)	19,812.000	LF
0960 854(B)6301	(SP) TRAFFIC STRIPE(PAINT)(ARROW)	15.000	EA
0970 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	25,510.000	LF
0980 857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	15.000	EA
0990 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	261.000	EA
1000 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	248.000	EA
1010 876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	66.000	SD
1020 880(A)6220	ARROW DISPLAY(TYPE C)	33.000	SD
1030 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	32,637.000	SD
1040 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	4,334.000	SD
1050 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,156.000	SD
1060 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,158.000	SD
1070 880(E)6607	WARNING LIGHTS(TYPE B)	23,947.000	SD
1080 880(F)6700	DRUMS	4,934.000	SD
1090 880(G)6805	CHANNELIZER CONES	6,270.000	SD
1100 880(I)7000	FLAGGER	17.000	SD
1110 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	616.000	HOURL
1120 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	581.000	SD
0004 TRAFFIC SIGNING AND STRIPING			
1130 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	1.000	EA
1140 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	3.000	EA
1150 850(A)1200	SHEET ALUMINUM SIGNS	10.000	SF
1160 851(C)2430	2 1/2" SQUARE TUBE POST	31.000	LF
1170 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	24.000	EA
1180 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	22,834.000	LF
1190 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	50.000	LF
0005 STAKING			
1200 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006 CONSTRUCTION			
1210 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1220 641 2100	MOBILIZATION	1.000	LSUM