

**Proposal:**260290  
**J/P Num:**30030(04)  
**Counties:**CUSTER

**Let Date:**November 12, 2026  
**Proj. Num:**CIRB-220D(088)RB

**Call Order:**310

**Description:**BRIDGE AND APPROACHES

COUNTY ROAD (EW-094): OVER CROOKED CREEK, 7 MILES  
EAST OF THE SH-34 JUNCTION NEAR BUTLER.  
PROJECT LENGTH = 0.217 MILES

| <u>Line #</u>            | <u>Item Description</u>                 | <u>Quantity</u> | <u>Unit</u> |
|--------------------------|-----------------------------------------|-----------------|-------------|
| <b>0001 ROADWAY</b>      |                                         |                 |             |
| 0010 201(A)1200          | CLEARING AND GRUBBING                   | 1.000           | LSUM        |
| 0020 202(H)2900          | EARTHWORK                               | 1.000           | LSUM        |
| 0030 221(B)2300          | TEMPORARY SILT FENCE                    | 760.000         | LF          |
| 0040 221(E)2600          | TEMPORARY SILT DIKE                     | 300.000         | LF          |
| 0050 230(A)7200          | SOLID SLAB SODDING                      | 2,200.000       | SY          |
| 0060 233(A)0200          | VEGETATIVE MULCHING                     | 0.460           | AC          |
| 0070 402(E)2600          | TRAFFIC BOUND SURFACE COURSE TYPE E     | 677.000         | TON         |
| 0080 509(D)0500          | CLASS C CONCRETE                        | 10.000          | CY          |
| 0090 613(A)5370          | 43" X 26" R.C.PIPE ARCH CLASS A-III     | 72.000          | LF          |
| 0100 613(B)5612          | 28" X 20" CORR. GALV. STEEL PIPE ARCH   | 68.000          | LF          |
| 0110 613(M)6904          | TYPE B3 CULVERT END TREATMENT           | 2.000           | EA          |
| 0120 613(M)6908          | TYPE C3 CULVERT END TREATMENT           | 2.000           | EA          |
| 0130 624(C)3410          | FENCE-STYLE SWF (6 BARBED WIRE)         | 668.000         | LF          |
| 0140 625(A)4200          | REMOVE AND STORE FENCE                  | 583.000         | LF          |
| <b>0002 BRIDGE</b>       |                                         |                 |             |
| 0150 501(B)1300          | SUBSTRUCTURE EXCAVATION COMMON          | 175.000         | CY          |
| 0160 501(D)1500          | UNCLASSIFIED BACKFILL                   | 549.000         | CY          |
| 0170 504(D)5420          | CONCRETE RAIL (TR4)                     | 120.000         | LF          |
| 0180 506(A)7200          | STRUCTURAL STEEL                        | 19,594.000      | LB          |
| 0190 509(A)0210          | CLASS AA CONCRETE                       | 50.400          | CY          |
| 0200 511(A)2210          | REINFORCING STEEL                       | 11,270.000      | LB          |
| 0210 512(A)3200          | PAINTING EXISTING STRUCTURES            | 1.000           | LSUM        |
| 0220 512(B)3300          | COLLECTION AND HANDLING OF WASTE        | 1.000           | LSUM        |
| 0230 514(A)5210          | PILES, FURNISHED (HP 10X42)             | 1,032.000       | LF          |
| 0240 514(B)5310          | PILES, DRIVEN (HP 10X42)                | 1,032.000       | LF          |
| 0250 514(H)5900          | SHEET PILING, FURNISHED                 | 344.000         | SY          |
| 0260 514(I)6000          | SHEET PILING, DRIVEN                    | 344.000         | SY          |
| 0270 514(L)6300          | PILE SPLICE, H-PILE (NON-BIDDABLE)      | 1.000           | EA          |
| 0280 535 7110            | HAUL AND ERECT STEEL BEAMS              | 1.000           | LSUM        |
| 0290 601(B)1210          | TYPE I PLAIN RIPRAP WITH FILTER BLANKET | 1,590.000       | TON         |
| 0300 619(D)6700          | REMOVAL OF EXISTING BRIDGE STRUCTURE    | 1.000           | LSUM        |
| 0310 623(F)1748          | GUARDRAIL ANCHOR UNIT (TYPE II)         | 4.000           | EA          |
| <b>0003 TRAFFIC</b>      |                                         |                 |             |
| 0320 880(B)6310          | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF  | 480.000         | SD          |
| 0330 880(B)6320          | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF  | 720.000         | SD          |
| 0340 880(C)6410          | CONSTRUCTION BARRICADES(TYPE III)       | 1,200.000       | SD          |
| 0350 880(E)6600          | WARNING LIGHTS(TYPE A)                  | 2,640.000       | SD          |
| <b>0004 STAKING</b>      |                                         |                 |             |
| 0360 642(B)3300          | CONSTRUCTION STAKING LEVEL II           | 1.000           | LSUM        |
| <b>0005 CONSTRUCTION</b> |                                         |                 |             |
| 0370 641 2100            | MOBILIZATION                            | 1.000           | LSUM        |