

Proposal:260291
J/P Num:29862(04)
Counties:GRANT

Let Date:November 12, 2026
Proj. Num:CIRB-227D(012)RB

Call Order:315

Description:BRIDGE AND APPROACHES

COUNTY ROAD (EW 15): OVER OSAGE CREEK,
2.75 MILES WEST OF THE US-81 JUNCTION NEAR MEDFORD.
PROJECT LENGTH = 0.321 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	2,586.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	5,010.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	1,300.000	LF
0060 221(E)2600	TEMPORARY SILT DIKE	252.000	LF
0070 230(A)7200	SOLID SLAB SODDING	10,030.000	SY
0080 233(A)0200	VEGETATIVE MULCHING	2.070	AC
0090 303(A)1200	AGGREGATE BASE TYPE A	572.000	CY
0100 509(D)0500	CLASS C CONCRETE	10.000	CY
0110 613(B)5508	18" CORR. GALV. STEEL PIPE	92.000	LF
0120 613(L)6708	18" PREFAB. CULVERT END SEC., ROUND	4.000	EA
0130 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0140 623(F)1704	GUARDRAIL ANCHOR UNIT (TYPE A)	4.000	EA
0150 623(F)1724	GUARDRAIL ANCHOR UNIT (TYPE D-BF)	4.000	EA
0002 BRDGE			
0160 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	292.000	CY
0170 501(F)1700	GRANULAR BACKFILL	148.000	CY
0180 504(D)5410	CONCRETE RAIL (TR3)	423.000	LF
0190 506(A)7200	STRUCTURAL STEEL	17,590.000	LB
0200 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	15.000	EA
0210 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	15.000	EA
0220 509(A)0210	CLASS AA CONCRETE	126.700	CY
0230 509(B)0320	CLASS A CONCRETE	188.400	CY
0240 511(A)2210	REINFORCING STEEL	57,010.000	LB
0250 514(A)5210	PILES, FURNISHED (HP 10X42)	192.000	LF
0260 514(A)5220	PILES, FURNISHED (HP 12X53)	430.000	LF
0270 514(B)5310	PILES, DRIVEN (HP 10X42)	192.000	LF
0280 514(B)5320	PILES, DRIVEN (HP 12X53)	430.000	LF
0290 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0300 516(A)8230	DRILLED SHAFTS 48" DIAMETER	192.000	LF
0310 517 9110	ELASTOMERIC COATING	784.000	SF
0320 518(B)0300	SEALED EXPANSION JOINTS	58.340	LF
0330 535 7110	HAUL AND ERECT STEEL BEAMS	1.000	LSUM
0340 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	3,892.000	TON
0350 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	52.000	LF
0360 613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	60.000	LF
0003 TRAFFIC			
0370 850(A)1200	SHEET ALUMINUM SIGNS	17.000	SF
0380 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,400.000	SD
0390 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	240.000	SD
0400 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,920.000	SD
0410 880(E)6600	WARNING LIGHTS(TYPE A)	4,800.000	SD

Proposal:260291
J/P Num:29862(04)
Counties:GRANT

Let Date:November 12, 2026
Proj. Num:CIRB-227D(012)RB

Call Order:315

Description:BRIDGE AND APPROACHES
COUNTY ROAD (EW 15): OVER OSAGE CREEK,
2.75 MILES WEST OF THE US-81 JUNCTION NEAR MEDFORD.
PROJECT LENGTH = 0.321 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004 STAKING			
0420 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005 CONSTRUCTION			
0430 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0440 641 2100	MOBILIZATION	1.000	LSUM