

Proposal:260292

Let Date:November 12, 2026

Call Order:320

J/P Num:38191(04)

Proj. Num:SBR-253B(096)SB

Counties:JOHNSTON

Description:BRIDGE REHABILITATION

SH-22: OVER PENNINGTON CREEK, 0.37 MILES WEST
OF THE US-377 JUNCTION IN THE CITY OF TISHOMINGO.
PROJECT LENGTH = 0.067 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 202(A)2200	UNCLASSIFIED EXCAVATION	128.000	CY
0020 221(B)2300	TEMPORARY SILT FENCE	608.000	LF
0030 221(E)2600	TEMPORARY SILT DIKE	56.000	LF
0040 229 6100	DITCH LINER PROTECTION	80.000	LF
0050 230(A)7200	SOLID SLAB SODDING	365.000	SY
0060 408 8100	PRIME COAT	115.000	GAL
0070 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	55.000	TON
0080 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	50.000	TON
0090 509(D)0500	CLASS C CONCRETE	6.560	CY
0100 518(J)0800	PREFORMED SILICONE FOAM JOINTS	137.300	LF
0110 601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	10.000	TON
0120 602(C)2410	FILTER FABRIC	8.000	SY
0130 619(B)6396	REMOVAL OF GUARDRAIL	237.500	LF
0140 619(C)6600	SAWING PAVEMENT	139.000	LF
0150 623 1100	(PL)GUARDRAIL CURBING	2.000	EA
0160 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	140.640	LF
0170 623(F)1764	GUARDRAIL TRAIL END TURNDOWN (31")	1.000	EA
0180 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA
0190 853 5175	GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	8.000	EA
0002	BRIDGE - NBI 13229		
0200 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	40.000	CY
0210 501(G)1800	CLSM BACKFILL	65.300	CY
0220 502 3100	TEMPORARY EARTH RETAINAGE	1.000	LSUM
0230 504(A)5200	APPROACH SLAB	155.300	SY
0240 504(B)5300	SAW-CUT GROOVING	147.900	SY
0250 504(D)5420	CONCRETE RAIL (TR4)	49.000	LF
0260 509 0100	SPECIAL CONCRETE FINISH	551.000	SY
0270 509(A)0210	CLASS AA CONCRETE	16.700	CY
0280 511(B)2310	EPOXY COATED REINFORCING STEEL	1,130.000	LB
0290 513(C)4400	CLASS C BRIDGE DECK REPAIR	30.000	SY
0300 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	626.000	SY
0310 517 9110	ELASTOMERIC COATING	280.000	SF
0320 518(B)0300	SEALED EXPANSION JOINTS	70.000	LF
0330 523(A)3200	SEALER CRACK PREPARATION	118.900	LF
0340 523(B)3300	SEALER RESIN	4.700	GAL
0350 523(D)3500	(SP) MULTI-COAT SEALER(PERFORMANCE TSTD)	1,017.000	SY
0360 540 8116	(PL)REPAIR BRIDGE ITEM (TYPE A)	1.000	LSUM
0370 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	331.000	TON
0380 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	38.000	LF
0390 613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	40.000	LF
0400 619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC SIGNING AND STRIPING		
0410 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	4.000	EA
0420 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	2,251.000	LF

Proposal:260292

Let Date:November 12, 2026

Call Order:320

J/P Num:38191(04)

Proj. Num:SBR-253B(096)SB

Counties:JOHNSTON

Description:BRIDGE REHABILITATION

SH-22: OVER PENNINGTON CREEK, 0.37 MILES WEST
OF THE US-377 JUNCTION IN THE CITY OF TISHOMINGO.
PROJECT LENGTH = 0.067 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004	TRAFFIC CONTROL		
0430 823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	180.000	SD
0440 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	2,536.000	LF
0450 857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	4,787.000	LF
0460 871(B)2300	CONST.ZONE IMPACT ATTEN.	360.000	SD
0470 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	595.000	LF
0480 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	595.000	LF
0490 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	900.000	SD
0500 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,080.000	SD
0510 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,340.000	SD
0520 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,350.000	SD
0530 880(E)6607	WARNING LIGHTS(TYPE B)	5,040.000	SD
0540 880(F)6700	DRUMS	1,440.000	SD
0550 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	540.000	HOURL
0560 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	568.000	SD
0005	STAKING		
0570 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006	CONSTRUCTION		
0580 641 2100	MOBILIZATION	1.000	LSUM