**Proposal:**260293 **Let Date:**January 14, 2027 **Call Order:**556
**J/P Num:**36716(04) **Proj. Num:**STP-255D(768)AG
**Counties:**OKLAHOMA
**Description:**PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
CITY STREETS (SOUTH SANTA FE DRIVE / WEST HURD STREET):
AT MULTIPLE LOCATIONS IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.451 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | ROADWAY | | | |
| 0010 | 201(A)1200 | CLEARING AND GRUBBING | 1.000 | LSUM |
| 0020 | 202(A)2200 | UNCLASSIFIED EXCAVATION | 183.000 | CY |
| 0030 | 202(H)2900 | EARTHWORK | 1.000 | LSUM |
| 0040 | 221(B)2300 | TEMPORARY SILT FENCE | 5,021.000 | LF |
| 0050 | 221(C)2400 | TEMPORARY SEDIMENT FILTER | 7.000 | EA |
| 0060 | 230(A)7200 | SOLID SLAB SODDING | 1,391.000 | SY |
| 0070 | 230(F)7700 | WATERING | 55.640 | KGAL |
| 0080 | 234(A)1200 | FERTILIZING (10-20-10) | 0.140 | TON |
| 0090 | 240(A)2200 | REMOVING TREES 6" TO 12" IN DIAMETER | 2.000 | EA |
| 0100 | 240(A)2220 | REMOVING TREES 19" TO 24" IN DIAMETER | 4.000 | EA |
| 0110 | 303(A)1200 | AGGREGATE BASE TYPE A | 330.000 | CY |
| 0120 | 501(F)1700 | GRANULAR BACKFILL | 500.000 | CY |
| 0130 | 509(D)0500 | CLASS C CONCRETE | 1.000 | CY |
| 0140 | 609 4100 | (PL) PARKING BLOCK | 4.000 | EA |
| 0150 | 609(A)4200 | CONC.CURB(2" MNTBLE-INTEGRAL) | 63.000 | LF |
| 0160 | 609(A)4240 | CONC.CURB(6" BARRIER-DOWELLED) | 83.000 | LF |
| 0170 | 609(B)4310 | COMBINED CURB & GUTTER(6" BARRIER) | 67.000 | LF |
| 0180 | 610(A)5200 | 4" CONCRETE SIDEWALK | 1,940.000 | SY |
| 0190 | 610(A)5220 | 6" CONCRETE SIDEWALK | 35.000 | SY |
| 0200 | 610(B)5300 | 6" CONCRETE DRIVEWAY (H.E.S.) | 843.000 | SY |
| 0210 | 610(I)6000 | TACTILE WARNING DEVICE-NEW | 210.000 | SF |
| 0220 | 612(A)3200 | MANHOLES ADJUST TO GRADE | 1.000 | EA |
| 0230 | 612(C)3400 | INLET ADJUST TO GRADE | 1.000 | EA |
| 0240 | 612(I)4000 | WATER METER RESET | 6.000 | EA |
| 0250 | 613(B)5508 | 18" CORR. GALV. STEEL PIPE | 70.000 | LF |
| 0260 | 613(B)5524 | 30" CORR. GALV. STEEL PIPE | 70.000 | LF |
| 0270 | 613(L)6708 | 18" PREFAB. CULVERT END SEC., ROUND | 2.000 | EA |
| 0280 | 613(L)6724 | 30" PREFAB. CULVERT END SEC., ROUND | 2.000 | EA |
| 0290 | 616(M)3705 | WATER VALVE RISER ADJUST TO GRADE | 1.000 | EA |
| 0300 | 619(B)6356 | REMOVAL OF CURB AND GUTTER | 51.000 | LF |
| 0310 | 619(B)6380 | REMOVAL OF CONCRETE DRIVEWAY | 443.000 | SY |
| 0320 | 619(B)6384 | REMOVAL OF ASPHALT DRIVEWAY | 439.000 | SY |
| 0330 | 619(B)6386 | REMOVAL OF GRAVEL DRIVEWAY | 64.000 | SY |
| 0340 | 619(B)6404 | REMOVAL OF SIDEWALK | 295.000 | SY |
| **0002** | TRAFFIC SIGNING AND STRIPING | | | |
| 0350 | 805(B)3300 | (PL)RESET OF PULL BOX | 2.000 | EA |
| 0360 | 805(D)3536 | (PL)REMOVE & RESET GROUND MOUNTED SIGN | 2.000 | EA |
| 0370 | 856(A)8203 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE) | 111.000 | LF |
| 0380 | 856(A)8219 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE) | 393.000 | LF |
| 0390 | 857(F)9700 | PAVEMENT MRKNG.REMOVAL(TRAF.STRP) | 18.000 | LF |

**Proposal:**260293 **Let Date:**January 14, 2027 **Call Order:**556
**J/P Num:**36716(04) **Proj. Num:**STP-255D(768)AG
**Counties:**OKLAHOMA
**Description:**PEDESTRIAN IMPROVEMENTS (SIDEWALKS)
CITY STREETS (SOUTH SANTA FE DRIVE / WEST HURD STREET):
AT MULTIPLE LOCATIONS IN THE CITY OF EDMOND.
PROJECT LENGTH = 0.451 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0003** | TRAFFIC LIGHTING | | | |
| 0400 | 802(B)0320 | 2" PVC SCH.40 PLASTIC CONDUIT BORED | 2,200.000 | LF |
| 0410 | 802(B)0324 | 2" PVC SCH.40 PLASTIC CONDUIT TRENCHED | 5,110.000 | LF |
| 0420 | 803(A)1210 | PULL BOX(SIZE I) | 44.000 | EA |
| 0430 | 804(A)2200 | STRUCTURAL CONCRETE | 14.500 | CY |
| 0440 | 804(B)2300 | REINFORCING STEEL | 835.000 | LB |
| 0450 | 806(E)4700 | DECORATIVE POLE AND MAST ARM | 25.000 | EA |
| 0460 | 809(A)7200 | ROADWAY LUMINAIRE | 25.000 | EA |
| 0470 | 811 9115 | 1/C NO.4 ELECT.COND. | 22,190.000 | LF |
| **0004** | TEMPORARY TRAFFIC CONTROL | | | |
| 0480 | 104 3250 | (SP) RAILROAD FLAGGING(NON-BIDDABLE) | 60.000 | DAY |
| 0490 | 880(J)7100 | (SP) CONSTRUCTION TRAFFIC CONTROL | 120.000 | SD |
| 0500 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 120.000 | SD |
| **0005** | STAKING | | | |
| 0510 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0006** | CONSTRUCTION | | | |
| 0520 | 641 2110 | MOBILIZATION | 1.000 | LSUM |