

Proposal:260296

Let Date:November 12, 2026

Call Order:350

J/P Num:36362(04)

Proj. Num:SBR-263N(129)SB

Counties:POTTAWATOMIE

Description:BRIDGE REHABILITATION

US-270: OVER NORTH CANADIAN RIVER, 0.4 MILES FROM THE JUNCTION OF US-177 NEAR SHAWNEE.

PROJECT LENGTH = 0.152 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	BRIDGE 'A'		
0010 201 1100	(PL)REMOVE DRIFT AND SILT	1.000	LSUM
0020 502(B)3320	(PL)FALSEWORK JACKING	1.000	LSUM
0030 506(A)7200	STRUCTURAL STEEL	3,500.000	LB
0040 512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0050 512(B)3300	COLLECTION AND HANDLING OF WASTE	1.000	LSUM
0060 512(C)3400	TREATING PACK RUST WITH PENETRAT. SEALER	140.000	EA
0070 513(B)4300	CLASS B BRIDGE DECK REPAIR	110.000	SY
0080 513(C)4400	CLASS C BRIDGE DECK REPAIR	50.000	SY
0090 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	272.000	SY
0100 515(B)7300	WATER REPELLENT (PERFORMANCE TESTED)	5,530.000	SY
0110 517 9110	ELASTOMERIC COATING	3,221.000	SF
0120 518(C)0400	RAPID CURE JOINT SEALANT	2,167.000	LF
0130 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0140 520(C)1400	EPOXY RESIN, ABOVE WATER	1.500	GAL
0150 521(A)2200	PNEUMATICALLY PLACED MORTAR	15.700	SY
0160 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	19.900	SY
0170 545 0111	(PL)REPLACE BRIDGE ITEM (TYPE A)	3.000	EA
0180 545 0121	(PL)REPLACE BRIDGE ITEM (TYPE B)	8.000	EA
0002	TRAFFIC SIGNING AND STRIPING		
0190 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	8,520.000	LF
0003	TRAFFIC CONTROL		
0200 857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	16,600.000	LF
0210 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	7,140.000	LF
0220 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	356.000	EA
0230 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	480.000	EA
0240 871(B)2300	CONST.ZONE IMPACT ATTEN.	240.000	SD
0250 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	2,525.000	LF
0260 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	2,500.000	LF
0270 880(A)6220	ARROW DISPLAY(TYPE C)	240.000	SD
0280 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,840.000	SD
0290 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,340.000	SD
0300 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	4,620.000	SD
0310 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	600.000	SD
0320 880(E)6607	WARNING LIGHTS(TYPE B)	3,900.000	SD
0330 880(F)6700	DRUMS	7,680.000	SD
0340 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	762.000	SD
0004	STAKING		
0350 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION		
0360 641 2100	MOBILIZATION	1.000	LSUM