

Proposal:260299
J/P Num:36451(04)
Counties:TULSA

Let Date:November 12, 2026
Proj. Num:STP-272B(477)IG

Call Order:365

Description:RESURFACE (ASPHALT)

CITY STREETS (SHERIDAN ROAD/MINGO ROAD): SHERIDAN ROAD,
FROM 81ST STREET EXTEND NORTH IN THE CITY OF TULSA.
MINGO ROAD, FROM 71ST STREET EXTEND NORTH IN THE CITY OF TULSA.
PROJECT LENGTH = 1.573 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY (SHERIDAN RD.)		
0010	202(A)2200 UNCLASSIFIED EXCAVATION	85.000	CY
0020	221(H)2910 INLET PROTECTION	960.000	LF
0030	230(A)7200 SOLID SLAB SODDING	4.000	SY
0040	303(A)1200 AGGREGATE BASE TYPE A	85.000	CY
0050	310(B)5300 SUBGRADE, METHOD B	252.000	SY
0060	325 0100 SEPARATOR FABRIC	297.000	SY
0070	326(C)1100 (SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	30,188.000	SY
0080	411(C)1420 SUPERPAVE, TYPE S4(PG 70-28 OK)	3,381.000	TON
0090	411(E)1610 SUPERPAVE, TYPE S6(PG 70-28 OK)	1,691.000	TON
0100	411(H)1900 SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	99.000	TON
0110	412 3100 COLD MILLING PAVEMENT	30,188.000	SY
0120	501(G)1810 CLSM BACKFILL	11.000	CY
0130	609(B)4375 2'-8" COMB.CRB.& GUT.(8" BARRIER)	7.000	LF
0140	610(A)5200 4" CONCRETE SIDEWALK	11.000	SY
0150	612(A)3200 MANHOLES ADJUST TO GRADE	2.000	EA
0160	612(E)3600 VALVE BOXES ADJUST TO GRADE	6.000	EA
0170	612(F)3700 METER BOXES ADJUST TO GRADE	4.000	EA
0180	619(A)6200 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0190	619(B)6392 REMOVAL OF EXISTING STRUCTURES	1.000	EA
0200	619(B)6404 REMOVAL OF SIDEWALK	11.000	SY
0002	ROADWAY (MINGO RD.)		
0210	202(A)2200 UNCLASSIFIED EXCAVATION	75.000	CY
0220	221(H)2910 INLET PROTECTION	580.000	LF
0230	303(A)1200 AGGREGATE BASE TYPE A	75.000	CY
0240	310(B)5300 SUBGRADE, METHOD B	223.000	SY
0250	325 0100 SEPARATOR FABRIC	253.000	SY
0260	326(C)1100 (SP) WOVEN GEOSYNTHETIC REINFORCEMENT FABRIC	28,408.000	SY
0270	411(C)1420 SUPERPAVE, TYPE S4(PG 70-28 OK)	3,182.000	TON
0280	411(E)1610 SUPERPAVE, TYPE S6(PG 70-28 OK)	1,591.000	TON
0290	411(H)1900 SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	44.000	TON
0300	412 3100 COLD MILLING PAVEMENT	28,408.000	SY
0310	414(E)5600 FULL DEPTH P.C.C. PATCH (PLACEMENT)	110.000	SY
0320	414(G)5800 P.C. CONCRETE FOR PAVEMENT	28.000	CY
0330	501(G)1810 CLSM BACKFILL	10.000	CY
0340	612(A)3200 MANHOLES ADJUST TO GRADE	9.000	EA
0350	612(E)3600 VALVE BOXES ADJUST TO GRADE	8.000	EA
0360	612(F)3700 METER BOXES ADJUST TO GRADE	2.000	EA
0370	619(A)6200 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM

Proposal:260299
J/P Num:36451(04)
Counties:TULSA

Let Date:November 12, 2026
Proj. Num:STP-272B(477)IG

Call Order:365

Description:RESURFACE (ASPHALT)

CITY STREETS (SHERIDAN ROAD/MINGO ROAD): SHERIDAN ROAD,
FROM 81ST STREET EXTEND NORTH IN THE CITY OF TULSA.
MINGO ROAD, FROM 71ST STREET EXTEND NORTH IN THE CITY OF TULSA.
PROJECT LENGTH = 1.573 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 TRAFFIC TEMPORARY (SHERIDAN RD.)			
0380	857(C)9400 REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	11,496.000	LF
0390	880(A)6200 ARROW DISPLAY(TYPE A)	180.000	SD
0400	880(B)6300 CONSTRUCTION SIGNS 0 TO 6.25 SF	2,820.000	SD
0410	880(B)6310 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	7,480.000	SD
0420	880(B)6320 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,860.000	SD
0430	880(C)6410 CONSTRUCTION BARRICADES(TYPE III)	5,980.000	SD
0440	880(E)6600 WARNING LIGHTS(TYPE A)	11,960.000	SD
0450	880(E)6610 WARNING LIGHTS(TYPE C)	48,770.000	SD
0460	880(F)6700 DRUMS	17,000.000	SD
0470	880(G)6805 CHANNELIZER CONES	17,610.000	SD
0480	880(I)7000 FLAGGER	60.000	SD
0490	882(A)8210 PORT.CHANGEABLE MESSAGE SIGN	180.000	SD
0004 TRAFFIC PERMANENT (SHERIDAN RD.)			
0500	850(A)1200 SHEET ALUMINUM SIGNS	170.000	SF
0510	851(C)2405 1 1/2" SQUARE TUBE POST	18.000	LF
0520	851(C)2410 1 3/4" SQUARE TUBE POST	161.000	LF
0530	851(C)2415 2" SQUARE TUBE POST	45.000	LF
0540	855(A)7201 (SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	11,496.000	LF
0550	855(B)7305 (SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	40.000	EA
0005 TRAFFIC TEMPORARY (MINGO RD.)			
0560	857(C)9400 REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	12,141.000	LF
0570	880(A)6200 ARROW DISPLAY(TYPE A)	240.000	SD
0580	880(B)6300 CONSTRUCTION SIGNS 0 TO 6.25 SF	1,675.000	SD
0590	880(B)6310 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,120.000	SD
0600	880(B)6320 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,490.000	SD
0610	880(C)6410 CONSTRUCTION BARRICADES(TYPE III)	6,180.000	SD
0620	880(E)6600 WARNING LIGHTS(TYPE A)	6,180.000	SD
0630	880(E)6610 WARNING LIGHTS(TYPE C)	16,285.000	SD
0640	880(F)6700 DRUMS	25,360.000	SD
0650	880(G)6805 CHANNELIZER CONES	29,685.000	SD
0660	880(I)7000 FLAGGER	80.000	SD
0670	882(A)8210 PORT.CHANGEABLE MESSAGE SIGN	240.000	SD

Proposal:260299
J/P Num:36451(04)
Counties:TULSA

Let Date:November 12, 2026
Proj. Num:STP-272B(477)IG

Call Order:365

Description:RESURFACE (ASPHALT)

CITY STREETS (SHERIDAN ROAD/MINGO ROAD): SHERIDAN ROAD,
FROM 81ST STREET EXTEND NORTH IN THE CITY OF TULSA.
MINGO ROAD, FROM 71ST STREET EXTEND NORTH IN THE CITY OF TULSA.
PROJECT LENGTH = 1.573 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0006	TRAFFIC PERMANENT (MINGO RD.)		
0680 805(A)3200	REMOVAL OF SIGN FOOTING	1.000	EA
0690 805(C)3410	LIGHT POLE FOOTING REPLACEMENTS	1.000	LSUM
0700 805(D)3500	(PL)REMOVE & RESET TRAF.SIG.EQUIPMENT	1.000	LSUM
0710 850(A)1200	SHEET ALUMINUM SIGNS	188.000	SF
0720 851(C)2405	1 1/2" SQUARE TUBE POST	20.000	LF
0730 851(C)2410	1 3/4" SQUARE TUBE POST	214.000	LF
0740 851(C)2415	2" SQUARE TUBE POST	57.000	LF
0750 855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	12,141.000	LF
0760 855(A)7209	(SP) TRAFFIC STRIPE(PLASTIC)(8" WIDE)	1,087.000	LF
0770 855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	455.000	LF
0780 855(B)7305	(SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	34.000	EA
0790 855(B)7313	(SP) TRAFFIC STRIPE(PLASTIC)(SYMBOLS)	32.000	EA
0007	STAKING		
0800 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0008	CONSTRUCTION		
0810 641 2110	MOBILIZATION	1.000	LSUM