

Proposal:260302

Let Date:November 19, 2026

Call Order:042

J/P Num:37100(17)

Proj. Num:EWC-28803B

Counties:CLEVELAND

Description:GRADE, DRAIN AND BRIDGE

TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/ 36TH AVENUE
NW:

FROM 0.3 MILES WEST OF I-35 INTERSECTION, EXTEND WEST NEAR NORMAN.

PROJECT LENGTH = 0.078 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	9,405.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	240,376.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(C)2400	TEMPORARY SEDIMENT FILTER	4.000	EA
0060 221(C)2410	REINFORCED SILT FENCE	3,341.000	LF
0070 221(E)2600	TEMPORARY SILT DIKE	210.000	LF
0080 221(G)2800	TEMPORARY FIBER LOG	6,340.000	LF
0090 230(A)7200	SOLID SLAB SODDING	60,582.000	SY
0100 233(E)0600	(SP) HYDROMULCH	60,582.000	SY
0110 242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0120 509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	4.000	CY
0130 611(G)0354	INLET (SMD-TYPE 2)	1.000	EA
0140 611(G)0362	INLET (SMD-TYPE 2B)	1.000	EA
0150 611(L)1600	JUNCTION BOXES	250.000	CF
0160 613(A)5314	24" R.C.PIPES CLASS V	318.000	LF
0170 613(A)5316	30" R.C.PIPES CLASS V	868.000	LF
0180 613(A)5358	28" X 18" R.C.PIPES ARCH CLASS A-III	106.000	LF
0190 613(A)5374	51" X 31" R.C.PIPES ARCH CLASS A-III	204.000	LF
0200 613(L)6620	28" X 18" PREFAB. CULVERT END SEC., ARCH	1.000	EA
0210 613(M)6904	TYPE B3 CULVERT END TREATMENT	1.000	EA
0220 613(M)6928	TYPE CC3 CULVERT END TREATMENT	3.000	EA
0230 613(Q)7500	OUTLET LATERAL HEADWALL	8.000	EA
0240 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM

Proposal:260302**Let Date:**November 19, 2026**Call Order:**042**J/P Num:**37100(17)**Proj. Num:**EW-28803B**Counties:**CLEVELAND**Description:**GRADE, DRAIN AND BRIDGETOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/ 36TH AVENUE
NW:

FROM 0.3 MILES WEST OF I-35 INTERSECTION, EXTEND WEST NEAR NORMAN.

PROJECT LENGTH = 0.078 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE TPO 113.64 WB		
0250 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0260 501(G)1800	CLSM BACKFILL	188.400	CY
0270 504(A)5200	APPROACH SLAB	273.400	SY
0280 504(B)5300	SAW-CUT GROOVING	1,742.500	SY
0290 504(E)5520	42" F-SHAPED PARAPET	824.700	LF
0300 506(A)7200	STRUCTURAL STEEL	524,680.000	LB
0310 507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	15.000	EA
0320 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	15.000	EA
0330 509(A)0210	CLASS AA CONCRETE	370.800	CY
0340 509(B)0320	CLASS A CONCRETE	228.600	CY
0350 509(D)0510	CLASS C CONCRETE	11.000	CY
0360 510(C)1450	SLOPE WALL (5")	1,202.000	SY
0370 510(D)1500	GRAFFITI TREATMENT	18,303.000	SF
0380 511(A)2210	REINFORCING STEEL	1,930.000	LB
0390 511(B)2310	EPOXY COATED REINFORCING STEEL	121,310.000	LB
0400 514(A)5210	PILES, FURNISHED (HP 10X42)	168.000	LF
0410 514(A)5220	PILES, FURNISHED (HP 12X53)	832.000	LF
0420 514(B)5310	PILES, DRIVEN (HP 10X42)	168.000	LF
0430 514(B)5320	PILES, DRIVEN (HP 12X53)	832.000	LF
0440 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0450 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,895.000	SY
0460 516(A)8250	DRILLED SHAFTS 72" DIAMETER	104.000	LF
0470 516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0480 517 9110	ELASTOMERIC COATING	1,162.400	SF
0490 518(B)0310	EXPANSION JOINT SYSTEM	80.350	LF
0500 535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0510 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	218.000	LF
0520 613(I)6310	6" NON-PERF.PIPES UNDERDRAIN RND.	95.000	LF

Proposal:260302

Let Date:November 19, 2026

Call Order:042

J/P Num:37100(17)

Proj. Num:EWC-28803B

Counties:CLEVELAND

Description:GRADE, DRAIN AND BRIDGE

TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/ 36TH AVENUE
NW:

FROM 0.3 MILES WEST OF I-35 INTERSECTION, EXTEND WEST NEAR NORMAN.

PROJECT LENGTH = 0.078 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003	BRIDGE TPO 113.64 EB		
0530 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	200.000	CY
0540 501(G)1800	CLSM BACKFILL	188.400	CY
0550 504(A)5200	APPROACH SLAB	273.400	SY
0560 504(B)5300	SAW-CUT GROOVING	1,742.500	SY
0570 504(E)5520	42" F-SHAPED PARAPET	824.700	LF
0580 506(A)7200	STRUCTURAL STEEL	524,680.000	LB
0590 507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	15.000	EA
0600 507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	15.000	EA
0610 509(A)0210	CLASS AA CONCRETE	370.800	CY
0620 509(B)0320	CLASS A CONCRETE	228.600	CY
0630 509(D)0510	CLASS C CONCRETE	5.000	CY
0640 510(C)1450	SLOPE WALL (5")	1,204.000	SY
0650 510(D)1500	GRAFFITI TREATMENT	18,360.000	SF
0660 511(A)2210	REINFORCING STEEL	1,930.000	LB
0670 511(B)2310	EPOXY COATED REINFORCING STEEL	121,310.000	LB
0680 514(A)5210	PILES, FURNISHED (HP 10X42)	172.000	LF
0690 514(A)5220	PILES, FURNISHED (HP 12X53)	854.000	LF
0700 514(B)5310	PILES, DRIVEN (HP 10X42)	172.000	LF
0710 514(B)5320	PILES, DRIVEN (HP 12X53)	854.000	LF
0720 514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0730 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	2,895.000	SY
0740 516(A)8250	DRILLED SHAFTS 72" DIAMETER	102.000	LF
0750 516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
0760 517 9110	ELASTOMERIC COATING	1,162.400	SF
0770 518(B)0310	EXPANSION JOINT SYSTEM	80.350	LF
0780 535 7200	(SP) AESTHETIC TREATMENT	1.000	LSUM
0790 613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	218.000	LF
0800 613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	95.000	LF
0004	TRAFFIC SIGNING AND STRIPING		
0810 850(A)1200	SHEET ALUMINUM SIGNS	56.000	SF
0005	TRAFFIC CONTROL		
0820 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,960.000	SD
0830 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,060.000	SD
0840 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	840.000	SD
0850 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	840.000	SD
0860 880(E)6607	WARNING LIGHTS(TYPE B)	2,640.000	SD
0870 880(I)7000	FLAGGER	20.000	SD
0880 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,680.000	HOURL
0890 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	448.000	SD
0006	STAKING		
0900 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:260302

Let Date:November 19, 2026

Call Order:042

J/P Num:37100(17)

Proj. Num:EW-28803B

Counties:CLEVELAND

Description:GRADE, DRAIN AND BRIDGE

TOBY KEITH EXPRESSWAY TURNPIKE(OTA ACCESS) / INDIAN HILLS ROAD/ 36TH AVENUE
NW:

FROM 0.3 MILES WEST OF I-35 INTERSECTION, EXTEND WEST NEAR NORMAN.

PROJECT LENGTH = 0.078 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0007	CONSTRUCTION		
0910 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0920 641 2100	MOBILIZATION	1.000	LSUM