

Proposal:260303**Let Date:**November 19, 2026**Call Order:**044**J/P Num:**36893(04)**Proj. Num:**IN-MC-78

38909(04)

IN-MC-80

Counties:MCINTOSH, PITTSBURG**Description:**BRIDGE REHABILITATION

INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH
CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE
SH-9 INTERCHANGE NEAR VERNON.

PROJECT LENGTH = 0.894 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	400.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	530.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	990.000	LF
0060 230(A)7200	SOLID SLAB SODDING	2,105.000	SY
0070 233(A)0200	VEGETATIVE MULCHING	0.350	AC
0080 241 3100	MOWING	0.700	AC
0090 307(K)4200	STABILIZED SUBGRADE	604.000	SY
0100 310(B)5300	SUBGRADE, METHOD B	100.000	SY
0110 407(B)7300	TACK COAT	77.000	GAL
0120 408 8100	PRIME COAT	335.000	GAL
0130 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	187.000	TON
0140 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	115.000	TON
0150 413(A)4200	RUMBLE STRIP-METHOD HMA-CON	453.000	LF
0160 413(C)4400	RUMBLE STRIP-METHOD PCC-CON	120.000	LF
0170 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	100.000	SY
0180 414(G)5800	P.C. CONCRETE FOR PAVEMENT	14.000	CY
0190 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	100.000	SY
0200 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	4,530.000	SY
0210 619(B)6396	REMOVAL OF GUARDRAIL	430.000	LF
0220 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	325.000	LF
0230 623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0240 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
0250 625(B)4300	REMOVE AND RECONSTRUCT FENCE	240.000	LF
0260 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	14.000	EA

Proposal:260303

Let Date:November 19, 2026

Call Order:044

J/P Num:36893(04)

Proj. Num:IN-MC-78

38909(04)

IN-MC-80

Counties:MCINTOSH, PITTSBURG

Description:BRIDGE REHABILITATION

INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH
CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE
SH-9 INTERCHANGE NEAR VERNON.

PROJECT LENGTH = 0.894 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE		
0270 501(G)1800	CLSM BACKFILL	10.000	CY
0280 504(A)5200	APPROACH SLAB	76.200	SY
0290 504(B)5300	SAW-CUT GROOVING	3,038.500	SY
0300 504(E)5500	CONCRETE PARAPET	61.350	LF
0310 509 0100	SPECIAL CONCRETE FINISH	1,323.000	SY
0320 509(A)0210	CLASS AA CONCRETE	691.700	CY
0330 509(B)0320	CLASS A CONCRETE	20.000	CY
0340 509(D)0510	CLASS C CONCRETE	12.000	CY
0350 511(B)2310	EPOXY COATED REINFORCING STEEL	165,650.000	LB
0360 512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0370 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	31,806.000	SY
0380 517 9110	ELASTOMERIC COATING	6,068.000	SF
0390 518(B)0310	EXPANSION JOINT SYSTEM	580.000	LF
0400 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	550.000	LF
0410 520(C)1400	EPOXY RESIN, ABOVE WATER	48.000	GAL
0420 521(A)2200	PNEUMATICALLY PLACED MORTAR	182.000	SY
0430 523(A)3200	SEALER CRACK PREPARATION	4,011.000	LF
0440 523(B)3300	SEALER RESIN	47.000	GAL
0450 524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	3,040.000	SF
0460 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	74.000	SY
0470 540 8120	(PL)REPAIR BRIDGE ITEM (TYPE A)	4.000	EA
0480 619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM

Proposal:260303**Let Date:**November 19, 2026**Call Order:**044**J/P Num:**36893(04)**Proj. Num:**IN-MC-78

38909(04)

IN-MC-80

Counties:MCINTOSH, PITTSBURG**Description:**BRIDGE REHABILITATIONINDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH
CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE
SH-9 INTERCHANGE NEAR VERNON.

PROJECT LENGTH = 0.894 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0009	ROADWAY		
0490 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0500 202(A)2200	UNCLASSIFIED EXCAVATION	400.000	CY
0510 202(D)2500	UNCLASSIFIED BORROW	2,150.000	CY
0520 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0530 221(B)2300	TEMPORARY SILT FENCE	4,701.000	LF
0540 230(A)7200	SOLID SLAB SODDING	6,229.000	SY
0550 233(A)0200	VEGETATIVE MULCHING	1.200	AC
0560 241 3100	MOWING	2.400	AC
0570 307(K)4200	STABILIZED SUBGRADE	7,285.000	SY
0580 310(B)5300	SUBGRADE, METHOD B	476.000	SY
0590 407(B)7300	TACK COAT	728.000	GAL
0600 408 8100	PRIME COAT	3,873.000	GAL
0610 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	1,921.000	TON
0620 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	1,072.000	TON
0630 413(A)4200	RUMBLE STRIP-METHOD HMA-CON	4,323.000	LF
0640 413(C)4400	RUMBLE STRIP-METHOD PCC-CON	571.000	LF
0650 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	476.000	SY
0660 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	1,521.000	SY
0670 414(G)5800	P.C. CONCRETE FOR PAVEMENT	447.000	CY
0680 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	1,996.000	SY
0690 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	43,230.000	SY
0700 619(B)6396	REMOVAL OF GUARDRAIL	4,175.000	LF
0710 623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	3,975.000	LF
0720 623(G)1820	GUARDRAIL END TREATMENT (31")	1.000	EA
0730 623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	3.000	EA
0740 625(B)4300	REMOVE AND RECONSTRUCT FENCE	765.000	LF
0750 853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	52.000	EA

Proposal:260303**Let Date:**November 19, 2026**Call Order:**044**J/P Num:**36893(04)**Proj. Num:**IN-MC-78

38909(04)

IN-MC-80

Counties:MCINTOSH, PITTSBURG**Description:**BRIDGE REHABILITATIONINDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH
CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE
SH-9 INTERCHANGE NEAR VERNON.

PROJECT LENGTH = 0.894 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0010	BRIDGE		
0760 501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	120.000	CY
0770 501(G)1800	CLSM BACKFILL	240.000	CY
0780 503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	3,983.350	LF
0790 504(A)5200	APPROACH SLAB	358.400	SY
0800 504(B)5300	SAW-CUT GROOVING	3,500.000	SY
0810 504(E)5520	42" F-SHAPED PARAPET	886.000	LF
0820 506(A)7225	STRUCTURAL STEEL M270 GRADE 50W	4,350.000	LB
0830 507(A)8210	WEATHERING STEEL FIXED BEARING ASSEMBLY	60.000	EA
0840 507(B)8310	WEATHERING STL EXP. BEARING ASSEMBLY	30.000	EA
0850 509(A)0210	CLASS AA CONCRETE	908.600	CY
0860 509(B)0320	CLASS A CONCRETE	20.000	CY
0870 509(D)0510	CLASS C CONCRETE	12.000	CY
0880 511(B)2310	EPOXY COATED REINFORCING STEEL	173,238.000	LB
0890 513(B)4300	CLASS B BRIDGE DECK REPAIR	35.000	SY
0900 515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	8,937.000	SY
0910 517 9110	ELASTOMERIC COATING	1,984.000	SF
0920 518(B)0310	EXPANSION JOINT SYSTEM	144.000	LF
0930 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	184.000	LF
0940 520(C)1400	EPOXY RESIN, ABOVE WATER	17.500	GAL
0950 521(A)2200	PNEUMATICALLY PLACED MORTAR	98.000	SY
0960 523(A)3200	SEALER CRACK PREPARATION	1,015.000	LF
0970 523(B)3300	SEALER RESIN	12.000	GAL
0980 524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	35.000	SF
0990 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	258.000	SY
1000 619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0011	TRAFFIC CONTROL		
1010 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	45,180.000	LF
1020 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	45,180.000	LF
1030 871(B)2300	CONST.ZONE IMPACT ATTEN.	2,210.000	SD
1040 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	9,850.000	LF
1050 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	9,850.000	LF
1060 880(A)6220	ARROW DISPLAY(TYPE C)	1,860.000	SD
1070 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,150.000	SD
1080 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,880.000	SD
1090 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	7,200.000	SD
1100 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	8,820.000	SD
1110 880(E)6600	WARNING LIGHTS(TYPE A)	16,000.000	SD
1120 880(F)6700	DRUMS	51,824.000	SD
1130 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	480.000	HOURL
1140 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	640.000	SD
0012	TRAFFIC - SIGNING AND STRIPING		
1150 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	61,224.000	LF

Proposal:260303

Let Date:November 19, 2026

Call Order:044

J/P Num:36893(04)

Proj. Num:IN-MC-78

38909(04)

IN-MC-80

Counties:MCINTOSH, PITTSBURG

Description:BRIDGE REHABILITATION

INDIAN NATION TURNPIKE/SH-375 (OTA ACCESS): OVER SOUTH
CANADIAN RIVER AND OVERFLOW, 8.6 MILES SOUTH OF THE
SH-9 INTERCHANGE NEAR VERNON.

PROJECT LENGTH = 0.894 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0013	TRAFFIC - CABLE BARRIER		
1160 509(A)0200	CLASS AA CONCRETE	51.230	CY
1170 619(B)6432	REMOVAL OF CABLE BARRIER	6,164.000	LF
1180 628(B)7300	HIGH-TENSION CABLE BARRIER(TL-4)	6,164.000	LF
1190 628(C)7400	END ANCHORS	4.000	EA
0014	STAKING		
1200 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0015	CONSTRUCTION		
1210 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1220 641 2100	MOBILIZATION	1.000	LSUM