

Proposal:260305

Let Date:November 19, 2026

Call Order:048

J/P Num:38910(04)

Proj. Num:MU-MC-56

Counties:WAGONER

Description:BRIDGE REHABILITATION

OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770):
OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 I
NTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

Line #	Item Description	Quantity	Unit
0001	ROADWAY		
0010	201(A)1200 CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200 UNCLASSIFIED EXCAVATION	34,484.000	CY
0030	202(C)2400 ROCK EXCAVATION	1,000.000	CY
0040	205(A)6200 TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300 TEMPORARY SILT FENCE	4,963.000	LF
0060	221(E)2600 TEMPORARY SILT DIKE	973.000	LF
0070	221(F)2710 TEMPORARY ROCK FILTER DAM TYPE 2	29.000	CY
0080	221(H)2900 (PL)TEMPORARY INLET SEDIMENT FILTER	4.000	EA
0090	230(A)7200 SOLID SLAB SODDING	44,635.000	SY
0100	233(A)0200 VEGETATIVE MULCHING	9.220	AC
0110	241 3100 MOWING	18.440	AC
0120	242 4101 STABILIZED CONSTRUCTION EXIT	1.000	EA
0130	303(A)1200 AGGREGATE BASE TYPE A	5,299.000	CY
0140	307(K)4200 STABILIZED SUBGRADE	20,818.000	SY
0150	325 0100 SEPARATOR FABRIC	14,280.000	SY
0160	402(E)2600 TRAFFIC BOUND SURFACE COURSE TYPE E	3,749.000	TON
0170	407(B)7300 TACK COAT	997.000	GAL
0180	408 8100 PRIME COAT	444.000	GAL
0190	411(B)1330 SUPERPAVE, TYPE S3(PG 64-22 OK)	1,982.000	TON
0200	411(C)1430 SUPERPAVE, TYPE S4(PG 64-22 OK)	648.000	TON
0210	414(A)5200 P.C.CONCRETE PAVEMENT(PLACEMENT)	5,330.000	SY
0220	414(B)5300 DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	6,580.000	SY
0230	414(G)5800 P.C. CONCRETE FOR PAVEMENT	3,170.000	CY
0240	501(A)1200 STRUCTURAL EXCAVATION UNCLASSIFIED	34.000	CY
0250	509(B)0300 CLASS A CONCRETE	82.000	CY
0260	509(D)0500 CLASS C CONCRETE	550.000	CY
0270	511(A)2200 REINFORCING STEEL	11,232.000	LB
0280	601(A)1100 TYPE I PLAIN RIPRAP	88.000	TON
0290	611(G)7978 INLET GPI TYPE 2 (DES. 12)	1.000	EA
0300	611(G)7982 INLET GPI TYPE 2 (DES. 13)	1.000	EA
0310	611(G)9039 PRECAST INLET (CDI RCP DES. 1B)	1.000	EA
0320	611(G)9040 PRECAST INLET (CDI RCP DES. 2)	1.000	EA
0330	613(A)5208 18" R.C.PIPE CLASS III	40.000	LF
0340	613(A)5216 24" R.C.PIPE CLASS III	174.000	LF
0350	613(A)5220 30" R.C.PIPE CLASS III	234.000	LF
0360	613(L)6708 18" PREFAB. CULVERT END SEC., ROUND	1.000	EA
0370	613(L)6716 24" PREFAB. CULVERT END SEC., ROUND	2.000	EA
0380	613(L)6724 30" PREFAB. CULVERT END SEC., ROUND	3.000	EA
0390	619(A)6200 REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0400	619(B)6352 REMOVAL OF FENCE	1,044.000	LF
0410	619(B)6360 REMOVAL OF CONCRETE PAVEMENT	3,683.000	SY
0420	619(B)6364 REMOVAL OF ASPHALT PAVEMENT	4,127.000	SY
0430	619(B)6396 REMOVAL OF GUARDRAIL	1,929.000	LF
0440	619(C)6600 SAWING PAVEMENT	2,595.000	LF
0450	624(A)3200 FENCE-STYLE WWF	436.000	LF

Proposal:260305**Let Date:**November 19, 2026**Call Order:**048**J/P Num:**38910(04)**Proj. Num:**MU-MC-56**Counties:**WAGONER**Description:**BRIDGE REHABILITATION

OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770):

OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 I

NTERCHANGE NEAR MUSKOGEE.

PROJECT LENGTH = 1.657 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0460	627(A)6200 CONCRETE LONGITUDINAL BARRIER, DESIGN 1	537.000	LF
0002	BRIDGE		
0470	501(B)1300 SUBSTRUCTURE EXCAVATION COMMON	80.000	CY
0480	501(G)1800 CLSM BACKFILL	134.000	CY
0490	504(A)5200 APPROACH SLAB	187.400	SY
0500	504(B)5300 SAW-CUT GROOVING	1,522.400	SY
0510	504(D)5420 CONCRETE RAIL (TR4)	681.000	LF
0520	506(A)7200 STRUCTURAL STEEL	317,980.000	LB
0530	507(A)8210 WEATHERING STEEL FIXED BEARING ASSEMBLY	8.000	EA
0540	507(B)8300 STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0550	507(C)8400 ELASTOMERIC BEARING PADS	24.000	EA
0560	509(A)0210 CLASS AA CONCRETE	349.000	CY
0570	509(B)0320 CLASS A CONCRETE	261.200	CY
0580	509(D)0510 CLASS C CONCRETE	10.000	CY
0590	510(C)1450 SLOPE WALL (5")	548.000	SY
0600	511(B)2310 EPOXY COATED REINFORCING STEEL	129,270.000	LB
0610	514(A)5210 PILES, FURNISHED (HP 10X42)	364.000	LF
0620	514(B)5310 PILES, DRIVEN (HP 10X42)	364.000	LF
0630	514(K)6200 (PL)PILOT HOLES	210.000	LF
0640	514(L)6300 PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0650	515(A)7200 WATER REPELLENT (VISUALLY INSPECTED)	878.000	SY
0660	516(A)8250 DRILLED SHAFTS 72" DIAMETER	207.000	LF
0670	516(C)8400 CROSSHOLE SONIC LOGGING	2.000	EA
0680	523(A)3200 SEALER CRACK PREPARATION	244.500	LF
0690	523(B)3300 SEALER RESIN	2.700	GAL
0700	613(H)6205 6" PERFORATED PIPE UNDERDRAIN ROUND	182.000	LF
0710	613(I)6310 6" NON-PERF.PIPE UNDERDRAIN RND.	100.000	LF
0720	613(Q)7500 OUTLET LATERAL HEADWALL	2.000	EA
0730	619(D)6700 REMOVAL OF EXISTING BRIDGE STRUCTURE	1.000	LSUM

Proposal:260305

Let Date:November 19, 2026

Call Order:048

J/P Num:38910(04)

Proj. Num:MU-MC-56

Counties:WAGONER

Description:BRIDGE REHABILITATION

OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770):
OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 I
NTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003	TRAFFIC SIGNING AND STRIPING		
0740 804(A)2200	STRUCTURAL CONCRETE	13.200	CY
0750 804(B)2300	REINFORCING STEEL	2,668.000	LB
0760 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	16.000	EA
0770 850(A)1200	SHEET ALUMINUM SIGNS	418.000	SF
0780 850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	270.000	SF
0790 851(A)2205	6"@15 GALV.STL.WD.FLANGE BM.POST	37.000	LF
0800 851(A)2235	10"@45 GALV.STL.WD.FLANGE BM.POST	126.000	LF
0810 851(B)2310	2 1/2"@5.79 GALV.STL.PIPE POST	135.000	LF
0820 851(B)2320	3 1/2"@9.11 GALV.STL.PIPE POST	180.000	LF
0830 851(C)2420	2 1/4" SQUARE TUBE POST	126.000	LF
0840 851(C)2430	2 1/2" SQUARE TUBE POST	120.000	LF
0850 853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	38.000	EA
0860 853 5135	DELINEATORS(TYPE 1, CODE 2, FLEXIBLE)	18.000	EA
0870 853 5155	DELINEATORS(TYPE 2, CODE 3, FLEXIBLE)	8.000	EA
0880 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	33,338.000	LF
0890 856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	957.000	LF
0900 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	113.000	LF
0910 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	5.000	EA
0920 858(A)0224	PAVE.MARKERS CLASS A TYPE 2-C	60.000	EA
0930 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	49.000	EA
0940 871(A)2200	IMPACT ATTENUATOR	6.000	EA
0004	TRAFFIC CONTROL		
0950 857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	32,350.000	LF
0960 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	40,438.000	LF
0970 871(B)2300	CONST.ZONE IMPACT ATTEN.	420.000	SD
0980 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	4,125.000	LF
0990 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	3,070.000	LF
1000 880(A)6220	ARROW DISPLAY(TYPE C)	840.000	SD
1010 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	28,170.000	SD
1020 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	12,900.000	SD
1030 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	6,690.000	SD
1040 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	5,700.000	SD
1050 880(E)6607	WARNING LIGHTS(TYPE B)	16,200.000	SD
1060 880(F)6700	DRUMS	16,740.000	SD
1070 880(G)6805	CHANNELIZER CONES	23,010.000	SD
1080 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,200.000	HOURL
1090 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	600.000	SD

Proposal:260305

Let Date:November 19, 2026

Call Order:048

J/P Num:38910(04)

Proj. Num:MU-MC-56

Counties:WAGONER

Description:BRIDGE REHABILITATION

OTA ACCESS MUSKOGEE TURNPIKE (SH-351)/ COUNTY ROAD (E0770):
OVER MUSKOGEE TURNPIKE, 7.27 MILES NORTHWEST OF THE US-69 I
NTERCHANGE NEAR MUSKOGEE.
PROJECT LENGTH = 1.657 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0005 TOLLING			
1100 506(A)7200	STRUCTURAL STEEL	1,300.000	LB
1110 516(A)8230	DRILLED SHAFTS 48" DIAMETER	71.000	LF
1120 516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1130 610(A)5200	4" CONCRETE SIDEWALK	112.000	SY
1140 648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
1150 650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
1160 802(B)0308	1" PVC SCH.40 PLASTIC CONDUIT TRENCHED	185.000	LF
1170 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	75.000	LF
1180 802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	335.000	LF
1190 802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	905.000	LF
1200 803(A)1220	PULL BOX(SIZE II)	12.000	EA
1210 804(A)2200	STRUCTURAL CONCRETE	1.460	CY
1220 811 9165	3/C NO.3 ELECT.COND.	1,240.000	LF
1230 824(C)7400	(SP)CABINET	2.000	EA
1240 852(B)3340	GALVANIZED STEEL OVERHEAD TOLL GANTRY (CANTILEVER	2.000	EA
0006 STAKING			
1250 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007 CONSTRUCTION			
1260 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1270 641 2110	MOBILIZATION	1.000	LSUM