

Proposal:260308

Let Date:November 19, 2026

Call Order:415

J/P Num:38021(04)

Proj. Num:TAP-216C(134)TP

Counties:COMANCHE

Description:PEDESTRIAN IMPROVEMENTS (SIDEWALK AND TRAIL)

CITY STREET (EAST GORE BOULEVARD): FROM 1.3 MILES

EAST OF THE I-44 JUNCTION, EXTEND EAST IN THE CITY OF LAWTON.

PROJECT LENGTH = 1.832 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	4,263.000	CY
0030 202(D)2500	UNCLASSIFIED BORROW	250.000	CY
0040 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050 221(B)2300	TEMPORARY SILT FENCE	10,751.000	LF
0060 221(C)2400	TEMPORARY SEDIMENT FILTER	15.000	EA
0070 221(E)2600	TEMPORARY SILT DIKE	896.000	LF
0080 229 6100	DITCH LINER PROTECTION	50.000	LF
0090 230(A)7200	SOLID SLAB SODDING	9,947.000	SY
0100 233(A)0200	VEGETATIVE MULCHING	3.000	AC
0110 303(A)1200	AGGREGATE BASE TYPE A	212.000	CY
0120 402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	382.000	TON
0130 414(A)5200	P.C.CONCRETE PAVEMENT(PLACEMENT)	1,751.000	SY
0140 414(G)5800	P.C. CONCRETE FOR PAVEMENT	390.000	CY
0150 504(F)5600	HANDRAILING	547.000	LF
0160 509(A)0200	CLASS AA CONCRETE	37.000	CY
0170 509(B)0300	CLASS A CONCRETE	8.000	CY
0180 509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	7.000	CY
0190 509(D)0500	CLASS C CONCRETE	20.000	CY
0200 511(A)2200	REINFORCING STEEL	3,137.000	LB
0210 609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	2,241.000	LF
0220 609(C)4410	CONCRETE HEADER CURB (8"X 18")	1,887.000	LF
0230 610(A)5200	4" CONCRETE SIDEWALK	8,119.000	SY
0240 610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	1,556.000	SY
0250 610(C)5420	8" CONCRETE DIVIDING STRIP	8.000	SY
0260 610(I)6000	TACTILE WARNING DEVICE-NEW	376.000	SF
0270 611(A)7210	MANHOLE (4' DIA.)	2.000	EA
0280 611(G)7754	INLET CI DES. 2 (STD)	2.000	EA
0290 611(P)2000	REPLACEMENT COVER/GRATE	3.000	EA
0300 612(A)3200	MANHOLES ADJUST TO GRADE	11.000	EA
0310 612(E)3600	VALVE BOXES ADJUST TO GRADE	1.000	EA
0320 613(A)5208	18" R.C.PIPES CLASS III	42.000	LF
0330 613(A)5220	30" R.C.PIPES CLASS III	28.000	LF
0340 613(A)5228	42" R.C.PIPES CLASS III	32.000	LF
0350 613(B)5604	21" X 15" CORR. GALV. STEEL PIPE ARCH	132.000	LF
0360 613(P)7450	21" X 15" GALV. STEEL CULV. END SEC.ARCH	8.000	EA
0370 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0380 619(B)6356	REMOVAL OF CURB AND GUTTER	584.000	LF
0390 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	801.000	SY
0400 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,186.000	SY
0410 619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	1,451.000	SY
0420 619(B)6404	REMOVAL OF SIDEWALK	464.000	SY
0430 619(B)6440	REMOVAL OF EXISTING PIPE	67.000	LF

Proposal:260308**Let Date:**November 19, 2026**Call Order:**415**J/P Num:**38021(04)**Proj. Num:**TAP-216C(134)TP**Counties:**COMANCHE**Description:**PEDESTRIAN IMPROVEMENTS (SIDEWALK AND TRAIL)

CITY STREET (EAST GORE BOULEVARD): FROM 1.3 MILES

EAST OF THE I-44 JUNCTION, EXTEND EAST IN THE CITY OF LAWTON.

PROJECT LENGTH = 1.832 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002 TRAFFIC			
0440 643 4100	WIRELESS SOLAR LIGHTING	2.000	EA
0450 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
0460 804(A)2200	STRUCTURAL CONCRETE	4.000	CY
0470 804(B)2300	REINFORCING STEEL	348.000	LB
0480 805(B)3300	(PL)RESET OF PULL BOX	11.000	EA
0490 805(D)3504	(PL)REMOVE & RESET LIGHT POLE	1.000	EA
0500 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	18.000	EA
0510 806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	8.000	EA
0520 830 2100	PEDESTRIAN PUSH BUTTON	11.000	EA
0530 831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	9.000	EA
0540 834(A)6200	2/C TRAFFIC SIGNAL ELECTRICAL CABLE	145.000	LF
0550 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	190.000	LF
0560 850(A)1200	SHEET ALUMINUM SIGNS	230.000	SF
0570 851(C)2415	2" SQUARE TUBE POST	270.000	LF
0580 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	1,676.000	LF
0590 856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	35.000	EA
0600 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	1,173.000	LF
0003 TRAFFIC CONTROL			
0610 880(A)6200	ARROW DISPLAY(TYPE A)	360.000	SD
0620 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,080.000	SD
0630 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	540.000	SD
0640 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	960.000	SD
0650 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	540.000	SD
0660 880(E)6600	WARNING LIGHTS(TYPE A)	1,800.000	SD
0670 880(G)6805	CHANNELIZER CONES	5,580.000	SD
0680 880(I)7000	FLAGGER	360.000	SD
0004 STAKING			
0690 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005 CONSTRUCTION			
0700 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0710 641 2110	MOBILIZATION	1.000	LSUM