

Proposal:260309
J/P Num:36364(04)
Counties:HUGHES

Let Date:November 19, 2026
Proj. Num:SBR-232B(079)SB

Call Order:420

Description:BRIDGE REHABILITATION

US-75: OVER CANADIAN RIVER AND COUNTY ROAD
(E -141), 0.75 MILES NORTH OF THE US-270 JUNCTION NEAR CALVIN.
PROJECT LENGTH = 0.256 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0010 221(B)2300	TEMPORARY SILT FENCE	100.000	LF
0020 230(A)7200	SOLID SLAB SODDING	1,000.000	SY
0030 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0040 623(I)2040	GUARDRAIL BRIDGE CONN (D-BF RETROFIT)	4.000	EA
0002 BRIDGE			
0050 504(E)5500	CONCRETE PARAPET	120.000	LF
0060 509 0100	SPECIAL CONCRETE FINISH	1,810.000	SY
0070 509(A)0210	CLASS AA CONCRETE	11.200	CY
0080 509(D)0510	CLASS C CONCRETE	10.000	CY
0090 511(B)2310	EPOXY COATED REINFORCING STEEL	1,320.000	LB
0100 512 3100	CLEANING BRIDGE SURFACES	100.000	SY
0110 512(A)3200	PAINTING EXISTING STRUCTURES	1.000	LSUM
0120 517 9110	ELASTOMERIC COATING	5,600.000	SF
0130 518(B)0300	SEALED EXPANSION JOINTS	208.000	LF
0140 520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	800.000	LF
0150 520(C)1400	EPOXY RESIN, ABOVE WATER	12.000	GAL
0160 521(A)2200	PNEUMATICALLY PLACED MORTAR	40.000	SY
0170 523(C)3400	DECK AREA SEALED (FLOODCOATS)	6,907.000	SY
0180 524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	150.000	SF
0190 535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	60.000	SY
0200 540 8104	(PL)REPAIR BRIDGE ITEMS	13.000	EA
0210 601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	590.000	TON
0220 619(B)6312	REMOVAL OF BRIDGE ITEM (TYPE A)	1.000	LSUM
0230 619(B)6320	REMOVAL OF BRIDGE ITEM (TYPE B)	1.000	LSUM
0240 619(B)6328	REMOVAL OF BRIDGE ITEM (TYPE C)	1.000	LSUM
0003 TRAFFIC STRIPING			
0250 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	15,656.000	LF
0004 TRAFFIC CONTROL			
0260 823 6100	(SP)PORTABLE TRAFFIC SIGNAL SYSTEM	125.000	SD
0270 857(A)9205	CONSTRUCTION TRAFFIC STR.(PAINT)(6" WIDE)	10,347.000	LF
0280 857(F)9740	PAVEMENT MARKING REMOVAL (HYDROBLASTING)	22,459.000	LF
0290 858(A)0216	PAVE.MARKERS CLASS A TYPE 2-A	2,500.000	EA
0300 858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	910.000	EA
0310 876(A)3210	(PL)TRUCK MOUNTED ATTENUATOR	500.000	SD
0320 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,253.000	SD
0330 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	1,099.000	SD
0340 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	2,125.000	SD
0350 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,141.000	SD
0360 880(E)6607	WARNING LIGHTS(TYPE B)	6,907.000	SD
0370 880(E)6616	WARNING LIGHTS(TYPE D)	1,950.000	SD
0380 880(F)6700	DRUMS	2,500.000	SD
0390 880(G)6800	TUBE CHANNELIZERS	5,980.000	SD
0400 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	278.000	SD

Proposal:260309
J/P Num:36364(04)
Counties:HUGHES

Let Date:November 19, 2026
Proj. Num:SBR-232B(079)SB

Call Order:420

Description:BRIDGE REHABILITATION
US-75: OVER CANADIAN RIVER AND COUNTY ROAD
(E -141), 0.75 MILES NORTH OF THE US-270 JUNCTION NEAR CALVIN.
PROJECT LENGTH = 0.256 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0005 CONSTRUCTION			
0410 641 2100	MOBILIZATION	1.000	LSUM