

Proposal:260310
J/P Num:35881(04)
Counties:KAY

Let Date:November 19, 2026
Proj. Num:ERSTP-236N(153)ER

Call Order:425

Description:EMERGENCY RELIEF

SH-11: OVER CHICKASKIA RIVER, 0.28 MILES EAST
OF THE US-177 INTERSECTION NEAR BLACKWELL.
PROJECT LENGTH = 0.00 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	BRIDGE 'A' - NBI 17951		
0010	201(A)1200 CLEARING AND GRUBBING	1.000	LSUM
0020	202(D)2520 UNCLASSIFIED BORROW (TOPSOIL)	950.000	CY
0030	202(H)2900 EARTHWORK	1.000	LSUM
0040	221(B)2300 TEMPORARY SILT FENCE	1,250.000	LF
0050	221(E)2600 TEMPORARY SILT DIKE	250.000	LF
0060	230(A)7200 SOLID SLAB SODDING	545.000	SY
0070	601(B)1210 TYPE I PLAIN RIPRAP WITH FILTER BLANKET	10,930.000	TON
0002	TRAFFIC CONTROL		
0080	871(B)2300 CONST.ZONE IMPACT ATTEN.	70.000	SD
0090	877(B)4300 DELIVER PORTABLE LONGITUDINAL BARRIER	760.000	LF
0100	880(B)6300 CONSTRUCTION SIGNS 0 TO 6.25 SF	660.000	SD
0110	880(B)6310 CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	465.000	SD
0120	880(B)6320 CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	860.000	SD
0130	880(C)6410 CONSTRUCTION BARRICADES(TYPE III)	265.000	SD
0140	880(E)6600 WARNING LIGHTS(TYPE A)	530.000	SD
0150	880(E)6607 WARNING LIGHTS(TYPE B)	795.000	SD
0160	880(E)6616 WARNING LIGHTS(TYPE D)	2,380.000	SD
0170	880(F)6700 DRUMS	2,380.000	SD
0180	880(I)7000 FLAGGER	70.000	SD
0190	882(A)8210 PORT.CHANGEABLE MESSAGE SIGN	163.000	SD
0003	TRAFFIC BARRIER		
0200	619(B)6396 REMOVAL OF GUARDRAIL	760.000	LF
0210	623(A)1200 BEAM GUARDRAIL W-BEAM SINGLE	723.000	LF
0220	623(I)2050 GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	2.000	EA
0230	853 5175 GUARDRAIL DELINEATORS(TYPE 2, CODE 1)	31.000	EA
0004	STAKING		
0240	642(B)3300 CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0005	CONSTRUCTION		
0250	220 1100 SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0260	641 2100 MOBILIZATION	1.000	LSUM