

Proposal:260313**Let Date:**November 19, 2026**Call Order:**440**J/P Num:**38099(04)**Proj. Num:**STPG-255N(765)AG**Counties:**OKLAHOMA**Description:**INTERSECTION MODIFICATION

CITY STREET (SW 29TH STREET): AT NEWCASTLE RD,
SOUTH INDEPENDENCE AVE, I-44 E/W RAMPS, AND SOUTH MAY AVE,
IN OKLAHOMA CITY.
PROJECT LENGTH = 0.107 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 202(A)2200	UNCLASSIFIED EXCAVATION	110.000	CY
0020 202(D)2500	UNCLASSIFIED BORROW	120.000	CY
0030 205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0040 221(B)2300	TEMPORARY SILT FENCE	1,198.000	LF
0050 221(G)2800	TEMPORARY FIBER LOG	85.000	LF
0060 230(A)7200	SOLID SLAB SODDING	458.000	SY
0070 303(A)1200	AGGREGATE BASE TYPE A	36.000	CY
0080 411(B)1340	SUPERPAVE, TYPE S3(PG 58-28 OK)	20.000	TON
0090 411(D)1530	SUPERPAVE, TYPE S5(PG 64-22 OK)	4.000	TON
0100 504(F)5600	HANDRAILING	117.000	LF
0110 509(B)0320	CLASS A CONCRETE	14.000	CY
0120 609(B)4360	2'-8" COMB.CRB.& GUT.(6" BARRIER)	250.000	LF
0130 610(A)5200	4" CONCRETE SIDEWALK	342.000	SY
0140 610(I)6000	TACTILE WARNING DEVICE-NEW	231.000	SF
0150 612(A)3200	MANHOLES ADJUST TO GRADE	1.000	EA
0160 612(F)3700	METER BOXES ADJUST TO GRADE	2.000	EA
0170 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0180 619(B)6356	REMOVAL OF CURB AND GUTTER	362.000	LF
0190 619(B)6396	REMOVAL OF GUARDRAIL	28.000	LF
0200 619(B)6404	REMOVAL OF SIDEWALK	139.000	SY
0210 619(C)6600	SAWING PAVEMENT	663.000	LF
0220 631(A)9200	(SP)STATIONARY BOLLARD	1.000	EA
0002	TRAFFIC SIGNAL		
0230 802(B)0328	3" PVC SCH.40 PLASTIC CONDUIT BORED	1,676.000	LF
0240 803(A)1210	PULL BOX(SIZE I)	18.000	EA
0250 804(A)2200	STRUCTURAL CONCRETE	10.000	CY
0260 804(B)2300	REINFORCING STEEL	825.000	LB
0270 805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0280 806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	19.000	EA
0290 815(A)2200	(SP)CCTV CAMERA, WEB	3.000	EA
0300 825(A)8200	SIGNAL SYSTEM CONTROLLER UPGRADE	4.000	EA
0310 828 0110	(PL)DETECTION SYSTEM (RADAR)	1.000	LSUM
0320 830 2100	PEDESTRIAN PUSH BUTTON	20.000	EA
0330 831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	20.000	EA
0340 831 3144	1WAY4SEC.ADJ.SIG.HD.S-13	4.000	EA
0350 833 5100	BACKPLATE	32.000	EA
0360 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,347.000	LF
0370 834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	506.000	LF
0380 834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	1,247.000	LF
0390 850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	120.000	SF

Proposal:260313**Let Date:**November 19, 2026**Call Order:**440**J/P Num:**38099(04)**Proj. Num:**STPG-255N(765)AG**Counties:**OKLAHOMA**Description:**INTERSECTION MODIFICATIONCITY STREET (SW 29TH STREET): AT NEWCASTLE RD,
SOUTH INDEPENDENCE AVE, I-44 E/W RAMPS, AND SOUTH MAY AVE,
IN OKLAHOMA CITY.

PROJECT LENGTH = 0.107 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0003 TRAFFIC SIGNING AND STRIPING			
0400 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	2.000	EA
0410 805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	8.000	EA
0420 850(A)1200	SHEET ALUMINUM SIGNS	45.000	SF
0430 851(C)2430	2 1/2" SQUARE TUBE POST	80.000	LF
0440 856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	967.000	LF
0450 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	499.000	LF
0460 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	18.000	EA
0470 856(B)8311	(SP) TRAFFIC STRIPE(PLURAL-COMP)(SYMBOLS)	12.000	EA
0480 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAFFIC STRIPES)	1,000.000	LF
0490 857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	14.000	EA
0004 TRAFFIC CONTROL			
0500 104 3250	(SP) RAILROAD FLAGGING(NON-BIDDABLE)	30.000	DAY
0510 857(C)9420	REMOVABLE PAVEMENT MARKING TAPE(ARROWS)	11.000	EA
0520 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,260.000	SD
0530 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	2,220.000	SD
0540 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,480.000	SD
0550 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	2,010.000	SD
0560 880(E)6607	WARNING LIGHTS(TYPE B)	11,460.000	SD
0570 880(F)6700	DRUMS	3,420.000	SD
0580 880(G)6800	TUBE CHANNELIZERS	2,100.000	SD
0590 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	536.000	SD
0005 STAKING			
0600 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006 CONSTRUCTION			
0610 641 2110	MOBILIZATION	1.000	LSUM