

Proposal:260315
J/P Num:31078(04)
Counties:TULSA

Let Date:November 19, 2026
Proj. Num:NHPPI-2440(057)PM

Call Order:450

Description:BRIDGE REHABILITATION

CITY STREETS (LEWIS AVENUE/UTICA AVENUE): OVER I-244, EAST OF THE US-75
INTERCHANGE IN THE CITY OF TULSA.
PROJECT LENGTH = 0.099 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY ITEMS		
0010	201(A)1200 CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200 UNCLASSIFIED EXCAVATION	200.000	CY
0030	221(B)2300 TEMPORARY SILT FENCE	300.000	LF
0040	230(A)7200 SOLID SLAB SODDING	67.000	SY
0050	303(A)1200 AGGREGATE BASE TYPE A	124.000	CY
0060	307(K)4200 STABILIZED SUBGRADE	362.000	SY
0070	411(C)1420 SUPERPAVE, TYPE S4(PG 70-28 OK)	31.000	TON
0080	412 3100 COLD MILLING PAVEMENT	278.000	SY
0090	414(B)5300 DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	334.000	SY
0100	414(E)5600 FULL DEPTH P.C.C. PATCH (PLACEMENT)	32.000	SY
0110	414(G)5800 P.C. CONCRETE FOR PAVEMENT	74.000	CY
0120	609(A)4230 CONC.CURB(6" BARRIER-INTEGRAL)	72.000	LF
0130	609(B)4360 2'-8" COMB.CRB.& GUT.(6" BARRIER)	82.000	LF
0140	610(A)5200 4" CONCRETE SIDEWALK	36.000	SY
0150	610(C)5410 6" CONCRETE DIVIDING STRIP	12.000	SY
0160	619(B)6352 REMOVAL OF FENCE	20.000	LF
0170	619(B)6360 REMOVAL OF CONCRETE PAVEMENT	302.000	SY
0180	619(B)6396 REMOVAL OF GUARDRAIL	40.000	LF
0190	619(B)6400 REMOVAL OF CURB	154.000	LF
0200	619(B)6404 REMOVAL OF SIDEWALK	36.000	SY
0210	619(C)6600 SAWING PAVEMENT	292.000	LF
0220	623(A)1200 BEAM GUARDRAIL W-BEAM SINGLE	80.000	LF
0230	624(E)3600 FENCE-STYLE CLF (4'HIGH, CLASS A)	20.000	LF

Proposal:260315
J/P Num:31078(04)
Counties:TULSA

Let Date:November 19, 2026
Proj. Num:NHPPI-2440(057)PM

Call Order:450

Description:BRIDGE REHABILITATION

CITY STREETS (LEWIS AVENUE/UTICA AVENUE): OVER I-244, EAST OF THE US-75
 INTERCHANGE IN THE CITY OF TULSA.
 PROJECT LENGTH = 0.099 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	BRIDGE "A" - NBI NO. 17240		
0240	501(G)1800 CLSM BACKFILL	155.300	CY
0250	504(A)5200 APPROACH SLAB	246.600	SY
0260	504(B)5300 SAW-CUT GROOVING	1,042.900	SY
0270	504(E)5500 CONCRETE PARAPET	340.100	LF
0280	506(A)7200 STRUCTURAL STEEL	216,120.000	LB
0290	507(A)8200 STAINLESS STEEL FIXED BEARING ASSEMBLY	8.000	EA
0300	507(B)8300 STAINLESS STEEL EXP. BEARING ASSEMBLY	16.000	EA
0310	509(A)0210 CLASS AA CONCRETE	277.800	CY
0320	511 2100 MECHANICAL SPLICES	512.000	EA
0330	511(B)2310 EPOXY COATED REINFORCING STEEL	69,910.000	LB
0340	515(A)7200 WATER REPELLENT (VISUALLY INSPECTED)	505.100	SY
0350	517 9110 ELASTOMERIC COATING	790.000	SF
0360	518(B)0300 SEALED EXPANSION JOINTS	125.580	LF
0370	518(C)0400 RAPID CURE JOINT SEALANT	62.800	LF
0380	520(A)1200 PREPARATION OF CRACKS, ABOVE WATER	15.800	LF
0390	520(C)1400 EPOXY RESIN, ABOVE WATER	1.400	GAL
0400	521(A)2200 PNEUMATICALLY PLACED MORTAR	5.600	SY
0410	523(A)3200 SEALER CRACK PREPARATION	423.600	LF
0420	523(B)3300 SEALER RESIN	34.000	GAL
0430	535 7100 CORROSION INHIBITOR(SURFACE APPLIED)	7.200	SY
0440	619(B)6304 REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0450	624(E)3640 FENCE-STYLE CLF (8'HIGH, CLASS A)	318.000	LF
0003	BRIDGE "B" - NBI NO. 17310		
0460	501(G)1800 CLSM BACKFILL	253.600	CY
0470	504(A)5200 APPROACH SLAB	400.000	SY
0480	504(B)5300 SAW-CUT GROOVING	1,813.400	SY
0490	504(E)5500 CONCRETE PARAPET	441.000	LF
0500	506(A)7200 STRUCTURAL STEEL	434,900.000	LB
0510	507(A)8200 STAINLESS STEEL FIXED BEARING ASSEMBLY	12.000	EA
0520	507(B)8300 STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0530	509(A)0210 CLASS AA CONCRETE	486.200	CY
0540	511(B)2310 EPOXY COATED REINFORCING STEEL	117,500.000	LB
0550	515(A)7200 WATER REPELLENT (VISUALLY INSPECTED)	626.000	SY
0560	517 9110 ELASTOMERIC COATING	1,249.000	SF
0570	518(B)0300 SEALED EXPANSION JOINTS	364.140	LF
0580	518(C)0400 RAPID CURE JOINT SEALANT	91.200	LF
0590	520(A)1200 PREPARATION OF CRACKS, ABOVE WATER	15.800	LF
0600	520(C)1400 EPOXY RESIN, ABOVE WATER	0.500	GAL
0610	521(A)2200 PNEUMATICALLY PLACED MORTAR	5.500	SY
0620	523(A)3200 SEALER CRACK PREPARATION	364.140	LF
0630	523(B)3300 SEALER RESIN	29.200	GAL
0640	535 7100 CORROSION INHIBITOR(SURFACE APPLIED)	6.950	SY
0650	619(B)6304 REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0660	624(E)3640 FENCE-STYLE CLF (8'HIGH, CLASS A)	441.000	LF

Proposal:260315
J/P Num:31078(04)
Counties:TULSA

Let Date:November 19, 2026
Proj. Num:NHPPI-2440(057)PM

Call Order:450

Description:BRIDGE REHABILITATION

CITY STREETS (LEWIS AVENUE/UTICA AVENUE): OVER I-244, EAST OF THE US-75
 INTERCHANGE IN THE CITY OF TULSA.
 PROJECT LENGTH = 0.099 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004 TRAFFIC CONTROL			
0670 857(C)9400	REMOVABLE PAVEMENT MARKING TAPE(4" WIDE)	23,730.000	LF
0680 871(B)2300	CONST.ZONE IMPACT ATTEN.	600.000	SD
0690 877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	673.000	LF
0700 877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	673.000	LF
0710 880(A)6220	ARROW DISPLAY(TYPE C)	2,404.000	SD
0720 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	24,734.000	SD
0730 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	12,450.000	SD
0740 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	13,332.000	SD
0750 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	4,548.000	SD
0760 880(E)6600	WARNING LIGHTS(TYPE A)	15,132.000	SD
0770 880(F)6700	DRUMS	68,374.000	SD
0780 880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	700.000	HOURL
0790 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	1,240.000	SD
0005 TRAFFIC SIGNING AND STRIPING			
0800 850(A)1200	SHEET ALUMINUM SIGNS	8.000	SF
0810 851(C)2430	2 1/2" SQUARE TUBE POST	20.000	LF
0820 852(G)3800	GALV. STL.OVERHEAD SIGN STR.-BR. MOUNTED	2.000	EA
0830 856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	5,203.000	LF
0840 856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	186.000	LF
0850 856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	6.000	EA
0006 STAKING			
0860 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0007 CONSTRUCTION			
0870 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0880 641 2100	MOBILIZATION	1.000	LSUM