Proposal: 260317 **Let Date:** December 17, 2026 **Call Order:** 060
J/P Num: 37300(13) **Proj. Num:** JKT-30601A
Counties: CANADIAN
Description: GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020	202(A)2200	UNCLASSIFIED EXCAVATION	6,066.000	CY
0030	202(D)2500	UNCLASSIFIED BORROW	12,017.000	CY
0040	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0050	221(B)2300	TEMPORARY SILT FENCE	3,121.000	LF
0060	221(E)2600	TEMPORARY SILT DIKE	273.000	LF
0070	221(F)2720	TEMPORARY ROCK FILTER DAM TYPE 3	44.000	CY
0080	221(M)3400	TEMPORARY ENVIRONMENTAL FENCE	263.000	LF
0090	230(A)7200	SOLID SLAB SODDING	22,670.000	SY
0100	233(E)0600	(SP) HYDROMULCH	22,670.000	SY
0110	241 3100	MOWING	9.400	AC
0120	242 4101	STABILIZED CONSTRUCTION EXIT	2.000	EA
0130	307(K)4200	STABILIZED SUBGRADE	26,496.000	SY
0140	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	81.000	TON
0150	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	61.000	TON
0160	414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	11,152.000	SY
0170	414(G)5800	P.C. CONCRETE FOR PAVEMENT	2,942.000	CY
0180	501(A)1200	STRUCTURAL EXCAVATION UNCLASSIFIED	20.000	CY
0190	509(A)0200	CLASS AA CONCRETE	874.000	CY
0200	509(D)0500	CLASS C CONCRETE	57.000	CY
0210	511(A)2200	REINFORCING STEEL	141,038.000	LB
0220	601(B)1200	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	56.000	TON
0230	602(C)2410	FILTER FABRIC	55.000	SY
0240	609(A)4270	CONC.CURB(8" BARRIER-INTEGRAL)	2,261.000	LF
0250	610(C)5400	4" CONCRETE DIVIDING STRIP	243.000	SY
0260	611(G)7754	INLET CI DES. 2 (STD)	5.000	EA
0270	611(G)7758	INLET CI DES. 2 (B)	2.000	EA
0280	611(G)7766	INLET CI DES. 2 (D)	3.000	EA
0290	611(G)7778	INLET CI DES. 2 (2C)	1.000	EA
0300	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0310	613(A)5208	18" R.C.PIPE CLASS III	773.000	LF
0320	613(A)5216	24" R.C.PIPE CLASS III	46.000	LF
0330	613(M)6960	TYPE A4 CULVERT END TREATMENT	6.000	EA
0340	613(M)7008	TYPE B6 CULVERT END TREATMENT	2.000	EA
0350	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0360	619(B)6356	REMOVAL OF CURB AND GUTTER	223.000	LF
0370	619(B)6360	REMOVAL OF CONCRETE PAVEMENT	2,134.000	SY
0380	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	101.000	SY
0390	619(B)6396	REMOVAL OF GUARDRAIL	254.000	LF
0400	619(C)6600	SAWING PAVEMENT	2,133.000	LF
0410	627(A)6200	CONCRETE LONGITUDINAL BARRIER, DESIGN 1	276.000	LF

Proposal:260317 **Let Date:**December 17, 2026 **Call Order:**060
J/P Num:37300(13) **Proj. Num:**JKT-30601A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0002	BRIDGE "C"			
0420	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	210.000	CY
0430	501(G)1800	CLSM BACKFILL	145.000	CY
0440	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,933.330	LF
0450	504(A)5200	APPROACH SLAB	186.800	SY
0460	504(B)5300	SAW-CUT GROOVING	1,561.130	SY
0470	504(E)5520	42" F-SHAPED PARAPET	1,123.000	LF
0480	506(A)7200	STRUCTURAL STEEL	1,530.000	LB
0490	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	16.000	EA
0500	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0510	509(A)0210	CLASS AA CONCRETE	381.400	CY
0520	509(B)0320	CLASS A CONCRETE	171.700	CY
0530	509(D)0510	CLASS C CONCRETE	7.900	CY
0540	511(B)2310	EPOXY COATED REINFORCING STEEL	126,520.000	LB
0550	514(A)5210	PILES, FURNISHED (HP 10X42)	140.000	LF
0560	514(A)5220	PILES, FURNISHED (HP 12X53)	470.000	LF
0570	514(B)5310	PILES, DRIVEN (HP 10X42)	140.000	LF
0580	514(B)5320	PILES, DRIVEN (HP 12X53)	470.000	LF
0590	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0600	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	3,531.200	SY
0610	516(A)8230	DRILLED SHAFTS 48" DIAMETER	200.000	LF
0620	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0630	517 9110	ELASTOMERIC COATING	1,250.000	SF
0640	518(B)0310	EXPANSION JOINT SYSTEM	51.930	LF
0650	523(A)3200	SEALER CRACK PREPARATION	52.000	LF
0660	523(B)3300	SEALER RESIN	1.000	GAL
0670	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	2,602.000	TON
0680	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	56.000	LF
0690	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF

Proposal:260317 **Let Date:**December 17, 2026 **Call Order:**060
J/P Num:37300(13) **Proj. Num:**JKT-30601A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0003	BRIDGE "D"			
0700	501(B)1300	SUBSTRUCTURE EXCAVATION COMMON	230.000	CY
0710	501(G)1800	CLSM BACKFILL	145.000	CY
0720	503(A)4240	PRESTRESSED CONCRETE BEAMS (TYPE IV)	1,793.330	LF
0730	504(A)5200	APPROACH SLAB	186.800	SY
0740	504(B)5300	SAW-CUT GROOVING	1,421.800	SY
0750	504(E)5520	42" F-SHAPED PARAPET	1,023.400	LF
0760	506(A)7200	STRUCTURAL STEEL	1,530.000	LB
0770	507(A)8200	STAINLESS STEEL FIXED BEARING ASSEMBLY	16.000	EA
0780	507(B)8300	STAINLESS STEEL EXP. BEARING ASSEMBLY	24.000	EA
0790	509(A)0210	CLASS AA CONCRETE	345.300	CY
0800	509(B)0320	CLASS A CONCRETE	173.300	CY
0810	511(B)2310	EPOXY COATED REINFORCING STEEL	128,280.000	LB
0820	514(A)5210	PILES, FURNISHED (HP 10X42)	138.000	LF
0830	514(A)5220	PILES, FURNISHED (HP 12X53)	316.000	LF
0840	514(B)5310	PILES, DRIVEN (HP 10X42)	138.000	LF
0850	514(B)5320	PILES, DRIVEN (HP 12X53)	316.000	LF
0860	514(L)6300	PILE SPLICE, H-PILE (NON-BIDDABLE)	1.000	EA
0870	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	3,230.200	SY
0880	516(A)8230	DRILLED SHAFTS 48" DIAMETER	268.000	LF
0890	516(C)8400	CROSSHOLE SONIC LOGGING	4.000	EA
0900	517 9110	ELASTOMERIC COATING	1,264.000	SF
0910	518(B)0310	EXPANSION JOINT SYSTEM	51.930	LF
0920	523(A)3200	SEALER CRACK PREPARATION	52.000	LF
0930	523(B)3300	SEALER RESIN	1.000	GAL
0940	601(B)1210	TYPE I PLAIN RIPRAP WITH FILTER BLANKET	1,510.000	TON
0950	613(H)6205	6" PERFORATED PIPE UNDERDRAIN ROUND	56.000	LF
0960	613(I)6310	6" NON-PERF.PIPE UNDERDRAIN RND.	50.000	LF
0004	BRIDGE RCB EXT.			
0970	202(A)2210	UNCLASSIFIED EXCAVATION	1,876.000	CY
0980	501(A)1210	STRUCTURAL EXCAVATION UNCLASSIFIED	212.000	CY
0990	508 9100	REMOVAL OF CULVERT END	2.000	EA
1000	509(A)0210	CLASS AA CONCRETE	446.000	CY
1010	511(A)2210	REINFORCING STEEL	69,820.000	LB

Proposal:260317 **Let Date:**December 17, 2026 **Call Order:**060
J/P Num:37300(13) **Proj. Num:**JKT-30601A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC SIGNING AND STRIPING			
1020	506(A)7200	STRUCTURAL STEEL	650.000	LB
1030	516(A)8230	DRILLED SHAFTS 48" DIAMETER	35.000	LF
1040	516(C)8400	CROSSHOLE SONIC LOGGING	1.000	EA
1050	804(A)2200	STRUCTURAL CONCRETE	17.840	CY
1060	804(B)2300	REINFORCING STEEL	5,226.000	LB
1070	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	9.000	EA
1080	850(A)1200	SHEET ALUMINUM SIGNS	321.000	SF
1090	850(B)1310	EXTRUDED ALUMINUM PANEL SIGNS	957.500	SF
1100	850(B)1320	EXTR.ALUM.PAN.SGN.(OVRHD SIGNS)	203.000	SF
1110	851(A)2200	4"@13 GALV.STL.WD.FLANGE BM.POST	78.000	LF
1120	851(A)2220	8"@31 GALV.STL.WD.FLANGE BM.POST	72.500	LF
1130	851(A)2230	8"@40 GALV.STL.WD.FLANGE BM.POST	74.000	LF
1140	851(A)2235	10"@45 GALV.STL.WD.FLANGE BM.POST	84.000	LF
1150	851(C)2430	2 1/2" SQUARE TUBE POST	300.000	LF
1160	852(B)3340	GALVANIZED STEEL OVERHEAD TOLL GANTRY (CANTILEVER	1.000	EA
1170	853 5165	BARRIER DELINEATORS(TYPE 2, CODE 1)	7.000	EA
1180	856(A)8203	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(4" WIDE)	2,985.000	LF
1190	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	10,039.000	LF
1200	856(A)8215	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(12" WIDE)	2,984.000	LF
1210	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	356.000	LF
1220	856(B)8307	(SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS)	24.000	EA
1230	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	4,000.000	LF
1240	857(F)9710	PAVEMENT MARKING REMOVAL(ARROWS)	9.000	EA
0006	TRAFFIC SAFETY			
1250	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	595.000	LF
1260	623(G)1820	GUARDRAIL END TREATMENT (31")	3.000	EA
1270	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	5.000	EA
1280	853 5170	GUARDRAIL DELINEATORS(TYPE 1, CODE 1)	19.000	EA
1290	870(A)1100	SAND FILLED IMPACT ATTEN.MODULE	19.000	EA
1300	871(A)2200	IMPACT ATTENUATOR	2.000	EA

Proposal:260317 **Let Date:**December 17, 2026 **Call Order:**060
J/P Num:37300(13) **Proj. Num:**JKT-30601A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0007	TRAFFIC SIGNAL			
1310	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	50.000	LF
1320	804(A)2200	STRUCTURAL CONCRETE	4.500	CY
1330	804(B)2300	REINFORCING STEEL	670.400	LB
1340	805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
1350	806(A)4252	32'MH POLE 40'TS & 10'LMA(G.STL.)	1.000	EA
1360	809(A)7200	ROADWAY LUMINAIRE	1.000	EA
1370	811 9130	1/C NO.10 ELECT.COND.	1,110.000	LF
1380	815(B)2300	(SP)CCTV CAMERA, PAN-TILT-ZOOM	2.000	EA
1390	828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
1400	831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	1.000	EA
1410	831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	3.000	EA
1420	833 5100	BACKPLATE	4.000	EA
1430	834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	55.000	LF
1440	834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	200.000	LF
1450	834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	525.000	LF
1460	840(B)0300	E.P.S. OPTICAL DETECTOR	1.000	EA
1470	840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	570.000	LF
1480	850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	40.000	SF
0008	TRAFFIC LIGHTING			
1490	802(A)0220	1 1/4" GALV.STEEL ELECT.COND. EXPOSED	1,050.000	LF
1500	802(B)0320	2" PVC SCH.40 PLASTIC CONDUIT BORED	350.000	LF
1510	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	3,645.000	LF
1520	802(E)0620	JUNCTION BOX (12"X12"X8")	10.000	EA
1530	803(A)1210	PULL BOX(SIZE I)	7.000	EA
1540	804(A)2200	STRUCTURAL CONCRETE	44.280	CY
1550	804(B)2300	REINFORCING STEEL	7,668.000	LB
1560	806(D)4616	40' MTG.HT.HL.PTP.(G.STL.)	33.000	EA
1570	809(A)7200	ROADWAY LUMINAIRE	33.000	EA
1580	810(A)8200	SERVICE POLE	1.000	EA
1590	811 9115	1/C NO.4 ELECT.COND.	16,135.000	LF
1600	811 9135	1/C NO.12 ELECT.COND.	2,640.000	LF
0009	TRAFFIC CONTROL			
1610	880(A)6220	ARROW DISPLAY(TYPE C)	350.000	SD
1620	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	3,680.000	SD
1630	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	6,010.000	SD
1640	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,860.000	SD
1650	880(E)6607	WARNING LIGHTS(TYPE B)	3,740.000	SD
1660	880(F)6700	DRUMS	7,490.000	SD
1670	880(G)6805	CHANNELIZER CONES	17,210.000	SD
1680	880(L)7310	(SP) TRAFFIC SURVEILLANCE, OHP (NON-BID)	1,000.000	HOUR
0010	STAKING			
1690	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal:260317 **Let Date:**December 17, 2026 **Call Order:**060
J/P Num:37300(13) **Proj. Num:**JKT-30601A
Counties:CANADIAN
Description:GRADE, DRAIN, BRIDGE AND SURFACE
OTA ACCESS: JOHN KILPATRICK TURNPIKE (I-344):
FROM 0.7 MILES SOUTH OF THE I-40 INTERCHANGE,
EXTEND SOUTH NEAR MUSTANG.
PROJECT LENGTH = 0.884 MILES

Line #		Item Description	Quantity	Unit
0011	CONSTRUCTION			
1700	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1710	641 2110	MOBILIZATION	1.000	LSUM
0012	TOLLING			
1720	506(A)7200	STRUCTURAL STEEL	860.000	LB
1730	516(A)8230	DRILLED SHAFTS 48" DIAMETER	63.000	LF
1740	516(C)8400	CROSSHOLE SONIC LOGGING	2.000	EA
1750	610(A)5200	4" CONCRETE SIDEWALK	70.000	SY
1760	648 6110	ELECTRIC SERVICE AND SERVICE CONNECTION	1.000	LSUM
1770	650(C)8310	ELECTRICAL EQUIPMENT	1.000	LSUM
1780	802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	80.000	LF
1790	802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	1,000.000	LF
1800	803(A)1220	PULL BOX(SIZE II)	4.000	EA
1810	804(A)2200	STRUCTURAL CONCRETE	1.200	CY
1820	811 9165	3/C NO.3 ELECT.COND.	1,000.000	LF
1830	824(C)7400	(SP)CABINET	2.000	EA
1840	852(B)3305	GALV.STEEL OVERHEAD SIGN STRUCTURE (MAST ARM)	56.000	LF
1850	853 5130	DELINEATORS(TYPE 1, CODE 1, FLEXIBLE)	32.000	EA