

Proposal:260319
J/P Num:34731(04)
Counties:TULSA

Let Date:October 15, 2026
Proj. Num:STP-272N(444)IG

Call Order:172

Description:INTERSECTION MODIFICATION
CITY STREETS (SHERIDAN RD): AT THE INTERSECTION OF 71ST ST,
2.38 MILES NORTH OF SH-364 IN THE CITY OF TULSA.
PROJECT LENGTH = 0.468 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	ROADWAY		
0010 201(A)1200	CLEARING AND GRUBBING	1.000	LSUM
0020 202(A)2200	UNCLASSIFIED EXCAVATION	9,350.000	CY
0030 221(C)2400	TEMPORARY SEDIMENT FILTER	54.000	EA
0040 221(G)2800	TEMPORARY FIBER LOG	425.000	LF
0050 230(A)7200	SOLID SLAB SODDING	465.000	SY
0060 303(A)1200	AGGREGATE BASE TYPE A	4,063.000	CY
0070 310(B)5300	SUBGRADE, METHOD B	18,016.000	SY
0080 325 0100	SEPARATOR FABRIC	19,030.000	SY
0090 407(B)7300	TACK COAT	1,346.000	GAL
0100 411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	25.000	TON
0110 411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	17.000	TON
0120 411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	18.000	TON
0130 414(B)5300	DOWEL JOINTED P.C.C.PAVT.(PLACEMENT)	18,016.000	SY
0140 414(E)5600	FULL DEPTH P.C.C. PATCH (PLACEMENT)	53.000	SY
0150 414(G)5800	P.C. CONCRETE FOR PAVEMENT	4,504.000	CY
0160 415 7100	CONCRETE JOINT SEALING	600.000	LF
0170 509(B)0300	CLASS A CONCRETE	521.000	CY
0180 609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	2,720.000	LF
0190 609(B)4310	COMBINED CURB & GUTTER(6" BARRIER)	321.000	LF
0200 610(A)5200	4" CONCRETE SIDEWALK	566.000	SY
0210 610(B)5310	6" CONCRETE DRIVEWAY	407.000	SY
0220 610(I)6000	TACTILE WARNING DEVICE-NEW	188.000	SF
0230 611(G)0544	PRECAST INLET PJB 5' WIDE (DES. 2 B)	1.000	EA
0240 611(G)0552	PRECAST INLET PJB 5' WIDE (DES. 2 D)	2.000	EA
0250 611(G)0576	PRECAST INLET PJB 5' WIDE (DES. 3 B)	1.000	EA
0260 611(G)0580	PRECAST INLET PJB 5' WIDE (DES. 3 D)	1.000	EA
0270 611(G)7758	INLET CI DES. 2 (B)	1.000	EA
0280 611(G)7766	INLET CI DES. 2 (D)	1.000	EA
0290 611(G)7786	INLET CI DES. 3 (STD)	2.000	EA
0300 611(G)7790	INLET CI DES. 3 (B)	3.000	EA
0310 611(G)7794	INLET CI DES. 3 (D)	4.000	EA
0320 611(G)7798	INLET CI DES. 3 (2B)	1.000	EA
0330 611(H)0416	ADD'L DEPTH IN INLET CI DES. 2B	5.000	VF
0340 611(H)0418	ADD'L DEPTH IN INLET CI DES. 2(D)	3.000	VF
0350 611(H)0422	ADD'L DEPTH IN INLET CI DES. 3	2.000	VF
0360 611(H)0424	ADD'L DEPTH IN INLET CI DES. 3B	4.000	VF
0370 611(H)0426	ADD'L DEPTH IN INLET CI DES. 3D	8.000	VF
0380 611(H)0856	ADD'L DEPTH IN INLET W/LJB, CI, DES. 3(2B)	1.000	VF
0390 612(A)3200	MANHOLES ADJUST TO GRADE	9.000	EA
0400 612(C)3400	INLET ADJUST TO GRADE	3.000	EA
0410 612(E)3600	VALVE BOXES ADJUST TO GRADE	7.000	EA
0420 613(A)5204	15" R.C.PIPES CLASS III	30.000	LF
0430 613(A)5208	18" R.C.PIPES CLASS III	45.000	LF
0440 613(A)5216	24" R.C.PIPES CLASS III	15.000	LF
0450 613(J)6400	EDGE DRAIN CONDUIT-PERFORATED	931.000	LF
0460 616 2120	(PL) SPRINKLER SYSTEM IMPROVEMENTS	1.000	LSUM

Proposal:260319
J/P Num:34731(04)
Counties:TULSA

Let Date:October 15, 2026
Proj. Num:STP-272N(444)IG

Call Order:172

Description:INTERSECTION MODIFICATION
CITY STREETS (SHERIDAN RD): AT THE INTERSECTION OF 71ST ST,
2.38 MILES NORTH OF SH-364 IN THE CITY OF TULSA.
PROJECT LENGTH = 0.468 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001 ROADWAY			
0470 619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0480 619(B)6360	REMOVAL OF CONCRETE PAVEMENT	18,016.000	SY
0490 619(B)6364	REMOVAL OF ASPHALT PAVEMENT	1,492.000	SY
0500 619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	406.000	SY
0510 619(B)6400	REMOVAL OF CURB	3,063.000	LF
0520 619(B)6404	REMOVAL OF SIDEWALK	566.000	SY
0530 619(B)6416	REMOVAL OF CONCRETE MEDIAN BARRIER	1,888.000	LF
0540 619(C)6600	SAWING PAVEMENT	850.000	LF
0002 TRAFFIC CONTROL			
0550 805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	21.000	EA
0560 850(A)1200	SHEET ALUMINUM SIGNS	174.000	SF
0570 851(C)2405	1 1/2" SQUARE TUBE POST	3.000	LF
0580 851(C)2410	1 3/4" SQUARE TUBE POST	200.000	LF
0590 851(C)2415	2" SQUARE TUBE POST	38.000	LF
0600 857(C)9405	REMOVABLE PAVEMENT MARKING TAPE(6" WIDE)	15,257.000	LF
0610 857(E)9600	(PL)CONSTRUCTION ZONE PAVEMENT MARKERS	240.000	EA
0620 857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAFF.STRP)	1,979.000	LF
0630 880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	6,350.000	SD
0640 880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	8,730.000	SD
0650 880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	360.000	SD
0660 880(B)6350	(SP) BUSINESS ACCESS SIGNS	2,210.000	SD
0670 880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	13,450.000	SD
0680 880(E)6600	WARNING LIGHTS(TYPE A)	6,100.000	SD
0690 880(F)6700	DRUMS	151,200.000	SD
0700 880(G)6805	CHANNELIZER CONES	12,230.000	SD
0710 880(I)7000	FLAGGER	85.000	SD
0720 882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	748.000	SD
0003 SIGNING AND STRIPING			
0730 855(A)7201	(SP) TRAFFIC STRIPE(PLASTIC)(4" WIDE)	9,123.000	LF
0740 855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	957.000	LF
0750 855(B)7305	(SP) TRAFFIC STRIPE(PLASTIC)(ARROWS)	35.000	EA

Proposal:260319
J/P Num:34731(04)
Counties:TULSA

Let Date:October 15, 2026
Proj. Num:STP-272N(444)IG

Call Order:172

Description:INTERSECTION MODIFICATION
CITY STREETS (SHERIDAN RD): AT THE INTERSECTION OF 71ST ST,
2.38 MILES NORTH OF SH-364 IN THE CITY OF TULSA.
PROJECT LENGTH = 0.468 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0004 TRAFFIC SIGNALS			
0760 802(B)0324	2" PVC SCH.40 PLASTIC CONDUIT TRENCHED	40.000	LF
0770 802(B)0332	3" PVC SCH.40 PLASTIC CONDUIT TRENCHED	100.000	LF
0780 802(C)0435	3" HIGH DENSITY PE PIPE - BORED	490.000	LF
0790 803(A)1210	PULL BOX(SIZE I)	3.000	EA
0800 803(A)1220	PULL BOX(SIZE II)	1.000	EA
0810 804(A)2200	STRUCTURAL CONCRETE	24.900	CY
0820 804(B)2300	REINFORCING STEEL	3,839.780	LB
0830 805(A)3256	(PL)REMOVAL OF TRAFFIC SIGNAL EQUIPMENT	1.000	LSUM
0840 806(A)4332	POLE & 50' TS MST.ARM(G.STL.)	2.000	EA
0850 806(A)4340	POLE & 70' TS MST.ARM(G.STL.)	2.000	EA
0860 806(B)4408	10' MTG.HT.TS PED.POLE(G.STL.)	4.000	EA
0870 809(A)7200	ROADWAY LUMINAIRE	2.000	EA
0880 810(A)8200	SERVICE POLE	1.000	EA
0890 811 9160	2/C NO.12 ELECT.COND.	600.000	LF
0900 823 6110	(SP)TRAFFIC SIGNAL SPAN WIRE EQUIPMENT	1.000	LSUM
0910 823 6120	WIRELESS SIGNAL COMMUNICATION SYSTEM	1.000	EA
0920 825 8100	TRAFFIC SIGNAL CONTROLLER ASSEMBLY	1.000	EA
0930 828 0100	(PL)DETECTION SYSTEM (VIDEO)	1.000	LSUM
0940 830 2100	PEDESTRIAN PUSH BUTTON	8.000	EA
0950 831 3116	1WAY2SEC.ADJ.PED.SIG.HD.S-20	8.000	EA
0960 831 3120	1WAY3SEC.ADJ.SIG.HD.S-6	10.000	EA
0970 831 3124	1WAY3SEC.ADJ.SIG.HD.S-9	4.000	EA
0980 831 3156	1WAY5SEC.ADJ.SIG.HD.S-19	4.000	EA
0990 834(A)6205	5/C TRAFFIC SIGNAL ELECTRICAL CABLE	175.000	LF
1000 834(A)6210	7/C TRAFFIC SIGNAL ELECTRICAL CABLE	1,790.000	LF
1010 834(A)6220	12/C TRAFFIC SIGNAL ELECTRICAL CABLE	650.000	LF
1020 834(A)6225	15/C TRAFFIC SIGNAL ELECTRICAL CABLE	525.000	LF
1030 834(A)6235	21/C TRAFFIC SIGNAL ELECTRICAL CABLE	650.000	LF
1040 834(B)6300	2/C SHIELDED LOOP DETECTOR LEAD-IN CABLE	135.000	LF
1050 834(C)6410	UNDERGROUND COMMUNICATION CABLE	320.000	LF
1060 840(B)0300	E.P.S. OPTICAL DETECTOR	4.000	EA
1070 840(C)0400	E.P.S. OPTICAL DETECTOR CABLE	860.000	LF
1080 840(D)0500	E.P.S. 2 CHANNEL PHASE SELECTOR	2.000	EA
1090 850(C)1400	MAST ARM MOUNTED SIGNS(ALUM.)	58.000	SF
0005 STAKING			
1100 642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM
0006 CONSTRUCTION			
1110 220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
1120 641 2110	MOBILIZATION	1.000	LSUM