

Proposal:260320**Let Date:**November 19, 2026**Call Order:**053**J/P Num:**39589(04)**Proj. Num:**SNL-27B-S**Counties:**POTTAWATOMIE

Description:SHAWNEE REGIONAL AIRPORT - SE TAXILANE FUTURE DEVELOPMENT
 CONSTRUCT TAXILANE FOR FUTURE HANGAR DEVELOPMENT
 IN THE CITY OF SHAWNEE.
 PROJECT LENGTH = 0.00 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0001	Taxilane Construction		
0010	C-102-005 Temporary Erosion Control	1.000	LSUM
0020	C-102-010 Temporary Seeding	3.000	AC
0030	C-102-015 Permanent Transition Mat	2,400.000	SF
0040	D-701-001 Storm Pipe	174.000	LF
0050	D-701-002 RCP End Section	3.000	EA
0060	D-701-003 Concrete End Section Treatment	3.000	EA
0070	D-705-005 Conventional Underdrain	560.000	LF
0080	D-705-015 Underdrain Cleanout Riser	2.000	EA
0090	D-751-001 Junction Box	1.000	EA
0100	L-108-005 Install Cable in Duct	2,350.000	LF
0110	L-108-010 Bare Counterpoise Wire	2,080.000	LF
0120	L-110-100 2" Electrical Duct and Trench (Native Soil)	2,200.000	LF
0130	L-110-201 2-Way, 2" PVC Schedule 40, Concrete Encased Electrical Duct	80.000	LF
0140	L-125-135 L-861T LED Taxiway Edge Light on New Base	24.000	EA
0150	L-125-150 L-853 (L) Solar Powered Taxiway Centerline Light	2.000	EA
0160	ODOT-303 Aggregate Base	1,050.000	SY
0170	ODOT-303 Aggregate Base	3,900.000	SY
0180	ODOT-411 Asphalt Pavement	305.000	TON
0190	ODOT-414 Concrete Pavement	3,740.000	SY
0200	P-101-005 Pavement and Base Removal	1,050.000	SY
0210	P-101-009 Saw Cut	565.000	LF
0220	P-101-025 Remove Electrical Systems	1.000	LSUM
0230	P-101-026 Remove, Store, and Reinstall Light	12.000	EA
0240	P-101-030 Pavement Marking Removal	460.000	SF
0250	P-101-050 Remove Storm Structures	1.000	LSUM
0260	P-152-020 Embankment in Place	4,600.000	CY
0270	P-152-025 Unsuitable Subgrade Removal & Replacement	460.000	CY
0280	P-156-001 Cement for Subgrade Treatment	100.000	TON
0290	P-156-050 8" Treated Subgrade	4,950.000	SY
0300	P-602-001 Prime Coat	350.000	GAL
0310	P-603-001 Tack Coat	85.000	GAL
0320	T-901-002 Seeding	3.000	AC
0330	T-904-005 Sodding	2,100.000	SY
0340	T-908-001 Mulching	3.000	AC

Proposal:260320**Let Date:**November 19, 2026**Call Order:**053**J/P Num:**39589(04)**Proj. Num:**SNL-27B-S**Counties:**POTTAWATOMIE

Description:SHAWNEE REGIONAL AIRPORT - SE TAXILANE FUTURE DEVELOPMENT
 CONSTRUCT TAXILANE FOR FUTURE HANGAR DEVELOPMENT
 IN THE CITY OF SHAWNEE.
 PROJECT LENGTH = 0.00 MILES

<u>Line #</u>	<u>Item Description</u>	<u>Quantity</u>	<u>Unit</u>
0002	Add Alternate 1 - Construct Additional Taxilane Pavement		
0350 C-100-001	Contractor Quality Control Program (CQCP)	1.000	LSUM
0360 C-102-005	Temporary Erosion Control	1.000	LSUM
0370 C-102-010	Temporary Seeding	3.000	AC
0380 C-102-015	Permanent Transition Mat	4,000.000	SF
0390 C-105-001	Mobilization	1.000	LSUM
0400 D-701-003	Concrete End Section Treatment	2.000	EA
0410 D-701-004	RCP Arch Pipe	109.000	LF
0420 D-701-005	RCP Arch Pipe End Section	2.000	EA
0430 D-705-005	Conventional Underdrain	740.000	LF
0440 D-705-010	Non-Perforated Outlet Pipe	30.000	LF
0450 D-705-015	Underdrain Cleanout Riser	2.000	EA
0460 D-705-020	Splash Pad	1.000	EA
0470 ODOT-303	Aggregate Base	3,100.000	SY
0480 ODOT-414	Concrete Pavement	2,950.000	SY
0490 P-152-010	Unclassified Excavation	20,610.000	CY
0500 P-152-025	Unsuitable Subgrade Removal & Replacement	1,601.000	CY
0510 P-156-001	Cement for Subgrade Treatment	65.000	TON
0520 P-156-050	8" Treated Subgrade	3,100.000	SY
0530 P-620-015	Reflectorized Pavement Marking	380.000	SF
0540 P-620-016	Non-Reflectorized Pavement Marking	755.000	SF
0550 T-901-002	Seeding	3.000	AC
0560 T-904-005	Sodding	2,050.000	SY
0570 T-908-001	Mulching	3.000	AC
0580 TEMP-001	Temporary Marking, Lighting & Barricades	1.000	LSUM
0003	Striping		
0590 P-620-015	Reflectorized Pavement Marking	620.000	SF
0600 P-620-016	Non-Reflectorized Pavement Marking	1,240.000	SF
0004	Temporary Traffic Control		
0610 TEMP-001	Temporary Marking, Lighting & Barricades	1.000	LSUM
0005	Construction		
0620 C-100-001	Contractor Quality Control Program (CQCP)	1.000	LSUM
0630 C-105-001	Mobilization	1.000	LSUM