Proposal: 270002 **Let Date:** January 14, 2027 **Call Order:** 502
J/P Num: 34264(04) **Proj. Num:** SBR-017N(307)SB
Counties: BEAVER
Description: BRIDGE REHABILITATION
US-270: OVER UNNAMED CREEK, 7.00 MILES EAST OF THE SH-23 INTERSECTION NEAR ELMWOOD.
PROJECT LENGTH = 0.144 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	205(A)6200	TYPE A-SALVAGED TOPSOIL	1.000	LSUM
0020	221(B)2300	TEMPORARY SILT FENCE	1,100.000	LF
0030	230(A)7200	SOLID SLAB SODDING	1,010.000	SY
0040	407(B)7300	TACK COAT	40.000	GAL
0050	411(B)1330	SUPERPAVE, TYPE S3(PG 64-22 OK)	88.000	TON
0060	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	59.000	TON
0070	412 3100	COLD MILLING PAVEMENT	3,779.000	SY
0080	619(B)6396	REMOVAL OF GUARDRAIL	600.000	LF
0090	619(C)6600	SAWING PAVEMENT	1,178.000	LF
0002	BRIDGE "A"			
0100	504(A)5200	APPROACH SLAB	256.000	SY
0110	504(B)5300	SAW-CUT GROOVING	880.000	SY
0120	504(D)5420	CONCRETE RAIL (TR4)	265.000	LF
0130	509(A)0210	CLASS AA CONCRETE	151.600	CY
0140	509(D)0510	CLASS C CONCRETE	10.000	CY
0150	511 2100	MECHANICAL SPLICES	354.000	EA
0160	511(B)2310	EPOXY COATED REINFORCING STEEL	35,480.000	LB
0170	515(A)7200	WATER REPELLENT (VISUALLY INSPECTED)	756.400	SY
0180	517 9110	ELASTOMERIC COATING	404.000	SF
0190	520(A)1200	PREPARATION OF CRACKS, ABOVE WATER	60.000	LF
0200	520(C)1400	EPOXY RESIN, ABOVE WATER	1.000	GAL
0210	521(A)2200	PNEUMATICALLY PLACED MORTAR	5.000	SY
0220	523(A)3200	SEALER CRACK PREPARATION	101.500	LF
0230	523(B)3300	SEALER RESIN	1.200	GAL
0240	524(A)4200	(SP) CARBON FIBER-REINFORCED POLYMER	60.000	SF
0250	535 7100	CORROSION INHIBITOR(SURFACE APPLIED)	5.000	SY
0260	619(B)6304	REMOVAL OF BRIDGE ITEMS	1.000	LSUM
0003	TRAFFIC SIGNING AND STRIPING			
0270	853 5115	DELINEATORS(TYPE 2, CODE 1)	18.000	EA
0280	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	12,326.000	LF
0004	TRAFFIC SAFETY			
0290	623 1100	(PL)GUARDRAIL CURBING	4.000	EA
0300	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	450.000	LF
0310	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0320	623(I)2050	GUARDRAIL BRIDGE CONN-THRIE BEAM (31")	4.000	EA

Proposal:270002 **Let Date:**January 14, 2027 **Call Order:**502
J/P Num:34264(04) **Proj. Num:**SBR-017N(307)SB
Counties:BEAVER
Description:BRIDGE REHABILITATION
US-270: OVER UNNAMED CREEK, 7.00 MILES EAST OF THE SH-23 INTERSECTION NEAR ELMWOOD.
PROJECT LENGTH = 0.144 MILES

Line #		Item Description	Quantity	Unit
0005	TRAFFIC CONTROL			
0330	857(A)9200	CONSTRUCTION TRAFFIC STR.(PAINT)(4" WIDE)	6,000.000	LF
0340	857(E)9630	(PL)CONST.ZONE PAV.MKRS(FLEX TAB)TYP.2-2	2,000.000	EA
0350	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	12,326.000	LF
0360	871(B)2300	CONST.ZONE IMPACT ATTEN.	240.000	SD
0370	877(B)4300	DELIVER PORTABLE LONGITUDINAL BARRIER	825.000	LF
0380	877(C)4400	RELOCATION OF PORT. LONGITUDINAL BARRIER	825.000	LF
0390	880(A)6220	ARROW DISPLAY(TYPE C)	450.000	SD
0400	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	2,475.000	SD
0410	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	3,375.000	SD
0420	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	3,150.000	SD
0430	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	1,575.000	SD
0440	880(E)6600	WARNING LIGHTS(TYPE A)	5,400.000	SD
0450	880(F)6700	DRUMS	25,650.000	SD
0460	880(G)6805	CHANNELIZER CONES	3,375.000	SD
0470	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	478.000	SD
0006	CONSTRUCTION			
0480	641 2100	MOBILIZATION	1.000	LSUM