Proposal:270012 **Let Date:**January 14, 2027 **Call Order:**529
J/P Num:35860(04) **Proj. Num:**STP-225B(127)AD
Counties:GARVIN
Description:PEDESTRIAN AND SIDEWALK IMPROVEMENTS
SH-19: FROM 0.1 MILES WEST OF THE US-177 JUNCTION,
EXTEND EAST IN THE TOWN OF STRATFORD.
PROJECT LENGTH = 1.32 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	100.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	100.000	CY
0030	221(B)2300	TEMPORARY SILT FENCE	10,000.000	LF
0040	221(G)2800	TEMPORARY FIBER LOG	500.000	LF
0050	230(A)7200	SOLID SLAB SODDING	3,333.000	SY
0060	303(A)1200	AGGREGATE BASE TYPE A	563.000	CY
0070	325 0100	SEPARATOR FABRIC	500.000	SY
0080	326(B)1300	GEOGRID REINFORCEMENT	500.000	SY
0090	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	29.000	TON
0100	411(C)1430	SUPERPAVE, TYPE S4(PG 64-22 OK)	149.000	TON
0110	412 3100	COLD MILLING PAVEMENT	593.000	SY
0120	414(F)5700	PARTIAL DEPTH P.C.C. PATCH (PLACEMENT)	1,327.000	SY
0130	414(G)5800	P.C. CONCRETE FOR PAVEMENT	221.000	CY
0140	509(C)0400	CLASS A CONCRETE, SMALL STRUCTURES	5.000	CY
0150	510(A)1230	BLOCK RETAINING WALL & CAP	240.000	SF
0160	609(A)4230	CONC.CURB(6" BARRIER-INTEGRAL)	1,168.000	LF
0170	610(A)5200	4" CONCRETE SIDEWALK	3,925.000	SY
0180	610(B)5300	6" CONCRETE DRIVEWAY (H.E.S.)	1,780.000	SY
0190	610(I)6000	TACTILE WARNING DEVICE-NEW	925.000	SF
0200	612(A)3200	MANHOLES ADJUST TO GRADE	2.000	EA
0210	619(A)6200	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.000	LSUM
0220	619(B)6352	REMOVAL OF FENCE	7.000	LF
0230	619(B)6356	REMOVAL OF CURB AND GUTTER	1,120.000	LF
0240	619(B)6364	REMOVAL OF ASPHALT PAVEMENT	707.000	SY
0250	619(B)6380	REMOVAL OF CONCRETE DRIVEWAY	769.700	SY
0260	619(B)6384	REMOVAL OF ASPHALT DRIVEWAY	597.000	SY
0270	619(B)6404	REMOVAL OF SIDEWALK	374.200	SY
0280	622(A)0200	PIPE RAILING	108.000	LF
0290	632 0100	(PL) SITESCAPING	1.000	LSUM
0002	TRAFFIC			
0300	805(A)3252	(PL)REMOVAL OF EXISTING SIGNS	31.000	EA
0310	805(D)3528	(PL)REMOVE & RESET EXISTING SIGNS	15.000	EA
0320	836 7110	RECTANGULAR RAPID FLASHING BEACON	4.000	EA
0330	850(A)1200	SHEET ALUMINUM SIGNS	174.000	SF
0340	851(C)2415	2" SQUARE TUBE POST	372.000	LF
0350	855(A)7217	(SP) TRAFFIC STRIPE(PLASTIC)(24" WIDE)	2,126.000	LF
0360	857(F)9700	PAVEMENT MRKNG.REMOVAL(TRAF.STRP)	144.000	LF
0370	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	700.000	SD
0380	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	500.000	SD
0390	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	360.000	SD
0400	880(E)6600	WARNING LIGHTS(TYPE A)	3,000.000	SD
0410	880(F)6700	DRUMS	3,000.000	SD
0003	STAKING			
0420	642(B)3300	CONSTRUCTION STAKING LEVEL II	1.000	LSUM

Proposal: 270012 **Let Date:** January 14, 2027 **Call Order:** 529
J/P Num: 35860(04) **Proj. Num:** STP-225B(127)AD
Counties: GARVIN
Description: PEDESTRIAN AND SIDEWALK IMPROVEMENTS
SH-19: FROM 0.1 MILES WEST OF THE US-177 JUNCTION,
EXTEND EAST IN THE TOWN OF STRATFORD.
PROJECT LENGTH = 1.32 MILES

Line #		Item Description	Quantity	Unit
0004	CONSTRUCTION			
0430	220 1100	SWPPP DOCUMENTATION AND MANAGEMENT	1.000	LSUM
0440	641 2100	MOBILIZATION	1.000	LSUM