Proposal: 270014 **Let Date:** January 14, 2027 **Call Order:** 535
J/P Num: 38397(04) **Proj. Num:** SSR-235C(104)SR
Counties: JOHNSTON
Description: RESURFACE (ASPHALT)
SH-22: FROM THE JUNCTION OF SH-99,
EXTEND WEST NEAR RAVIA.
PROJECT LENGTH = 3.13 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	202(A)2200	UNCLASSIFIED EXCAVATION	200.000	CY
0020	202(D)2500	UNCLASSIFIED BORROW	638.000	CY
0030	402(A)2200	TRAFFIC BOUND SURFACE COURSE TYPE A	460.000	TON
0040	407(B)7300	TACK COAT	12,882.000	GAL
0050	411(L)2444	BMD, TYPE B5 (PG 64-22 OK)	9,026.000	TON
0060	412 3100	COLD MILLING PAVEMENT	2,864.000	SY
0070	619(B)6396	REMOVAL OF GUARDRAIL	400.000	LF
0080	623(A)1200	BEAM GUARDRAIL W-BEAM SINGLE	200.000	LF
0090	623(G)1820	GUARDRAIL END TREATMENT (31")	4.000	EA
0002	TRAFFIC			
0100	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	15,840.000	LF
0110	413(B)4310	RUMBLE STRIP-METHOD HMA-CYC	31,680.000	LF
0120	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	49,579.000	LF
0130	856(A)8211	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(8" WIDE)	1,200.000	LF
0140	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	216.000	LF
0150	856(B)8303	(SP) TRAF.STR.(PLURAL-COMPONENT)(SYM,WRD,ETC)	1.000	EA
0160	858(A)0228	PAVE.MARKERS CLASS A TYPE 2-D	206.000	EA
0170	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	1,030.000	SD
0180	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	890.000	SD
0190	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	1,294.000	SD
0200	880(E)6607	WARNING LIGHTS(TYPE B)	515.000	SD
0210	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	84.000	SD