**Proposal:**270015 **Let Date:**January 14, 2027 **Call Order:**540
**J/P Num:**39342(04) **Proj. Num:**HSIPG-249B(097)TR
**Counties:**MAYES
**Description:**INTERSECTION MODIFICATION
SH-20: AT THE INTERSECTION OF COUNTY ROAD (NS-435),
3.6 MILES EAST OF THE US-69 JUNCTION NEAR PRYOR.
PROJECT LENGTH = 0.642 MILES

| Line # | | Item Description | Quantity | Unit |
|---|---|---|---|---|
| **0001** | TRAFFIC SIGNING | | | |
| 0010 | 805(A)3252 | (PL)REMOVAL OF EXISTING SIGNS | 4.000 | EA |
| 0020 | 805(D)3528 | (PL)REMOVE & RESET EXISTING SIGNS | 2.000 | EA |
| 0030 | 850(A)1200 | SHEET ALUMINUM SIGNS | 250.000 | SF |
| 0040 | 851(C)2430 | 2 1/2" SQUARE TUBE POST | 240.000 | LF |
| 0050 | 853 5135 | DELINEATORS(TYPE 1, CODE 2, FLEXIBLE) | 231.000 | EA |
| 0060 | 856(A)8207 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE) | 11,309.000 | LF |
| 0070 | 856(A)8219 | (SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE) | 77.000 | LF |
| 0080 | 856(B)8307 | (SP) TRAFFIC STRIPE(PLURAL-COMP)(ARROWS) | 5.000 | EA |
| 0090 | 857(F)9700 | PAVEMENT MRKNG.REMOVAL(TRAF.STRP) | 6,249.000 | LF |
| **0002** | TRAFFIC CONTROL | | | |
| 0100 | 876(A)3210 | (PL)TRUCK MOUNTED ATTENUATOR | 14.000 | SD |
| 0110 | 880(B)6300 | CONSTRUCTION SIGNS 0 TO 6.25 SF | 266.000 | SD |
| 0120 | 880(B)6310 | CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF | 452.000 | SD |
| 0130 | 880(B)6320 | CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF | 190.000 | SD |
| 0140 | 880(C)6410 | CONSTRUCTION BARRICADES(TYPE III) | 28.000 | SD |
| 0150 | 880(E)6600 | WARNING LIGHTS(TYPE A) | 154.000 | SD |
| 0160 | 880(E)6610 | WARNING LIGHTS(TYPE C) | 1,262.000 | SD |
| 0170 | 880(F)6700 | DRUMS | 1,262.000 | SD |
| 0180 | 880(G)6805 | CHANNELIZER CONES | 360.000 | SD |
| 0190 | 880(I)7000 | FLAGGER | 7.000 | SD |
| 0200 | 882(A)8210 | PORT.CHANGEABLE MESSAGE SIGN | 42.000 | SD |
| **0003** | TRAFFIC SAFETY | | | |
| 0210 | 413(B)4300 | RUMBLE STRIP-METHOD HMA-CYC GROUP | 6.000 | EAGP |
| **0004** | STAKING | | | |
| 0220 | 642(B)3300 | CONSTRUCTION STAKING LEVEL II | 1.000 | LSUM |
| **0005** | CONSTRUCTION | | | |
| 0230 | 641 2110 | MOBILIZATION | 1.000 | LSUM |