Proposal:270021 **Let Date:**January 14, 2027 **Call Order:**565
J/P Num:36174(04) **Proj. Num:**SSR-259C(094)SR
Counties:NOBLE, PAWNEE
Description:RESURFACE (ASPHALT)
SH-15: FROM THE INTERSECTION OF US-177, EXTEND EAST NEAR PAWNEE.
PROJECT LENGTH = 7.58 MILES

Line #		Item Description	Quantity	Unit
0001	ROADWAY			
0010	303(A)1200	AGGREGATE BASE TYPE A	1,344.000	CY
0020	402(E)2600	TRAFFIC BOUND SURFACE COURSE TYPE E	1,749.000	TON
0030	407(C)7500	NT TACK MATERIAL	7,246.000	GAL
0040	411(H)1900	SUPERPAVE, TYPE S3(PATCH)(PG64-22OK)	1,008.000	TON
0050	411(L)2428	BMD, TYPE B4 (PG 70-28 OK)	12,443.000	TON
0060	412 3100	COLD MILLING PAVEMENT	49,425.000	SY
0002	TRAFFIC			
0070	413(A)4210	RUMBLE STRIP-CENTERLINE HMA-CON	40,000.000	LF
0080	856(A)8207	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(6" WIDE)	126,900.000	LF
0090	856(A)8219	(SP) TRAFFIC STRIPE(PLURAL-COMPONENT)(24" WIDE)	84.000	LF
0100	880(A)6220	ARROW DISPLAY(TYPE C)	17.000	SD
0110	880(B)6300	CONSTRUCTION SIGNS 0 TO 6.25 SF	360.000	SD
0120	880(B)6310	CONSTRUCTION SIGNS 6.26 SF TO 15.99 SF	350.000	SD
0130	880(B)6320	CONSTRUCTION SIGNS 16.0 SF TO 32.99 SF	887.000	SD
0140	880(C)6410	CONSTRUCTION BARRICADES(TYPE III)	160.000	SD
0150	880(E)6607	WARNING LIGHTS(TYPE B)	887.000	SD
0160	880(G)6805	CHANNELIZER CONES	2,707.000	SD
0170	880(I)7000	FLAGGER	32.000	SD
0180	882(A)8210	PORT.CHANGEABLE MESSAGE SIGN	104.000	SD
0003	CONSTRUCTION			
0190	641 2110	MOBILIZATION	1.000	LSUM